



KEYNOTES

CEILING SYMBOL LEGEND

| SYMBOL | DESCRIPTION | SYMBOL | DESCRIPTION |
|----------|------------------------------------|----------|--|
| [Symbol] | GYPSUM BOARD / SUSPENDED SOFFIT | [Symbol] | FLOURESCENT LIGHT FIXTURE: 24" X 48" |
| [Symbol] | PLASTER | [Symbol] | FLOURESCENT LIGHT FIXTURE: 12" X 48" |
| [Symbol] | ACOUSTICAL CEILING TILE: 12" X 12" | [Symbol] | FLOURESCENT LIGHT FIXTURE: STRIP |
| [Symbol] | ACOUSTICAL CEILING TILE: 24" X 24" | [Symbol] | LIGHT FIXTURES : 24"x24" FLOOR, 12"x12" INCAN. |
| [Symbol] | ACOUSTICAL CEILING TILE: 24" X 48" | [Symbol] | SPECULAR CEILING GRID: 1" X 1" WITH FLOR. LGTS. |
| [Symbol] | ACCESS PANEL: 24" X 24" : U.O.N. | [Symbol] | DOWN LIGHT FIXTURES: A SPOT BUDON, CIBUL WISHER, DSDONCE |
| [Symbol] | EXPOSED METAL | [Symbol] | EXIT LIGHT FIXTURE |
| | | [Symbol] | LIGHT TRACK FIXTURE |
| | | [Symbol] | EMERGENCY LIGHT FIXTURE |
| | | [Symbol] | SPRINKLER HEAD |
| | | [Symbol] | MECHANICAL DIFFUSER: SUPPLY |
| | | [Symbol] | MECHANICAL DIFFUSER: RETURN |

ROOM SCHEDULE

| RM. NO. | ROOM NAME | RM. NO. | ROOM NAME |
|--------------------------------------|---|---------|-----------|
| 153E 153F | WOMEN'S TOILET MEN'S TOILET | | |
| 154A 154B 154C 154D 154E | OPEN OFFICE OFFICE KITCHENETTE CONFERENCE ROOM | | |
| 155 155A 155B | VESTIBULE MAINTENANCE OFFICE AREA MAINTENANCE WORKSHOP/STORAGE AREA | | |

GENERAL NOTES

- REFER TO DRAWING G001 FOR PROJECT GENERAL NOTES.
- REFER TO DRAWING G003 FOR KEYNOTE DESCRIPTIONS NOT APPEARING ON THIS DRAWING.
- REFER TO DRAWING A801, FINISH SCHEDULE, FOR CEILING HEIGHTS.
- COORDINATE FIRE RATED ASSEMBLIES INFORMATION CONTAINED ON DRAWING A301 WITH THE WORK OF ALL CONTRACTS INCLUDING MECHANICAL, PLUMBING, FIRE PROTECTION, ELECTRICAL AND LOW VOLTAGE TRADES.
- SPOT ELEVATIONS ARE DESIGNATED NOMINAL HEIGHTS ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE. COORDINATE FINAL HEIGHTS OF CEILING ELEMENTS WITH INFORMATION CONTAINED ON STRUCTURAL, MECHANICAL, PLUMBING, FIRE PROTECTION AND ELECTRICAL DRAWINGS.
- PROVIDE GYPSUM BOARD HEADERS TO FORM VERTICAL SOFFITS AT CHANGES OF ACOUSTICAL CEILING HEIGHTS UNLESS NOTED OR DETAILED OTHERWISE.
- INSTALL GYPSUM BOARD CONTROL JOINTS AT MAX. 24 FOOT CENTERS IN ALL CONTINUOUS GYPSUM BOARD WALL AND SOFFIT SURFACES THAT EXCEED 24 FEET IN LENGTH. SEE DETAIL #10 ON SHEET A901 FOR CONTROL JOINTS IN 1-HOUR RATED AND NON-RATED PARTITIONS.

KEY PLAN

| | | | | | | | | | | | |
|---------------------|--|---|--|---|--|--|--|------------------------------|--|--|--|
| CONSULTANTS: | | ARCHITECT/ENGINEERS: | | Drawing Title PARTIAL FIRST FLOOR REF. CEILING PLANS | | Project Title HINES BUILDING 37 O.I. AND T. FIELD OFFICES - PHASE 3 OFFICE AND RESTROOM RENOVATIONS | | Project Number 796-13-004 | | Office of Construction and Facilities Management Department of Veterans Affairs | |
| | | Kluber, Inc. 10 South Shumway Batavia, Illinois 60510 tel. 630.406.1213 fax 630.406.9472 www.kluberinc.com | | Approved: Project Director | | Location VA OFFICE OF ACQUISITION AND LOGISTICS HINES, ILLINOIS | | Building Number 37 | | | |
| | | | | | | Date 04-12-13 | | Checked CJH | | | |

100% CONSTRUCTION DOCUMENTS FOR BID
95% CONSTRUCTION DOCUMENTS SUBMITTAL
90% CONSTRUCTION DOCUMENTS SUBMITTAL
Revisions:

04-12-13
03-12-13
02-09-13
Date

VA FORM 08-6231