



JLG Architects

Ryan M. Murphy, Assoc. AIA

214 Broadway

Fargo, ND 58102

p. 701.364.0237 f. 701.364.0228

rmurphy@jlgarchitects.com

Project Name: **Loading Dock Leveler Replacement**

Project Number: 11080C/437-13-119

June 17, 2013

## **Addendum No. 3**

### **NOTICE TO CONTRACTORS**

This Addendum is prepared to supplement information presented in the Drawings and Project Manual dated May 17, 2013 for the above referenced project. All additions, changes, omissions and conditions listed herein shall become an integral part of the Contract Documents.

### **SPECIFICATIONS**

N/A

### **DRAWINGS**

**Note: intent is to replace the perimeter top-angle and bottom sill angle at the "north" loading dock leveler only (shown in drawings: 1/AS101, 4/AS101 and 7/AS101). Vertical angles are to be installed at all leveler locations.**

#### **AS101 – ARCHITECTURAL PLAN**

1. Drawing 2/AS101: delete demolition keynotes #4 and #6, at all locations, in this drawing.
2. Drawing 3/AS101: delete demolition keynotes #4 and #6, at all locations, in this drawing.
3. Drawing 5/AS101: delete keynotes #6 and #12, at all locations, in this drawing.
4. Drawing 6/AS101: delete keynotes #6 and #12, at all locations, in this drawing.

#### **AS201 – ARCHITECTURAL ELEVATIONS, SECTIONS AND DETAILS**

1. Drawing 10/AS201 - Clarifications:
  - a. The top-most note which reads [3"X3"X1/4" STL. ANGLE-GALVANIZED] shall include the verbiage: "at north loading dock leveler location only."
  - b. The middle note which reads [3"X3"X1/4" ANGLE-GALVANIZED] shall include the verbiage: "at all loading dock leveler locations."
  - c. The note which reads [3"X3"X1/4" GALVANIZED BOTTOM SILL ANGLE] shall include the verbiage: "at the north loading dock leveler location only."

### **PROJECT NOTES**

Regarding the demolition and installation of new perimeter angles at the north-loading dock leveler location - it is the Contractor's option on the means of removal of the existing angle: angle grinder, torching, etc. It is the responsibility of the Contractor to determine the means and methods for demolition of existing angles at locations where the project is replacing this detail – ie: at north loading dock leveler. The specifications cover both the angles and cast-in-place concrete if concrete work is required.

### **END OF ADDENDUM NO. 3**