

Attachment #5

Table 1: Summary of Known and Potential Asbestos Containing Materials Related to Contract Work

Building	Level	Room	Material Description	Quantity	Abatement Needed	Notes
1	6	6E13	2" - 6" aircell pipe insulation	26 lf	Y	Piperuns are behind walls and above ceiling.
1	6	6E13	2" - 6" brown felt pipe insulation	-	P	None observed during spot check but if encountered must be removed.
1	10	10CE03	9" off white with black floor tile	108 sf	Y	May also be encountered under existing walls during wall demo.
1	10	10E12	Black cove base mastic	40 lf	Y	Same material present in 10E14C.
1	10	10E14C	Transite table top	196 sf	Y	Four laboratory table tops.
1	10	10E14C	9" off white with black floor tile	378 sf	Y	May also be encountered under existing walls to be removed during demo.
1	10	10E14C	2" - 6" aircell pipe insulation	34 lf	Y	Piperuns are above ceiling.
1	10	10E14C	Black cove base mastic	58 lf	Y	Same material present in 10E12.

Notes: Building, Level, room, and material description taken from VA provided 2007 Asbestos Survey. Applicable pages attached.

Quantities are estimates only, based on spot check, and contractor must perform it's own field measurements.

sf = square feet

lf = lineal feet

ftg = fittings

P = Potentially. Materials that are adjacent demolition areas may be impacted and contractor must review means and methods to determine if abatement will be required.

Y = Yes. Materials will require abatement. Note that some materials may not be readily visisble (i.e. behind walls).

Black cove base in 10E12 and 10E14C based on spot check. Lab report attached.