

ROOM FINISH LEGEND

FLOORING				
Key	Material	Manufacturer	Product Properties	Style/Color
SV-1	Sheet Vinyl	Armstrong or equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Rejuvenation Timberline/Cherry 37362 Rusty Cheeks or equal
SV-2	Sheet Vinyl	Armstrong or equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Rejuvenation StoneRun/Sidestar 34359 Penny or equal
SV-3	Sheet Vinyl	Armstrong or equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Rejuvenation StoneRun/Sidestar 34355 Uptown or equal
SV-4	Sheet Vinyl	Armstrong or equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Meditone - H831/Natural White or equal
SV-5	Sheet Vinyl	Armstrong or equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Meditone - H 8342/Terracotta or equal
SV-6	Sheet Vinyl	Armstrong or equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Meditone - H 8333/Tea Green or equal
SV-7	Sheet Vinyl	CBC Flooring/CERES or equal	0.080"/wear 0.022"	WELS Sheet-T10/Color: Salsa w/Salsa W/80 R60 for installation or equal
VCT-1	Vinyl Composition Tile	Armstrong or equal	BioStride polymer	Migrations BBT - T3512/Sandy Beige or equal
VCT-2	Vinyl Composition Tile	Armstrong or equal	7% recycled	Migrations BBT - T3511/Quartz or equal
T-1	Terrazzo Tile	Mats Inc./Floorazzo or equal	3/16" thick 2' X 2' panels, Fusion System	Gem Collection/Pearl or equal
T-2	Terrazzo Tile	Mats Inc./Floorazzo or equal	3/16" thick 2' X 2' panels, Fusion System	Gem Collection/Lovell VA #1 or equal
CPT-1	Carpet	Manning Commercial or equal	100% Antron Legacy Nylon 6.6 - Solution Dyed	Benchmark Carpet Tile - #7311 Merlot or equal
CT-1	Ceramic Tile	Crossville or equal	Porcelain -	Coto Americana 12x12 - AV173 RED or equal
TS-1	Transition Strip	Johnsonite or Equal	Slim line transitions - 5/8" exposed visual	STL-47-C - Color: Brown -47 (.080"x1/4" material) or equal
TS-2	Transition Strip	Schluter or Equal	Stainless Steel	Schiene-E -E45-3/16" or equal
TS-3	Transition Strip	Johnsonite or Equal	Slim line transitions - 5/8" exposed visual	STL-47-B - Color: Brown -47 (.080"x1/8" material) or equal
TS-4	Transition Strip	Johnsonite or Equal	Slim line transitions - 5/8" exposed visual	STL-47-A - Color: Brown -47 (1/4"x1/8" material) or equal
TS-5	Transition Strip	Johnsonite or Equal	Slim line transitions - 5/8" exposed visual	STL-47-F (Carpet to Ceramic Tile)
TS-6	Transition Strip	Schluter or Equal	Stainless Steel	Schiene-E -E30-3/16" or equal
TS-7	Transition Strip	Johnsonite or Equal	Reducer Strip	RRS-47-B-Color: Brown-47 (.080" to floor)
WALL BASE				
Key	Material	Manufacturer	Product Properties	Style/Color
VB-1	Vinyl Base	Johnsonite or equal	4' - 1/8" gauge - Thermoplastic Vinyl	Desert Camel - 19 or equal
VB-2	Vinyl Base	Johnsonite or equal	4' - 1/8" gauge - Thermoplastic Vinyl	Bone White W or equal
VB-3	Vinyl Base	Johnsonite or Equal	4' - 1/8" gauge - Thermoplastic Vinyl	Zen 474 or equal
FCB-2	Integral Flash Cove Former	Gradus or equal	PVC-u compound	CCF1001 - Almond or equal
FCB-3	Integral Flash Cove Base	Armstrong or Equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Meditone -H 8333 - Tea Green or equal
FCB-4	Integral Flash Cove Base	Armstrong or Equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Meditone - H 8342 - Terracotta or equal
FCB-5	Integral Base	Mats Inc./Floorazzo or Equal	3" or 3/16"H X 24"W X 24"D	Floorazzo - Gem/Pearl or equal
FCB-7	Floorazzo Base	Mats Inc./Floorazzo or Equal.	4"H X 24"W X 3/16"D	Floorazzo - Gem - Lovell VA #1 or equal
FCB-8	Integral Flash Cove Base	Armstrong or equal	0.080"/wear 0.022"/ UV-cured Polyurethane	Rejuvenation StoneRun/Sidestar 34359 Penny or equal
CTB-1	Ceramic Tile Base	Crossville or Equal	Porcelain	Coto Americana-4x12 - AV172 TAN or equal
WALL FINISH				
Key	Material	Manufacturer	Product Properties	Style/Color
PT-1	Paint	Benjamin Moore or Equal	#538 - Interior Egg Shell	Classic Colors- Eggshell - #1100 Sundial or equal
PT-2	Paint	Benjamin Moore or Equal	#538 - Interior Egg Shell	Classic Colors- Egg Shell - HC-73 - Plymouth Brown or equal
PT-3	Paint	Benjamin Moore or Equal	#538 - Interior Egg Shell - wall/soffit	Classic Colors- EggshellHC-49 Mayflower Red or equal
PT-4	Paint	Benjamin Moore or Equal	#538 - Interior Egg Shell - wall/soffit	Classic Colors- Eggshell #496 Chopped Dill or equal
PT-5	Paint	Benjamin Moore or Equal	#538 - Interior Egg Shell	Color Preview- Eggshell2159-40 Amber Waves or equal
PT-6	Paint	Benjamin Moore or Equal	V331-Corotech Acrylic DTM - Walls & HM-OR/ENDO	Color Preview - Epoxy - OC-97 Cream Froth or equal
PT-7	Paint	Benjamin Moore or Equal	#793 - Interior Alkyd - Semi-Gloss- for HM - GI/ON	Classic Colors - Fennel Seed - 1101 or equal
PT-8	Paint	Benjamin Moore or Equal	#536 - Interior Flat Finish- soffit/ceiling	Classic Colors- Flat-Super White or equal
PT-9	Paint	Benjamin Moore or Equal	V331-Corotech Acrylic DTM - Ceiling- OR/ENDO	Classic Colors- White - INT. RM. or equal
W-2	Terrazzo Tile	Mats Inc. or Equal	3/16" thick 2' X 2' panels	Floorazzo - Gem - Pearl or equal
CT-2	Ceramic Tile	Crossville or Equal	Porcelain	Coto Americana - AV172 TAN - 12 x 12 - or equal
CT-3	Ceramic Tile	Crossville or equal	Porcelain	Color Blx Too - 6x12 CRVA117 2612 - or equal
CT-4	Ceramic Tile	Crossville or Equal	Porcelain	Color Blx Too- 6x12 - A1112 Mr. Green Jeans or equal
CT-5	Ceramic Tile	Crossville or equal	Porcelain	Color Blx Too- 6x12 - A1113 BlueSuedeShoes or equal
WALL PROTECTION				
Key	Material	Manufacturer	Product Properties	Style/Color
WP-1	High Impact Wallcovering	C/S ACROVYN or equal	Engineered PETG	.060" Acrovyn 4000-Yosemite Sand #310 or equal
WP-2	High Impact Wallcovering	C/S ACROVYN or equal	Engineered PETG	.060" Acrovyn 4000 - Parchment #253 or equal
WP-3	High Impact Wallcovering	InPro	Engineered PETG	.060" Rigid Sheets - Cinnabar 0257 or equal
WP-4	Handrails	C/S ACROVYN or equal	Vinyl acrylic resin/ shock modifiers/fire retardant/UV stabilizer	HRB-10CN - Yosemite Sand #310 - or equal
WP-5	Bumper Guards	C/S ACROVYN or equal	Vinyl acrylic resin/ shock modifiers/fire retardant/UV stabilizer	SCR-50N - Yosemite Sand #310 or equal
WP-6	Corner Guard	C/S ACROVYN or equal	Vinyl acrylic resin/ shock modifiers/fire retardant/UV stabilizer	Full Height Flush Mounted - FS-10N-Yosemite Sand #310 or equal
WP-7	Corner Guard	C/S ACROVYN or equal	Vinyl acrylic resin/ shock modifiers/fire retardant/UV stabilizer	Full Height Surface Mounted - SM-10N-Parchment #253 or equal
WP-8	Corner Guard	C/S ACROVYN or equal	Vinyl acrylic resin/ shock modifiers/fire retardant/UV stabilizer	Full Height Surface Mounted - SM20MN-Yosemite Sand #310 or equal
WP-9	Handrails	C/S ACROVYN or equal	Vinyl acrylic resin/ shock modifiers/fire retardant/UV stabilizer	HRB-4CN-Parchment #253 - or equal
WP-10	Bumper Guards	C/S ACROVYN or equal	Vinyl acrylic resin/ shock modifiers/fire retardant/UV stabilizer	SCR-40N-Parchment#253 - or equal
WC-1	Wall Covering/Panels	Carnegie or equal	100% IFR Xrel	Xrel - Meteor - 6427 W713 - or equal
WC-2	Wainscot Cap	Schluter or Equal	Stainless Steel	Rondec-E -R045E - 3/16" - Stainless Steel or equal
MILLWORK SURFACE				
Key	Material	Manufacturer	Product Properties	Style/Color
PL-1	Plastic Laminate	Wilsonart or equal	60 Finish	Spiced Zephr -4859-60 - Base and Upper Cabinets or equal
PL-2	Plastic Laminate	Wilsonart Compact Laminate or equal	1/2" thick/Class B/2 fire rating/60 Finish	Amber Cherry -7919K-12-Accent wall panels waitg rms or equal
SS-1	Solid Surface	Silestone or equal	Non-porous, dense, scratch/shock resistance /anti-microbial built-in	Zynite-Waiting/Reception/Nurses Station or equal
SS-2	Solid Surface	Silestone or equal	Non-porous, dense, scratch/shock resistance /anti-microbial built-in	Bamboo (08)-Exam/Infusion/Lounge or equal
SS-3	Not Used			
SS-4	Solid Surface	3Form or equal	1/2" Stucco finish on face/Patent on back	Varia Ecoresin-Fossil Leaf spade random or equal
SS-5	Solid Surface	3Form or equal	1/2" - Patent on face/Patent on back	Chroma - Ivory or equal
CEILING TILE				
Key	Material	Manufacturer	Product Properties	Style/Color
ACT-1	Acoustical Ceiling Tile	Armstrong or equal	Wet formed mineral fiber/vinyl faced membrane	Clean Room VL Unperforated 868- 2x2x5/8" - White or equal
ACT-2	Acoustical Ceiling Tile	Armstrong or equal	Wet formed mineral fiber/ 62% recycled content	Ultima #1941 Tegular - 2x2x3/4"White or equal
ACT-3	Axiom - Knife Edge Trim	Armstrong or equal	Aluminum - 5-9/16" D, factory manu. corners	Finish to match Benjamin Moore HC-49 Mayflower Red or equal
ACT-4	Axiom - Knife Edge Trim	Armstrong or equal	Aluminum - 5-9/16" D, factory manu. corners	Finish to match Benjamin Moore #496 Chopped Dill or equal
MISCELLANEOUS FINISHES				
Key	Material	Manufacturer	Product Properties	Style/Color
CC-1	Privacy Curtains	Maharam	60% Solution Dyed Poly/40% FR Polyester	Laurel 511473 - 002 Bud or equal (ON)
CC-2	Privacy Curtains	Maharam	60% Solution Dyed Poly/40% FR Polyester	Laurel 511473 - 004 Honeysuckle or equal(GI)
	Door - Red Oak	Benjamin Moore	Waterborne Alkyd	Clear Coat - Matte Finish - Building Standard
	Interior Signage			Match Building Standard - B18 New VA Blue with White Letters

ROOM FINISH SCHEDULE- SURGERY DEPARTMENT

Room No.	Room Name	Floor		Base		Walls												CEILING		Remarks
		Material	Color	Material	Color	North			West			South			East			Type	Height	
2C-111	SOILED UTILITY	VINYL	SV-6	VINYL	FCB-2/3	EXISTING	PAINT	PT-6	EXISTING	PAINT	PT-6	EXISTING	PAINT	PT-6	EXISTING	PAINT	PT-6	EXISTING G/G YD BO*	8'-0"	A-OR-801 - ONLY EAST ROOM WITH WALL/DOOR CHANGES / CEILING-PT-9
2C-114	PATHOLOGIST	VINYL	SV-4	EXISTING	VB-2	EXISTING	PAINT	PT-6	EXISTING	PAINT	PT-6	EXISTING	PAINT	PT-6	EXISTING	PAINT	PT-6	ACT-1/ GYP BD*	8'-0"	* PAINT SOFFITS - PT-9
2C-118	STORAGE	VINYL	SV-6	VINYL	FCB-2/3	EXISTING	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	ACT-1	8'-0"	* WP-2 - 54" WAINSCOT
2C-119	CLEAN LINEN	VINYL	SV-6	VINYL	FCB-2/3	EXISTING	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	ACT-1	8'-0"	* WP-2 - 54" WAINSCOT
2C-120	RESTRICTED CORRIDOR	VINYL	SV-4/5/6	INTEGRATED BASE	FCB-2/3	GYP. BD	PAINT	PT-6*	EXISTING	PAINT	PT-6*	EXISTING	PAINT*	PT-6*	EXISTING	PAINT	PT-6	ACT-1	8'-0"	* A-OR-801/FCB-2/5V-5 AT DOUBLE DOORS
2C-120A	CASE CART ALCOVE	VINYL	SV-6	INTEGRATED BASE	FCB-2/3	EXISTING	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	--	--	--	GYP. BD	PAINT	PT-6*	ACT-1	8'-0"	* WP-2 -54" WAINSCOT
2C-120B	SCRUB	VINYL	SV-6	INTEGRATED BASE	FCB-2/3	--	--	--	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6	ACT-1/ GYP BD*	8'-0"	* SOFFIT - PT-9
2C-120C	GURNEY ALCOVE	VINYL	SV-6	INTEGRATED BASE	FCB-2/3	--	--	--	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6*	ACT-1/ GYP BD*	8'-0"	* WP-2 - 54" WAINSCOT/SOFFIT - PT-9
2C-121	EQUIPMENT STORAGE	VINYL	SV-6	VINYL	FCB-2/3	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6*	ACT-1	8'-0"	* WP-2 - 54" WAINSCOT
2C-122	GENERAL OR	TERRAZZO TILE	T-1/2	INTEGRATED TERRAZZO	FCB-5	GYP. BD	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	EXISTING	PAINT	PT-6*	EXISTING	PAINT	PT-6*	GYP. BD/PT-9	10'-0"	* T-1 - 3'-6" WAINSCOT
2C-123	SUB-STERILE	TERRAZZO TILE	T-1	INTEGRATED TERRAZZO	FCB-5	EXISTING	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	EXISTING	PAINT	PT-6*	GYP. BD	PAINT	PT-6	GYP. BD/PT-9	8'-0"	
2C-124	CYSTO	TERRAZZO TILE	T-1/2	INTEGRATED TERRAZZO	FCB-5	GYP. BD	PAINT	PT-6*	GYP. BD	PAINT	PT-6*	EXISTING	PAINT	PT-6*	EXISTING	PAINT*	PT-6*	GYP. BD/PT-9	10'-0"	* T-1 - 3'-6" WAINSCOT
C-2218	EXISTG RESTRICTED CORRIDOR	EXISTING	VINYL	VB*	EXISTING	PAINT	PT*	EXISTING	PAINT	PT*	EXISTING	PAINT	PT*	EXISTING	PAINT	PT*	EXISTING	ACT-1	8'-0"	* MATCH EXISTING PER SAMPLE APPROVAL BY COR/ARCHITECT

three inches = one foot
 one and one half inches = one foot
 one inch = one foot
 three quarters inch = one foot
 one half inch = one foot
 three eighths inch = one foot
 one quarter inch = one foot
 one eighth inch = one foot

100% ISSUE FOR BID	04-16-2013
100% CD Review	03-28-2013
99% CD Internal QA/QC	03-20-2013
90% CD Submission	02-08-2013
QA/QC Review	01-29-2013
50% Life Safety Review Package	01-07-2013
50% Finish Review Package	01-07-2013
50% CD Submission	12-28-2012
Design Development	11-08-2012
Revisions	Date

ARCHITECT + ENGINEERS:	
700 Nicholas Blvd, Suite 403 Blk Grove Village, IL 60007 T: 847.952.9362 F: 847.952.9403	

CONSULTANT:	
WAUKEGAN CRYSTAL LAKE OAK BROOK CHICAGO 24 NORTH CHAPEL STREET WAUKEGAN, IL 60085 PH: 847.662.3535 FX: 847.249.0398 WWW.LEGAT.COM	

Drawing Title ROOM FINISH SCHEDULE AND DETAILS	Project Title LOVELL FHCC OR-GI-ON RENOVATIONS SECOND AND THIRD FLOORS
Approved: Project Director - VAPAHCS PLANNING AND ENGINEERING	Project Number #556-12-127 Building Number 133 Drawing Number A-OR-821
Date 05-17-2013	Checked DD Drawn KB

Office of Construction and Facilities Management
 Department of Veterans Affairs