

AMENDMENT NO. 5

DATE: June 19, 2013

RE: VA Medical Center
5000 West National Avenue
Milwaukee, WI 53295

VA No. 695-12-195

This Addendum consists of 1 page.

The following items are to provide clarification to the contract documents:

1. Refer to the Bid Schedule on page 5 of the Solicitation for the bid items. Disregard the notes on the drawing set dated 4.19.13 highlighting key notes as bid alternate work. The items identified as bid items on the drawing set should all be included in the base bid cost. For example, key notes 3 through 6 on sheet AS-102 should be part of the base bid cost. As stated in the posted Bid Schedule, the base bid "Work includes rubber flooring system in the corridors and replacing the corridor wall finishes." Therefore, according to the posted bid schedule, key notes 3 through 5 on sheet AS-102 should be deleted to get the cost for alternate bid item 1.
2. The underside of the roof slab is 3'-6" above the X-ray treatment room finished ceiling. The slab is 10" thick, cast in place reinforced concrete. Per sheet AS-202 the contractor is responsible for the design of the unistrut system & shall provide installation drawings sealed by a State of Wisconsin Professional Structural Engineer.