



MARK	SERVES	PRESSURE (PSIG)		MINIMUM CAPACITY (LBS/HR)	ACTUAL CAPACITY (LBS/HR)	TYPE	SPRING PRESSURE RANGE (PSIG)	SIZE (INCHES)	REMARKS
		IN	OUT						
PRV-1	DT-1	105	5	1582	1799	SINGLE SEATED, DIAPHRAGM OPERATED, SPRING LOAD STEAM- PLOT CONTROLLED PACKLESS	2-15	1"	
PRV-2	HC-1	105	15	1582	1799	SINGLE SEATED, DIAPHRAGM OPERATED, SPRING LOAD STEAM- PLOT CONTROLLED PACKLESS	2-15	1"	

STEAM TRAP SCHEDULE								
MARK	SERVES	CONDENSATE LOAD (LBS/HR)	TRAP SAFETY FACTOR	MIN TRAP CAPACITY (LBS/HR)	DIFFERENTIAL PRESSURE (PSIG)	TYPE	CONNECTION SIZE (IN)	REMARKS
T-1	END OF MAIN	300	2	600	105	F&T	2 1/2"	
T-2	END OF MAIN	300	2	600	105	F&T	2 1/2"	
T-3	HC-1	1,580	3	4,746	15	F&T	3/4"	
T-4	MOBILE BOILER	20,000	3	60,000	105	F&T	2 1/2"	