




A CPT-1 INSTALLATION PATTERN
IN102 1" = 1'-0"




B CPT-2 INSTALLATION PATTERN
IN102 1" = 1'-0"



C PT-1 INSTALLATION PATTERN: BRICK
IN102 3/4" = 1'-0"



D PT-2 INSTALLATION PATTERN: BRICK
IN102 3/4" = 1'-0"



ROOM FINISH SCHEDULE continued

COUNTERTOP			
NO.	COLOR NO. / MANUFACTURE	ROOM LOCATION	REMARKS
SS-1	POLAR CAP/ECO BY COSENTINO	ROOM 008, ROOM 028	
SS-2	SAVANNAH/CORIAN	ROOM 002, ROOM 005	
SS-3	WITCH HAZEL/CORIAN	ROOM 007, ROOM 009, ROOM 010, ROOM11, ROOM 12, ROOM 14, ROOM 015, ROOM 016, ROOM 019, ROOM 022, ROOM 023, ROOM 024, ROOM 025, ROOM 030	

CASEWORK MATERIALS

NO.	COLOR NO. / MANUFACTURE	ROOM LOCATION	REMARKS
PLAM-1	STUDIO TEAK/7960K-18/WILSONART LAMINATE	ROOM 002, ROOM 005	
PLAM-2	CHARDONNAY/7955-38/WILSONART LAMINATE	ROOM 011, ROOM 012, ROOM 014, ROOM 015, ROOM 016, ROOM 019	
PLAM-3	GREY/1500-60/WILSONART LAMINATE	ROOM 022.5, ROOM 023.5, ROOM 028	ROOMS 022.5 AND 23.5 PLAM-3 WILL BE USED ON BENCH

WALL PANELING

NO.	COLOR NO. / MANUFACTURE	ROOM LOCATION	REMARKS
AP	SWIM + REEF + REEF: 3 FORM VARIA ECORESIN	ROOM 008	

WALL PROTECTION

NO.	COLOR NO. / MANUFACTURE / MODEL NUMBER	REMARKS
WG-1	WALL GUARD - COLOR 100: EGGSHELL / CS GROUP / ACROVYN - SCR-64N	
CG-1	CORNER GUARD - COLOR 100: EGGSHELL / CS GROUP / ACROVYN - SM-20N	
CG-2	CORNER GUARD - COLOR 100: EGGSHELL / CS GROUP / ACROVYN - FSC-25N	

CEILINGS

NO.	MATERIAL	SIZE	COLOR/NO.	MANUFACTURER	REMARKS
ACT	ACOUSTIC CEILING TILE	2'x2'	WHITE (WH)/CIRRUS/SQUARE LAY-IN	ARMSTRONG	SEE RCP FOR ACT LOCATION
QWB	GYPSUM WALL BOARD	SEE RCP	SW 7102/WHITE FLOUR/EGGSHELL	SHERWIN-WILLIAMS	USE SEMI-GLOSS PAINT IN THE FOLLOWING ROOMS: ROOM 019, ROOM 034

SOLAR SHADING

NO.	COLOR NO. / MANUFACTURE	REMARKS
SS	MECHOSHADE; EUROVEIL 5300 SERIES BASKETWEAVE, COLOR: SAND 5304, 5% OPENNESS FACTOR WITH VALANCE.	ALL WINDOWS TO RECEIVE MECHOSHADE EXCEPT CLERESTORY WINDOWS.

TRIM

NO.	MATERIAL	COLOR NO. / MANUFACTURE	REMARKS
P-1	PAINT	SHERWIN WILLIAMS/SW 7102 WHITE FLOUR/SEMI-GLOSS	INTERIOR DOOR FRAMES AND INTERIOR WINDOW FRAMES, U.N.O.


GENERAL NOTES

- ALL EXTERIOR WINDOWS TO RECEIVE WOVEN SOLAR SHADES WITH 5% TRANSPARENCY FACTOR AND VALANCES, UNLESS NOTED OTHERWISE.
- WINDOWS IN EXAM ROOMS TO RECEIVE 1" MINI BLINDS.
- INTERIOR WOOD DOORS TO BE MARSHFIELD; PLAIN SLICED WHITE OAK, COLOR: NUTMEG 48-97.
- INTERIOR STOREFRONT FRAMES TO BE BRONZE.
- LIGHT SWITCHES, POWER, COMM AND DATA COVERS TO BE WHITE ENAMEL.
- ALL PORCELAIN TILE FLOOR AND WALL TILES TO HAVE GROUT MATCHING THE COLOR OF THE TILE. GROUT JOINTS SHALL BE NO MORE THAN 3/8" WIDE.

FINAL SUBMISSION
APRIL 9, 2013

IF SHEET IS LESS THAN (30"x42") IT IS A REDUCED PRINT; SCALE ACCORDINGLY

IN102



NATURAL RESOURCES & ENVIRONMENTAL AFFAIRS SAFETY DEPARTMENT FIRE DEPARTMENT PUBLIC WORKS SUPERVISOR	P.W. DWG. NO.	DEPARTMENT OF THE NAVY NAVAL SUPPORT ACTIVITY PANAMA CITY, FLORIDA
	DRAWN BY AAC	CONSTRUCT NAVAL BRANCH HEALTH CLINIC PANAMA CITY
	CHECKED BY KAM	FINISH SCHEDULE & FLOOR INSTALLATION PATTERN
	SUPERVISOR	NAVFAC DRAWING NO. N/A
APPROVED DATE	SIZE F	CODE IDENT. NO.
PUBLIC WORKS OFFICER	SCALE	CONSTR. CONTR. NO.
		MACC.
		T.O.#
		SHEET 2 OF 6