

FIXTURE SCHEDULE						
ITEM	DESCRIPTION	CW	HW	WASTE	VENT	REMARKS (SEE NOTE)
P-101	WATER CLOSET	1"	-	3"	2"	WHITE, WALL MOUNT, ELONGATED, 1.28 GPF, TOP SPUD WITH EXPOSED INFRARED FLUSH VALVE, WALL CARRIER AND ELONGATED OPEN FRONT SEAT.
P-401	LAVATORY, WALL MOUNTED SLAB TYPE	3/8"	3/8"	1 1/2"	1 1/2"	WALL MOUNTED, SLAB TYPE, VITREOUS CHINA, ELECTRONIC FAUCET
P-501	MOP SINK	1"	1"	3"	1 1/2"	TERRAZZO MOP SERVICE SINK FITTING WITH VACUUM BREAKER, ADJUSTABLE TOP BRACE, 3/4" HOSE THREAD ON SPOUT W/ BUCKET HOOK INLETS, 8" O.C., CHROME FINISH
P-508	SINK, CRS	3/8"	3/8"	1 1/2"	1 1/2"	SINGLE BOWL SINK, STAINLESS STEEL, SELF-RIMMING WITH SWIVELING GOOSENECK FAUCET W/ 4" WRIST BLADE HANDLES
P-508A	SINK, CRS W/ GARBAGE DISP.	3/8"	3/8"	1 1/2"	1 1/2"	SINGLE BOWL SINK, STAINLESS STEEL, SELF-RIMMING WITH SWIVELING GOOSENECK FAUCET W/ 4" WRIST BLADE HANDLES WITH GARBAGE DISPOSAL
P-604	ELECTRIC WATER COOLER	3/8"	-	1 1/2"	1 1/2"	BI-LEVEL HEAVY DUTY 14 GUAGE DRINKING FOUNTAIN, WALL MOUNT, FULLY EXPOSED, BARRIER-FREE ACCESS MODEL (OR APPROVED EQUAL)
P-701	SHOWER	1/2"	1/2"	2"	2"	SHOWER VALVE AND TRIM WITH 1.5 GPM ROUGH VALVE WITH INTEGRAL STOPS AND TRIM KIT WITH 1.5 GPM HANDSHOWER
P-801	HOSE BIB	3/4"	-	-	-	STANDARD BRASS, 3/4" MHT, FROSTPROOF WITH VACUUM BREAKER BACKFLOW PREVENTOR
P-900	ICE MAKER	1/2"	-	-	-	SIOUX CHIEF 696-1000MF OX BOX ICE MAKER OUTLET BOX
FD	FLOOR DRAIN	-	-	3"	-	SIOUX CHIEF 832-36PNR "FINISH LINE" ADJUSTABLE FLOOR DRAIN W/TRAP PRIMER CONNECTION W/ 45 GPM 4" DEEP SEAL TRAP AND AUTOMATIC TRAP PRIMING VALVE
HD	HUB DRAIN	-	-	3"	-	SIOUX CHIEF 832-36PF/832-4HHD "FINISH LINE" ADJUSTABLE HUB DRAIN

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION. PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

SOLAR WATER HEATER SCHEDULE							
MARK	STORAGE GALLONS	BACK-UP ELECTRICAL ELEMENTS			RECOVERY ⊗ 70°F RISE	BASIS OF DESIGN	NOTES
		NO.	KW EA.	V			
EW-1	119	1	4.5	277		SUPERSTOR MODEL SSU-119SE	1 REQUIRED, SINGLE PHASE

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION. PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

SOLAR PANELS						
MARK	DESCRIPTION	QTY.	TRANSPARENT AREA EA.	WORKING PRESSURE	FLOW RATE	BASIS OF DESIGN
SP	SOLAR PANEL COLLECTOR	2	39.7 SF	165 PSI	0.5-1.8 GPM (RECOMMENDED)	SOLAR SPECTRUM MODEL FP-40SC

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION. PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

DRAIN-BACK TANK SCHEDULE					
MARK	DESCRIPTION	QTY.	CAPACITY	BASIS OF DESIGN	NOTES
DB-1	DRAIN-BACK TANK	1	15 GALLON	HTP MODEL NO. SSU-15DB	

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION. PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

RECIRCULATION PUMP SCHEDULE						
MARK	SERVICE	GPM	ELECTRICAL	HP	BASIS OF DESIGN	REMARKS
RP-1	HOT WATER RECIRCULATION	7	115V, 60Hz, 1 PH	1/40	TACO MODEL 003-ST4	
RP-2	SOLAR WATER RECIRCULATION	1.5	115V, 60Hz, 1 PH	1/8	TACO MODEL 113	1" FLANGE, HEAD = 16'

NOTE: BASIS OF DESIGN IS NOT INTENDED TO LIMIT EQUIPMENT SELECTION. PROVIDE INDICATED EQUIPMENT OR EQUIPMENT OF EQUAL PERFORMANCE AND QUALITY.

FINAL SUBMISSION  
APRIL 9, 2013

IF SHEET IS LESS THAN (30"x42") IT IS  
A REDUCED PRINT; SCALE ACCORDINGLY

P011



 766 MIDDLE ST., FARMHSE, AL 36532 251-890-5778 ARCH. & ENGR. SEAL 	NATURAL RESOURCES & ENVIRONMENTAL AFFAIRS SATISFACTORY TO DATE	P.W. DWG. NO.	DEPARTMENT OF THE NAVY NAVAL SUPPORT ACTIVITY PANAMA CITY, FLORIDA		
	SAFETY DEPARTMENT SATISFACTORY TO DATE	DRAWN BY JLL	CONSTRUCT NAVAL BRANCH HEALTH CLINIC PANAMA CITY  PLUMBING SCHEDULES		
	FIRE DEPARTMENT SATISFACTORY TO DATE	CHECKED BY WWB			
	PUBLIC WORKS SUPERVISOR SATISFACTORY TO DATE	SUPERVISOR WWB			
		APPROVED DATE	PUBLIC WORKS OFFICER	SIZE F HQC PROJ. NO. 520-13-200 SCALE NONE	CODE IDENT. NO. N/A CONSTR. CONTR. NO.
			MACC.	T.O.#	SHEET 2 OF 8