

STEAM LOSS REPORT

SURVEY FOR: VA HOSPITAL
 SURVEYOR: ENERGY WEST CONTROLS
 03/04/2008

Tag	Mfg	Model	Conn	Pin	Appl	Months in Use		Steam Loss lbs/hr.	\$ Loss Annually
1355	ARM	125A3	3/4"	80	DR	12	BT	89.21	\$13,103.65
1354	ARM	125A3	3/4"	50	DR	12	BT	60.95	\$8,952.55
1366	ARM	125A3	3/4"	50	DR	12	BT	60.95	\$8,952.55
1374	SAR	FT125	1"	50	DR	12	BT	60.95	\$8,952.55
1418	SAR	FT75	3/4"	50	DR	12	BT	60.95	\$8,952.55
1465	DUN	40215	3/4"	50	DR	12	BT	60.95	\$8,952.55
1466	DUN	40215	3/4"	50	DR	12	BT	60.95	\$8,952.55
1467	DUN	40-215A	1"	50	DR	12	BT	60.95	\$8,952.55
1481	SAR	TD52	1"	50	PR	12	BT	60.41	\$8,873.54
1402	SAR	B1X	3/4"	15	DR	12	BT	49.69	\$7,298.89
1483	HOF	601A	3/4"	100	DR	12	BT	37.55	\$5,515.04
1442	SAR	B1X	3/4"	25	DR	12	BT	37.40	\$5,493.29
1490	SAR	B1X	3/4"	25	DR	12	BT	37.40	\$5,493.29
1492	ARM	15B3	3/4"	25	DR	12	BT	37.40	\$5,493.29
1307	ARM	800	3/4"	100	DR	12	BT	36.85	\$5,412.91
1373	ARM	800	3/4"	100	DR	12	BT	36.85	\$5,412.91
1357	ARM	125A3	3/4"	20	DR	12	BT	32.69	\$4,801.44
1358	ARM	125A3	3/4"	20	DR	12	BT	32.69	\$4,801.44
1330	DUN	44215	3/4"	15	DR	12	BT	27.98	\$4,109.59
1348	DUN	44215	3/4"	15	DR	12	BT	27.98	\$4,109.59
1364	ARM	125A3	3/4"	15	DR	12	BT	27.98	\$4,109.59
1371	DUN	40215	3/4"	15	DR	12	BT	27.98	\$4,109.59
1375	SAR	FT15	3/4"	15	DR	12	BT	27.98	\$4,109.59
1378	SAR	FT15	3/4"	15	DR	12	BT	27.98	\$4,109.59
1461	ARM	15B5	1-1/4"	15	DR	12	BT	27.98	\$4,109.59
1489	ARM	811	3/4"	25	CL	12	BT	24.04	\$3,531.40
1493	DUN	40215	3/4"	25	CL	12	BT	24.04	\$3,531.40
1386	DUN	40215	3/4"	10	DR	12	BT	21.59	\$3,171.46
1389	DUN	40215	3/4"	10	DR	12	BT	21.59	\$3,171.46
1454	DUN	44-275	3/4"	25	DR	12	BT	20.85	\$3,062.39
1331	WAT	WFT	3/4"	15	PR	12	BT	14.82	\$2,176.07
1306	ARM	800	3/4"	5	DR	12	BT	14.27	\$2,095.44
1323	DUN	44215	3/4"	5	DR	12	BT	14.27	\$2,095.44
1351	ARM	15B3	3/4"	5	DR	12	BT	14.27	\$2,095.44
1352	ARM	800	3/4"	5	DR	12	BT	14.27	\$2,095.44
1359	DUN	40215	3/4"	5	DR	12	BT	14.27	\$2,095.44
1361	ARM	30B3	3/4"	5	DR	12	BT	14.27	\$2,095.44
1365	WAT	WFT	3/4"	5	DR	12	BT	11.75	\$1,725.98
1344	DUN	44215	3/4"	15	CL	7	BT	17.99	\$1,541.10
1314	DUN	44-275	3/4"	5	DR	12	BT	8.07	\$1,184.91
1338	DUN	44215	3/4"	15	DR	12	LK	6.99	\$1,027.40
1317	W-M	TT125	1/2"	5	CL	7	BT	9.17	\$785.79
1311	W-M	FT3	3/4"	5	DR	12	LK	3.57	\$523.86
1320	SAR	TD52	1/2"	5	CL	7	LK	1.64	\$140.32
1304	ARM	800	3/4"	100	DR	12	PL		
1305	ARM	800	3/4"	100	DR	12	PL		
1309	ARM	880	3/4"	50	DR	12	PL		
1368	DUN	40215	3/4"	10	DR	12	PL		

STEAM LOSS REPORT

SURVEY FOR: VA HOSPITAL
SURVEYOR: ENERGY WEST CONTROLS
03/04/2008

Tag	Mfg	Model	Conn	Pin	Appl	Months in Use		Steam Loss lbs/hr.	\$ Loss Annually
1438	SAR	B1X	3/4"	65	DR	12	PL		
1449	ARM	881	3/4"	15	DR	12	PL		
1477	SAR	FT15	3/4"	15	DR	12	PL		

TOTALS: **1382.38 \$201,280.85**