

ADDENDUM #2

ISSUE DATE: July 16, 2013
VA PROJECT NUMBER: 636A8-13-009
VA PROJECT NAME: Replace Fan Coils and Convectors, Phase I

The following items are to be corrected, deleted from, or added to the Contract documents for subject project and become a part of said documents.

PART I - SPECIFICATIONS**ITEM 1 – SECTION 02 8211 TADITIONAL ASBESTOS ABATEMENT**

- A. Paragraph 1.1.2. Extent of Work
 - a. Paragraph B: Delete 'Approximately 120-140 linear feet of 2"-6" diameter pipe insulation'.
 - b. Paragraph B: Revise 'Approximately 500 square feet of boiler /tank insulation' to read "Approximately 500 square feet of boiler/tank insulation adhesive"

PART II - DRAWINGS**ITEM 2 – DRAWING 1-D1.1A DUMB WAITER DEMOLITION PLAN**

- A. Refer to General Demolition Notes "B" and revise to read the following: "Saw cut opening in structural clay wall for new door and remove a portion of vinyl base where wall is to be saw cut.
- B. Refer to General Demolition Notes and add the following note "BB" to read: "Where new opening in wall is to be provided remove existing handrail and crashrail on wall, salvage for reinstallation."
- C. Refer to First Fl. DW Demo Plan and add General Demolition Note "BB" to south side of corridor where portion of wall is to be removed for new door.
- D. Refer to Sec. Fl. DW Demo Plan and add General Demolition Note "BB" to south side of corridor where portion of wall is to be removed for new door.
- E. Refer to Third Fl. DW Demo Plan and add General Demolition Note "BB" to south side of corridor where portion of wall is to be removed for new door.
- F. Refer to Third Fl. DW Demo Plan; remove and salvage existing display case located on south side of corridor where portion of wall is to be removed for new door. Contractor is to salvage display case to Owner.
- G. Refer to Fifth Fl. DW Demo Plan and add General Demolition Note "BB" to south side of corridor where portion of wall is to be removed for new door.
- H. Refer to Seventh Fl. DW Demo Plan and add General Demolition Note "BB" to south side of corridor where portion of wall is to be removed for new door.
- I. Refer to Eleventh Floor Dumb Waiter Demo Plan; remove an additional structural steel I-Beam supporting the existing dump waiters.

ITEM 3 – DRAWING 1-A1.1A BUILDING SHAFT CONSTRUCTION PLAN

- A. Refer to General Construction Notes and the following to the end of note 22: “Contractor is provide and replace any damaged wall covering located in corridor due to the removal of rated dust partition. Replacement wall covering is to match color, texture, and finish of existing.”
- B. Refer to General Construction Notes and add the following note 23 to read: Cut/modify existing handrail and crashrail and reinstall in corridor. Contractor to provide appropriate end cap and hardware for a complete finished installation.”
- C. Refer to First Fl. DW Const Plan; add note 23 to the south wall of Corridor 1CE01 on both the east and west side of new door 1W01A.
- D. Refer to Sec. Fl. DW Const Plan; add note 23 to the south wall of Corridor 2CW01 on both the east and west side of new door 2W01A. Refer to ASD-1 for more information.
- E. Refer to Sec. Fl. DW. Const. Plan; paint portion of south wall in Corridor 2CW01 where door 2W01A was installed. Paint from corner to corner approximately 26'-0" from finished floor to finished ceiling.
- G. Refer to Third Fl. DW Const Plan; add note 23 to the south wall of Corridor 3CW01 on both the east and west side of new door 3W01A.
- H. Refer to Fifth Fl. DW Const Plan; add note 23 to the south wall of Corridor 5CW01 on both the east and west side of new door 5W01A.
- J. Refer to Seventh Fl. DW Const Plan; add note 23 to the south wall of Corridor 7CW01 on both the east and west side of new door 7W01A.

ITEM 4 – DRAWING 1-FP1.1A – BUILDING SHAFT - FIRE PROTECTIONS PLAN

- A. Revise Basement DW Plan to show existing sprinkler heads. Refer to supplemental drawing FPSD-1.
- B. Revise First Floor DW Plan to show existing sprinkler heads. Refer to supplemental drawing FPSD-2.
- C. Revise Fourth Floor DW Plan to show existing sprinkler heads. Refer to supplemental drawing FPSD-3.

ITEM 5 – DRAWING 1-MD1.00 – SUB-BASEMENT FLOOR MECHANICAL PIPING DEMOLITION PLAN

- A. Revise domestic water piping demolition at main service in room SB08. Refer to supplemental drawing MSD-1

ITEM 6 – DRAWING 1-M1.00 – SUB-BASEMENT FLOOR MECHANICAL PIPING PLAN

- A. Revise domestic water piping new work at main service in room SB08. Refer to supplemental drawing MSD-2.

ITEM 7 – DRAWING 1-M5.05 – MECHANICAL SCHEDULES AND DETAILS

- A. Add the following to Mechanical Note M-37: “Existing roof is torch applied Genisys system by Viridian. All roof work shall be accomplished by a qualified Viridian Systems installer and all existing warranties shall be maintained.”

END OF ADDENDUM #2

DESIGN ENGINEERS, P.C.
Cedar Rapids, Iowa

By: Blake Anderson, PE
Yolanda Cruz

c: