

RE-BUILD GAZEBO, B-112

PROJECT NO. 528A6-13-629


V.A. MEDICAL CENTER
BATH, NEW YORK 14810


DRAWING NO.	SYMBOL	<u>SHEET</u>	<u>TITLE</u>
VAMC-528A6-1757	T-1	I OF 3	COVER SHEET
VAMC-528A6-1757	A-I	2 OF 3	PLANS, DETAILS & GENERAL NOTES
VAMC-528A6-1757	A-2	3 OF 3	SECTIONS, DETAILS \$ NOTES





		ALL WORK TO BE IN ACCORDANCE WITH N.F.P.A., NATIONAL, STATE AND CITY CODES & O.S.H.A.	Approved: A.F.G.E. Date Approved: Interior Designer Date		Approved: Fire Chief Date Approved: Safety Officer Date		Approved: Energy Engineer Date	Drawing Title COVER SHEET	Project Title RE-BUILD GAZEBO	Date 05/29/2013	•	
		Approved: Logistics Manager. Date					Approved: M&R Foreman Date		Drawing File Number:		Project No. 528A6-13-629	
		Approved: Infection Control Mgr. Date	Approved: Info. Sys.	Date	Approved: GEMS Coordinator	Date		Date	Approved: Engineering Project Manager Date	Building No. 112 Checked Drawn JHH	DRAWING NO. VAMC-528A6-1757	
Revisions	Date	Approved: Chief Security Date	Approved: Associate Director	Date	Approved: <u>MVAC</u> Careline Manager [Date		Date	Approved: Medical Center Director Date	Location BATH, NEW YORK]	





FL*oo*r framing Plan


SCALE: 1/4" = 1-0"

ROOF FRAMING PLAN — LOWER LEVEL

SCALE: 1/4" = 1'-0"

GENERAL CONSTRUCTION NOTES

- I. THE CONTRACTOR SHALL REVIEW THE CONTRACT DOCUMENTS FOR CONFLICTS. WHERE CONFLICTS EXIST WITHIN THE DRAWINGS, WORK SHALL NOT PROCEED UNTIL THE ENGINEER HAS BEEN NOTIFIED AND GIVEN DIRECTION BY THE PROJECT COR.
- 2. THE CONTRACT DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE UNLESS OTHERWISE INDICATED, THEY DO NOT SPECIFY METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL TAKE ALL NECESSARY STEPS AND PRECAUTIONS TO MAINTAIN THE STABILITY OF THE STRUCTURE AND PROTECT WORKERS, VA STAFF AND PATIENTS DURING THE CONSTRUCTION. SPECIFIC ITEMS TO BE CONSIDERED SHALL INCLUDE, BUT NOT LIMITED TO THE ADEQUACY OF ALL FORMS, SCAFFOLDING, AND SHORING FOR CONSTRUCTION EQUIPMENT AND THE TEMPORARY LATERAL BRACING OF THE STRUCTURE. REFER TO SPECIFICATIONS SECTION 0/06/0 SAFETY AND HEALTH REGULATIONS.
- 3. ALL FRAMING ANCHORS, CLIPS, STRAPS, HANGERS, ETC. REFERENCED ON THE DRAWINGS SHALL BE MANUFACTURED BY SIMPSON STRONG—TIE CO. OR AS APPROVED BY THE V.A. STRUCTURAL ENGINEER AND RESIST MAX. RATED LOADS.
- 4. BOLT, LAG SCREW HEADS & NUTS AGAINST WOOD SHALL BEAR AGAINST STANDARD STEEL WASHERS, UNLESS SPECIAL WASHERS ARE INDICATED ON PLANS OR DETAILS.
- 5. LAG SCREWS SHALL BE THREADED INTO LEAD HOLES BORED AS FOLLOWS; THE LEAD HOLE FOR THE SHANK SHALL BE THE SAME DEPTH & DIAMETER AS THE SHANK. THE LEAD HOLE FOR THE THREADED PORTION SHALL HAVE A DIAMETER EQUAL TO 60-75 PERCENT OF THE SHANK DIAMETER AND A DEPTH EQUAL TO AT LEAST THE LENGTH OF THE TREADED PORTION.
- 6. WHERE INCIDENTAL WORK IS REQUIRED TO ACCOMPLISH
 SHOWN ON THE DRAWINGS, THIS WORK IS IMPLIED AND SHALL
 BE CONSIDERED AS PART OF THE BASE BID.
- 7. PRIOR TO ANY WORK COMMENCING IN A WORK AREA, THE CONTRACTOR SHALL NOTIFY THE PROJECT COR OF THEIR INTENTION TO WORK IN THE AREA. THE CONTRACTOR SHALL SCHEDULE A WALK THROUGH OF THE AREA WITH THE COR TO VERIFY THE EXISTING CONDITIONS. AFTER CONSTRUCTION IS COMPLETED THE CONTRACTOR SHALL VERIFY WITH THE COR THAT THE AREA IS RETURNED TO ITS ORIGINAL CONDITION BEFORE FINAL APPROVAL IS GRANTED.
- 8. ALL LOCATIONS / DIMENSIONS ARE APPROXIMATE. CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY LOCATIONS / DIMENSIONS AND EXISTING CONDITIONS IN THE FIELD.
- 9. CONSTRUCTION & DUST BARRIERS SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR AND BE APPROVED BY THE
- 10. THE CONTRACTOR SHALL ENSURE THAT THE WORK AREA 15 CLEAN & SECURE AT THE END OF EACH WORK DAY. ALL TRASH AND DEBRIS SHALL REMOVED DAILY.



ROOF FRAMING PLAN -UPPER LEVEL scale: 1/4" = 1'-0"

Revisions		Date
	SCALE: /4" =	- 1-0

COLUMN PLAN

FOOTING SIZES & REINFORCING SHALL BE AS FOLLOWS:

FI: $3' \times 3'$, REINF. W/ (3) #5 BARS EACH WAY F2: $4' \times 4'$, REINF. W/ (4) #5 BARS EACH WAY LOCATIONS.)

Drawing Title FLOOR PLANS & GENERAL NOTES		Project Title RE-BUILD GA	AZEBO	Date 05/29/2013 Project No. 528A6-13-629	*	
Approved: Engineering Project Manager D	Date	Building No. 112	Checked JAY	Drawn JHH	DRAWING NO. VAMC-528A6-1757	
Approved: Medical Center Director	Date	Location BATH, NEW`	YORK		A-1 Dwg. 2 Of 3	

