

JLG Architects

Ross McIntyre, Assoc. AIA

801 Washington Avenue North Unit 120 Minneapolis, MN 55401

p. 612.746.4260 d. 612.436.4009 c. 651.283.6031

rmcintyre@jlgarchitects.com

JLG 11050L-5 Upgrade Reception Stations St Cloud VAHCS Proj. No. 656-13-226

RE: Amendment No. 2

July 22, 2013

Amendment No.2

Please issue the following changes to the contract documents as Amendment No. 2 for the Upgrade Reception Stations Project at the St. Cloud, MN VAHCSC (Project No. 656-13-226)

To:	CC:	
	\boxtimes	Gary Johnson St. Could VA
\boxtimes		Randy Collins
		St. Could VA Aaron Mueller
\Box	\square	Design Tree Engineering Jerry Richardson
ш		JLG Architects

Shee	et#	Sheet Name	Description of Change	
GENERAL:				
•	GI1	Project Cover Sheet	Designated project staging and dumpster areas shown in details 2&3/GI1 are to be a maximum of 40'x40.	
•		window treatments	Window treatments will be taken down by the VA, stored and put back up following project completion.	
•		Bldg 51	Staff toilet and med room walls have been field verified to be metal stud construction. A CW shut-off is located in the ceiling space just north of the existing toilet room. CW, HW, and Recirc are all located in the large chase to the east and routed overhead to the toilet room plumbing chase. Shut-offs can be found downstairs in the mechanical room.	
			Contractor is responsible for fire caulking any new penetrations made in plumbing chase walls or the mechanical room walls.	
			New plumbing work is to be done using threaded plumbing fittings (not grooved). Existing, non-conforming Victaulic piping and fitting need only be removed/replaced to the extent needed to connect new fittings properly.	
ARCHITECTURAL:				
• AS1, AS2, AS3			Project Demolition Notes: See revised drawing sheets. Modular furniture/casework or millwork identified as 'to be removed from project' is to be disposed of by the contractor off site per specifications.	
• AS1, AS2		AS2	See attached sheets for clarifications to locations of VWC removal, skim coating and prepping for paint.	
•	AS5	Details and Schedules	See attached sheet for clarifications to Room Finish Schedule at Bldg 2.	
•	AS8	B51 2 nd Flr RCP	See attached sheet for clarifications to RCP and soffiting at this station location.	

AS8 B51 2nd FIr RCP Connect new down lights shown at new soffit area to nearest emergency lighting circuit on this floor with spare capacity. Verify exact conditions on site.

Attachments:

- Drawing Sheet: 11050L_Nurses Stations_REVISED AS-1_B2-1_Amend No2 130722
- Drawing Sheet: 11050L_Nurses Stations_REVISED AS-2_B51-1_Amend No2 130722
- Drawing Sheet: 11050L_Nurses Stations_REVISED AS-3_B51-2_Amend No2 130722
- Drawing Sheet: 11050L_Nurses Stations_REVISED AS-5_details_Amend No2 130722
- Drawing Sheet: 11050L_Nurses Stations_REVISED AS-8_B51-2_RCP_Amend No2 130722