

SECTION 09 06 00
SCHEDULE FOR FINISHES

PART I - GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

1.4 APPLICABLE PUBLICATIONS

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in text by basic designation only.

B. MASTER PAINTING INSTITUTE: (MPI)

2001.....Architectural Painting Specification Manual

PART 2- PRODUCTS

2.1 DIVISION 05 - METALS

A. SECTION 05 50 00, METAL FABRICATION

Item	Finish
Frames for Lead Lined Doors	Color: Match Wall, Kelly Moore, Enviro Coat (No VOC),

	1500 Series, 1520 semi-gloss, Acrylic Enamel.
Guard Angles for Overhead Doors (exposed only)	Color: Match Wall, Kelly Moore, Enviro Coat (No VOC), 1500 Series, 1520 semi-gloss, Acrylic Enamel.
Aluminum Plate Door Sill	Mill finish

B. SECTION 07 95 13, EXPANSION JOINT COVER ASSEMBLIES

	Material	Finish	Manufacturer	Mfg. Color Name/No.
Floor Component Cover Plate Frame (interior only)	Aluminum	Clear	Construction Specialties	Duranodic "Clear"
Wall Component Cover Plate Frame (interior only)	Aluminum	Clear	Construction Specialties	Duranodic "Clear"
Exterior Wall Cover Plate Frame	Aluminum	Clear	Construction Specialties	Duranodic "Clear"

2.2 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

A. SECTION 06 20 00, FINISH CARPENTRY

1. SEATS AND BENCHES (TYPE 20 A, 12 E, 13 B)		
Room No. and Name	Component	Finish/Color
	Seat	Maple
	Support	

2. GLASS FIBER REINFORCE PLASTIC PANELS			
Location	Finish	Manufacturer	Mfg. Color Name/No.
Lavatory backsplashes	Scored FRP with Sani-Coat	Marlite	Symmetrix FRP #C100-G44 White

2.3 DIVISION 07 - THERMAL AND MOISTURE PROTECTION

A. SECTION 07 41 20, METAL WALL PANELS

Type	Shape	Ext. Finish	Int. Finish	Manufacturer	Mfg. Color Name/No.
2" Insulated	Flat	PVDF	Per Mfg.	Centria	#9964 XL Medium Bronze

B. SETION 07 53 23, ETHYLENE-PROPYLENE-DIENE-MONOMER ROOFING

Color	Manufacturer	Mfg. Color Name/No.
White	Carlisle	Sure Seal Ballasted EPDM

C. SECTION 07 60 00, FLASHING AND SHEET METAL

Item	Material	Finish
	Stainless steel	Mill
	Aluminum	

D. SECTION 07 71 00 / 07 72 00, ROOF SPECIALITIES AND ACCESSORIES

Item	Material	Finish	Manufacturer	Manufacturer/Color
------	----------	--------	--------------	--------------------

				Name/Number.
Equipment Support	Galv. Steel	Paint		
Gravity Ventilators	Aluminum	Mill		
Grating Walkway	Galv Steel			
Copings	Extruded Aluminum			
Gravel Stops and Fascia System	Extruded Aluminum			
Fascia Systems	Extruded Aluminum			
Roof Expansion Joint Covers	Extruded Aluminum	Mill		

2.4 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal louvers, and hardware attached to door	
Component	Color of Paint Type and Gloss
Frame	Color: Match Wall, Kelly Moore, Enviro Coat (No VOC), 1500 Series, 1520 semi-gloss, Acrylic Enamel.
Window frame S11	Bronze Anodized - Match Existing

B. SECTION 08 14 00, WOOD DOORS

Component	Manufacturer	Finish/Color
Doors - Plain Sliced White Maple	Marshfield Door Systems	Enviroclad UV Stain/ Clear 0-95

C. SECTION 08 31 13, ACCESS DOORS AND FRAMES

Material	Finish/Color
Steel	Color: Match Wall, Kelly Moore, Acrylic Enamel, GL 5

D. SECTION 08 33 00, COILING GRILLES

Location	Item	Material	Finish	Manufacturer	Manufacturer Color Name/No.
G2511A, G2511B, & G2512B	Grille	Aluminum	Mill	Cookson	----

E. SECTION 08 41 13, ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

Material	Finish	Manufacturer	Manufacturer Color Name/No.
Aluminum (Interior)	Anodized	Kawneer	Clear #14
Aluminum (Exterior)	Anodized	Kawneer	Medium Bronze #28

F. WINDOW STOOLS

Room No. and Name	Material	Finish
Where occurs on drawings	Solid surfacing	Corian "Sagebrush"

DESIGNER NOTE: Coordinate with Section 08 71 00, DOOR HARDWARE for preferred finishes, specified par 2.28. List only items deviating from Section 08 71 00, par 2.28.

G. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Stainless Steel	US32D Dull Stainless Steel
Door Closers	Stainless Steel	US32D Dull Stainless Steel
Floor Closers	Stainless Steel	US32D Dull Stainless Steel
Floor Pivot Sets	Stainless Steel	US32D Dull Stainless Steel
Closer/ Holder	Stainless Steel	US32D Dull Stainless Steel
Floor Stops	Stainless Steel	US32D Dull Stainless Steel
Door Holders	Stainless Steel	US32D Dull Stainless Steel
Lock/ Latches	Stainless Steel	US32D Dull Stainless Steel
Key Cabinet	Steel	Painted
Armor Plates	Stainless Steel	US32D Dull Stainless Steel
Kick Mop Plates	Stainless Steel	US32D Dull Stainless Steel
Door Edging	Stainless Steel	US32D Dull Stainless Steel
Exit Device	Stainless Steel	US32D Dull Stainless Steel
Flush Bolts	Stainless Steel	US32D Dull Stainless Steel
Door Pulls	Stainless Steel	US32D Dull Stainless Steel
Push Plates	Stainless Steel	US32D Dull Stainless Steel
Combination Push Pull Plate	Stainless Steel	US32D Dull Stainless Steel
Coordinators	Stainless Steel	US32D Dull Stainless Steel
Weather Strip	Stainless Steel/rubber	US32D Dull Stainless Steel
Threshold	Aluminum	Mill Finish

H. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
--------------	--------------	---------------------

G4	Guardian Industries	Surface No. 2: SunGuard SuperNeutral 68 (SN 68)
G5	Guardian Industries	Surface No. 2: SunGuard SuperNeutral 68 (SN 68)
G7	Guardian Industries	Surface No. 2: SunGuard SuperNeutral 68 (SN 68) Acid Etched Surface #3: SunGuard SatinDeco on clear float glass

2.9 DIVISION 09 - FINISHES

A. SECTION 09 30 13, CERAMIC TILING

1. SECTION 09 30 13, CERAMIC TILING					
Finish Code	Size	Shape	Pattern	Manufacturer	Mfg. Color Name/No.
W5	3"x6"	Field Tile	Matte	Daltile	0161 Urban Putty
B6	4 1/4" x 6"	Cove A-3461	Matte	Daltile	0161 Urban Putty
	2"x6"	Bullnose S-4269	Matte	Daltile	0161 Urban Putty

Wall to tile to be laid in a Straight Standard Set "stacked bond" pattern. Colors to be a mixed blend, as indicated.

2. SECTION 09 30 13, CERAMIC TILE GROUT		
Finish Code	Manufacturer	Mfg. Color Name/No.
	Custom Building Products	Polyblend Non-Sanded #135 Mushroom

Ceramic tile grout joints shall be 1/16".

3. SECTION 09 30 13, PORCELAIN TILE (PT)					
Finish Code	Size	Shape	Pattern	Manufacturer	Mfg. Color Name/No.
F4	12"x24"	Rectangular	Fabrique	Daltile	Gris Linen/P690 (unpolished)

Porcelain to tile to be laid in a Straight Standard Set "stacked bond" pattern.

4. SECTION 09 30 13, PORCELAIN TILE GROUT		
Finish Code	Manufacturer	Mfg. Color Name/No.
PT-G	Custom Building Products	Polyblend Nonsanded #185 New Taupe

Porcelain tile grout joints shall be 1/16".

5. SECTION 09 30 13, MARBLE THRESHOLDS		
Marble Type	Manufacturer	Mfg. Color Name/No.
Polished threshold	As submitted	To be selected from manufacturer's standard colors

B. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
CS1	Exposed Suspension System	White Aluminum (WA)	Armstrong	Al Prelude plus XL
CS2	Exposed Suspension System	Tech Black (BL)	Armstrong	Suprafine XL

C3	2x2 ACT	White	Armstrong	Cirrus Beveled Tegular 578 (Use with suspension system CS1)
C4	2x4 ACT	White	Armstrong	Cirrus Second Look II Beveled Tegular 513 (Use with suspension system CS1)
C5	2x2 Lay-in Wood Ceiling	Maple	USG	True Wood "Maple" (Use with suspension system CS2)
C8	2x2 ACT - Special Faced	White	Armstrong	Optima Health Zone Square Tegular 3316
C9	2x4 ACT - Special Faced	White	Armstrong	Optima Health Zone Square Tegular 3317

C. SECTION 09 65 16, VINYL SHEET FLOORING, HEAT WELDED SEAMS (WSF)

Finish Code	Pattern name	Manufacturer	Mfg. Color Name/No.
F2	Naturelife: Wood	Shaw	#05304 "Light Maple"
F5	Marmorette	Armstrong	#LP553 "Smoke"
F7	Marmorette	Armstrong	#LP554 "Smolder"
F8	Marmorette	Armstrong	#LP065 "Light Chocolate"
F9	Biolife	Shaw	#01018 "Peppercorn"
F10	Biolife	Shaw	#01019 "Thyme"

--

1. SECTION 09 65 16, WELDING RODS (WSF)		
Finish code (paired with vinyl flooring above)	Manufacturer	Mfg. Color Name/No.
F2	Shaw	To be selected from Mfg. standard colors
F5	Armstrong	W1253 "Wood Smoke"
F7	Armstrong	W1257 "Smoulder Gray"
F8	Armstrong	W1240 "Paperbag Tan"
F9	Shaw	WEL1018
F10	Shaw	WEL1019

2. SECTION 09 65 16, CAP STRIPS (WSF)		
Finish Code	Manufacturer	Mfg. Color Name/No.
	Per sheet vinyl manufacturer	To be selected from Mfg. standard colors

D. SECTION 09 65 13, RESILIENT BASE AND ACCESSORIES

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
B1	Rubber Base (RB)	6"	Johnsonite	80 Fawn
B2	Thermoplastic Rubber Profile Base	6"	Johnsonite	Mandalay 6" 80 Fawn

E. SECTION 09 68 00, CARPET (CP)

1. SECTION 09 68 00, CARPET EDGE STRIP			
Finish Code	Material	Manufacturer	Mfg. Color Name/No.
---	Vinyl	As submitted	Selected from mfg. standard colors

F. SECTION 09 68 00, CARPET MODULES (CFT)

Finish Code	Size	Pattern	Manufacturer	Mfg. Color Name/No.
F3	24" x 24"	Imprint #59592	Shaw	Moonlight #33761
F11	24" x 24"	Stereo #59250	Shaw	Metallic #507000

G. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units
Gloss Level 5	a traditional semi-gloss	35-70 units	
Gloss Level 6	a traditional gloss	70-85 units	
Gloss level 7	a high gloss	more than 85 units	

1. Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
P1	5	Kelly-Moore	KM3970-1 "Meadow Day"
P2	5	Kelly-Moore	Accent Color #1: TBD

P3	5	Kelly-Moore	Accent Color #2: TBD
P4	5	Kelly-Moore	Not Used
P5	5	Kelly-Moore	HLS4212-12 "Windsor Toffee"
2. Special Coatings code(SC)	Gloss	Manufacturer	Mfg. Color Name/No.
S	6	Kelly-Moore*	KM3969-1 "Campiello"

* Match manufactuer's color, as specified.

2.10 DIVISION 10 - SPECIALTIES

A. SECTION 10 25 13, PATIENT BED SRVICE WALLS

Item	Material	Manufacturer	Mfg. Color Name/No.
Face panels	Plastic Laminate	Wilsonite	Wilsonite #7909-60 "Fusion Maple"
Frame/Enclosure	Aluminum Alloy	HSI, Inc.	Powder coated to match Face Panels. Color to be selected by Architect

B. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

ITEM	MATERIAL	MANUFACTURER	MFG. COLOR NAME/NO.
Corner Guards	Stainless Steel	Construction Specialties	Stainless Steel
Wall Guards And Handrail	Stainless Steel	Construction Specialties	Stainless Steel
Wall Guard	Stainless Steel	Construction Specialties	Stainless Steel

C. SECTION 10 51 23, FLOOR OR BASE MOUNTED LOCKERS, PHENOLIC

Item	Material	Manufacturer	Mfg. Color Name/No.
Doors & Side panels	Phenolic	ASI Storage Solutions	To be selected from mfg. standard color selection

2.11 DIVISION II - EQUIPMENT

2.12 DIVISION 12- FURNISHINGS

A. SECTION 12 32 00, WOOD CASEWORK

Item Type	Location	Finish/Color
Plastic Laminate	All Casework	Wilsonite #7909-60 "Fusion Maple"

B. SECTION 12 36 00, COUNTERTOPS AND ACCESSORIES

Type	Finish/Color
Solid Surfacing	Corian "Sagebrush"
Stainless Steel	Per manufacturer
Molded Resin	Manufacturer's standard

2.13 DIVISION 13 - SPECIAL CONSTRUCTION

A. SECTION 13 05 41, SEISMIC RESTRAINT REQUIREMENTS FOR NON STRUCTURAL COMPONENTS

Item	Location	Finish	Color
As required	If exposed, Paint To Match Wall	Kelly Moore, Enviro Coat (No VOC), 1500 Series, 1520 semi-gloss, Acrylic Enamel.	Match wall

2.15 DIVISION 22 - PLUMBING

A. SECTION 22 40 00, PLUMBING FIXTURES AND TRIM

Item	Color
Water Closet P-103	White
Urinal P-201	White
Sink P-516	Stainless Steel
Lavatories P-408	White
Service Sink Corner P-502	To be selected from Mfg. standard colors
Surgeons Scrub Sink P-519	Stainless Steel
Kitchen Sink P-524	Stainless Steel
Sink P-528	Stainless Steel
Elec. Water Cooler P-609	Stainless Steel

2.16 DIVISION 26 - ELECTRICAL

A. SECTION 26 51 00, BUILDING LIGHTING INTERIOR

Fixture Type	Exterior Finish	Color
--------------	-----------------	-------

See Electrical Fixture Schedule	See Electrical Fixture Schedule	See Electrical Fixture Schedule

B.

REV 072213

PART III EXECUTION

3.1 ROOM FINISH SCHEDULE

A. Match adjoining or existing similar surfaces colors, textures or patterns where disturbed or damaged by alterations or new work when not scheduled.

B. ROOM FINISH SCHEDULE: See drawings for Room Finish Schedule.

--- E N D---