

VA249-13-Q-0427 Questions & Answers

1. CLIN 005- Are you wanting the vent piping ran individually and sized accordingly, or is the piping just being re-sized to fit what is already in place? **Piping is to be ran individually and sized accordingly.**
2. CLIN 008- This is 1 panel for each boiler equaling 4 panels in total, correct? **YES, this is correct.**
3. Is insulation work involved? **Possible, if you have to pull out the insertion meter in CLIN 0002 you will need to recalibrate meter and reinsulate. Also any insulation you pull off you must replace or repair to put back.**

The following changes have been made to the **SOW**:

1. The flame safeguard displays in item #10 should be for Boilers 1, 2, & 3 for a total of 3 displays not 4.
2. Item #12-14 have been edited to reflect actual number it is to refer to in the SOW.
3. Period of Performance has been edited to add the weekend work needed on the PRV work in item #11-14. This work can't be performed during the week.