



CONSTRUCTION NOTES

- 1 WALLS TO HAVE LEAD PAINT REMOVED
- 2 CEILING TO HAVE LEAD PAINT REMOVED TYP
- 3 BEAMS TO HAVE LEAD PAINT REMOVED
- 4 MISCELLANEOUS CONDUIT AND PIPING TO HAVE PAINT REMOVED TYP
- 5 ALL SURFACE REMOVED OF LEAD PAINT TO BE REPAINTED WITH NO VOC LATEX PAINT
- 6 FLOORS TO HAVE LEAD-BASED EPOXY FLOORING REMOVED
- 7 REPAINT EPOXY FLOORING AND SAFETY LINES

THESE DRAWINGS ARE NOT ALL INCLUSIVE AND ARE TO BE USED AS REFERENCE ONLY.
CONTRACTOR TO VERIFY ALL EXISTING FIELD CONDITIONS.
DRAWINGS ARE NOT TO BE USED AS CONTRACT DOCUMENTS.

VA MEDICAL CENTER ORLANDO, FLORIDA

Remove Lead Paint at Lake Baldwin Central Energy Plant

VHA NRM 675-14-600



Office of Construction & Facilities Management

Department of Veterans Affairs