

Addendum #3

1. Locker specification and associated drawings have been modified/updated:
 - Drawing A1 is issued to update the Locker Height in the equipment list.
 - Drawing A-3 is issued to update the Locker Height.
 - Drawing A-7 is issued to update the Locker Height and to update the glass block infill.
 - Specification Section 10 51 13 is issued to update the Locker Height in paragraph 2.1, B, 2.

	RFI Question	Answer
1	Section 096900, part 2, page 3 "products" calls for KIVA low profile system. Is Haworth Access Flooring an approved substitution? If yes to question 1, what would the floor covering be on the panels?	Flooring product should be equal to the specified product by meeting all specification and drawing requirements. Submittals will be reviewed and accepted or rejected after award.
2	What is the dimension from the floor to deck?	The existing floor to floor height in the area of work is 11'-0". The typical existing floor thickness in the area of work is 4 1/2". the floor to deck height varies.
3	Is there one (1) existing gun box to be relocated and one (1) new gun box to be furnished and installed? Please confirm.	There are 3 existing gun boxes to be relocated (an existing gun box consists of 16 individual lockable storage units.) and 2 new gun boxes to be furnished and installed. (New gun boxes consist of 8 individual storage units.)
4	Will the VA accept bids from ASHRAE CPMP certified Commissioning Agencies in lieu of the Building Commissioning Association CCP certification requirement as listed in the specification for this project?	Commissioning agents are hired by the contractor, not the VA. Commissioning Agent qualifications must meet the specifications, including agent verification.