



1D Section 5 - Stair Section @ Mechanical Room
1/2" = 1'-0"

3D Section 6 - Stair Section @ Mechanical Room
1/2" = 1'-0"



- | WALL SECTION KEYNOTES | |
|-----------------------|--|
| 1 | STRUCTURAL STEEL. REFERENCE STRUCTURAL. |
| 2 | EXISTING CONSTRUCTION. |
| 3 | STRUCTURAL PRECAST LINTEL. WINDOW HEAD. |
| 4 | PRECAST CONCRETE COPING. |
| 5 | ALUMINUM SINGLE HUNG WINDOW. REFERENCE SPECIFICATIONS |
| 6 | EIFS AT BOTTOM OF SOFFIT. EIFS OVER PLYWOOD AND 7/8" HAT CHANNELS. |
| 7 | EXPANSION JOINT. REFERENCE SPECIFICATIONS. |
| 8 | IN-FLI CONSTRUCTION TO MATCH EXISTING WALL ASSEMBLY. |
| 9 | COLUMN CAP. REFERENCE F7/AE502. |
| 10 | ARCHITECTURAL PRECAST SILL. |
| 11 | EXISTING STRUCTURE. REFERENCE STRUCTURAL. |
| 12 | CEILING. REFERENCE REFLECTED CEILING PLAN FOR INFORMATION |
| 13 | EXISTING WINDOW. |
| 14 | HOLLOW METAL DOOR AND FRAME. |
| 15 | EXISTING BRICK. |
| 16 | BRICK TIE @ 16" O.C. MAX. REF SPECIFICATIONS. |
| 17 | MECHANICAL EQUIPMENT. REFERENCE MECHANICAL. |
| 18 | MECHANICAL VENT. REFERENCE MECHANICAL. |
| 19 | GYPSUM BOARD BULKHEAD OR SOFFIT. |
| 20 | CAST IN PLACE CONCRETE STAIRWAY. |
| 21 | REINSTALLED HANDRAIL. PATCH AND REPAIR ALL WALL/SLAB PENETRATIONS. |
| 22 | REPLACE CONCRETE SLAB ON GRADE AS NECESSARY AFTER COLUMN INSTALLATION. |
| 23 | LIGHT FIXTURE. REFERENCE ELECTRICAL. |
| 24 | PNEUMATIC TUBE SYSTEM STATION. |
| 25 | PNEUMATIC TUBE SYSTEM TUBE PATHWAY. |
| 26 | SEAL AT ALL PENETRATIONS TO 2-HOUR RATING. |
| 27 | EXISTING HOLLOW METAL DOOR AND FRAME. |
| 28 | REINSTALL EXISTING HANDRAIL. |
| 29 | ISOLATION JOINT. REFERENCE F7/AE502. |
| 30 | PRECAST COLUMN COVER. REFERENCE DETAIL 7E/ AE503 |
| 31 | HANDRAIL BRACKET |

NOTE: NOT ALL KEYNOTES MAY BE USED ON EACH PLAN

**FULLY SPRINKLERED
100% CONSTRUCTION DOCUMENTS**

CONSULTANTS:



RPA Design
Suite 500
Charlotte, NC 28210
Phone 704-887-3500
Fax 704-887-3507



ARCHITECTS/ ENGINEERS:

TSP, Inc.
1112 N. West Ave,
Sioux Falls, SD 57104
phone: (605) 336-1160
fax: (605) 336-7926
www.teamtsp.com



To Solve. To Excel. Together.

Drawing Title
WALL SECTIONS

Approved: Project Director

Project Title	<p>Sioux Falls VA Health Care System Acute Inpatient Medical Unit Addition and Renovation</p>
---------------	--

Location	VA Medical Center 2501 W. 22nd Street, PO Box 5046 Sioux Falls, SD 57117-5046
-----------------	---

Date
08/06/12

Checked	RAH
---------	-----

Drawn
E00

Project Number
438-369

Building Number
5

Drawing Number

5-AE313
Dwg 34 of 123

**Office of
Construction
and Facilities
Management**

