



MECH DEMO GENERAL NOTES

- WHERE EQUIPMENT AND/OR FIXTURES ARE INDICATED TO BE REMOVED, THE EXISTING SERVICES SHALL BE CAPPED AND CONCEALED BEHIND FINISHED SURFACES. ABANDONED BRANCH SERVICES SHALL BE REMOVED BACK TO THE MAINS AND CAPPED. UNLESS OTHERWISE INDICATED.
- CAP ANY ABANDONED OR UNUSED PIPE AND/OR DUCT OPENINGS.
- THIS CONTRACTOR SHALL BE RESPONSIBLE FOR PATCHING AND PAINTING TO MATCH EXISTING WALLS, FLOORS, AND CEILINGS.
- HYDROING AND DOMESTIC PIPING SHALL BE PROPERLY AND THOROUGHLY CLEANED AND PUT INTO FURNISHMENT SERVICES.

PIPING DEMO KEYNOTES

- DEMO ALL PLUMBING FIXTURES SHOWN IN DASHED LINES. REMOVE PIPING BACK TO MAINS AND CAP. TYPICAL ALL.
- DEMO ALL PLUMBING PIPING SHOWN IN DASHED LINES BACK TO MAINS AND CAP. TYPICAL ALL.
- DEMO RADIANT CEILING PANELS, ASSOCIATED PIPING AND CONTROLS. REMOVE PIPING BACK TO MAINS AND CAP. TYPICAL ALL.
- DEMO THERMOSTATS, ASSOCIATED CONTROLS, CONTRA, PIPING AND CONTROL WIRING. TYPICAL ALL.
- DEMO ALL TUBING, VALVES, AND UNIT HEADERS. REMOVE PIPING BACK TO MAINS AND CAP. TYPICAL ALL.
- EXISTING CABINET UNIT HEATER TO REMAIN.
-
-
-
-
-

NOTE: NOT ALL KEYNOTES MAY BE USED ON EACH PLAN

1F

3RD FLOOR PIPING DEMOLITION PLAN

1/8" = 1'-0"

CONSULTANTS:

ARCHITECTS/ENGINEERS:

TSP Inc.

1112 N. West Ave.

Sioux Falls, SD 57104

phone: (605) 336-1160

fax: (605) 336-9293

www.tspinc.com

To Solve. To Excel. Together.

Drawing Title

3RD FLOOR PIPING DEMOLITION PLAN

Project Title

Sioux Falls VA Health Care System
Acute Inpatient Medical Unit Addition
and Renovation

Project Number

04100857

Building Number

5

Drawing Number

5-MD103

Dwg. of

76 of 123

Location

1112 N. West Ave.
Sioux Falls, SD 57104

Date

08/06/2012

Checked

BSW

Drawn

JTC

Approved: Project Director

Office of
Construction
and Facilities
Management

Department of
Veterans Affairs