

| PLUMBING FIXTURE SCHEDULE |                                       |            |        |           |        |            |        |           |        |                           |                           |                           |                    |   |
|---------------------------|---------------------------------------|------------|--------|-----------|--------|------------|--------|-----------|--------|---------------------------|---------------------------|---------------------------|--------------------|---|
| MARK                      | DESCRIPTION                           | WASTE PIPE |        | VENT PIPE |        | COLD WATER |        | HOT WATER |        | WASTE<br>FIXTURE<br>UNITS | WATER<br>FIXTURE<br>UNITS | WRIST<br>BLADE<br>HANDLES | ELECTRIC<br>SENSOR | REMARKS   |
|                           |                                       | IN         | [mm]   | IN        | [mm]   | IN         | [mm]   | IN        | [mm]   |                           |                           |                           |                    |   |
| P-101                     | WATER CLOSET- FLOOR MTD               | 3          | [ 75 ] | 2         | [ 50 ] | 1.25       | [ 31 ] |           |        | 6                         | 10                        | N/A                       | YES                |   |
| P-102                     | WATER CLOSET - FLOOR MTD              | 3          | [ 75 ] | 2         | [ 50 ] | 1.25       | [ 31 ] |           |        | 6                         | 10                        | N/A                       | NO                 | BED PAN WASHER  |
| P-114                     | BARIATRIC WATER CLOSET<br>FLOOR MTD   | 3          | [ 75 ] | 2         | [ 50 ] | 1.25       | [ 31 ] |           |        | 6                         | 10                        | N/A                       | NO                 | BED PAN WASHER  |
| P-413                     | LAVATORY - COUNTERTOP                 | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 | SOLID SURFACE COUNTER WITH INTEGRAL LAVATORY BY G.C.  |
| P-418                     | LAVATORY                              | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 |   |
| P-502                     | SINK SERVICE FLOOR MOUNTED            | 3          | [ 75 ] | 2         | [ 50 ] | .75        | [ 19 ] | .75       | [ 19 ] | 3                         | 4                         | N/A                       | NO                 |   |
| P-505                     | SINKSERVICE CLINIC                    | 3          | [ 75 ] | 2         | [ 50 ] | 1          | [ 25 ] | .75       | [ 19 ] | 3                         | 4                         | N/A                       | NO                 | RIM FLUSHING  |
| P-524                     | SINK - COUNTERTOP TWO<br>COMPARTMENT  | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 | DROP-IN TYPE STAINLESS STEEL SINK                     |
| P-528                     | SINK - UNDER-MOUNT ONE<br>COMPARTMENT | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 | UNDER-MOUNT STAINLESS STEEL SINK                      |
| P-528A                    | SINK - COUNTERTOP ONE<br>COMPARTMENT  | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 | DROP-IN TYPE STAINLESS STEEL SINK                     |
| P-528B                    | COUNTERTOP WITH INTEGRAL<br>SINK      | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 | STAINLESS STEEL COUNTERTOP WITH INTEGRAL SINK BY G.C. |
| P-701                     | SHOWER                                | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 |   |
| P-801                     | ROOF HYDRANT                          |            |        |           |        | 1          | [ 25 ] |           |        |                           | 4                         | N/A                       | NO                 | FREEZELESS TYPE WITH 1/8" DRAIN HOLE                  |
| P-809                     | DIALYSIS BOX                          | 2          | [ 50 ] | 1.5       | [ 38 ] | .5         | [ 13 ] | .5        | [ 13 ] | 2                         | 2                         | N/A                       | NO                 |   |

MARK

REVISION DESCRIPTION

DATE

CONSULTANTS:

REGISTERED PROFESSIONAL ENGINEER  
REG. NO. 9008  
BRIAN S. WEBSTER  
8/06/2012

ARCHITECTS/ ENGINEERS:

TSP, Inc.  
1112 N. West Ave.  
Sioux Falls, SD 57104  
phone: (605) 336-1160  
fax: (605) 336-7926  
www.teamtsp.com

TSP

To Solve. To Excel. Together.

Drawing Title  
PLUMBING SCHEDULES

Approved: Project Director

Project Title  
Sioux Falls VA Health Care System  
Acute Inpatient Medical Unit Addition  
and Renovation

Location  
VA Medical Center  
2801 W. 22nd Street, PO Box 5046  
Sioux Falls, SD 57117-5046

Date  
08/06/2012

Checked  
BSW

Drawn  
RAK

Project Number  
04100857

Building Number  
5

Drawing Number  
5-PL603  
Dwg. 72 of 123

Office of  
Construction  
and Facilities  
Management

Department of  
Veterans Affairs

VA FORM 08-6231

1

2

3

4

5

6

7

8

9

Copyright TSP, Inc. 2012

C:\Users\csalig\Documents\04100857\_VA\_MEP12\_Central\_csalig.rvt  
8/6/2012 12:09:46 PM