LIGHTING FIXTURE SCHEDULE (PER DEDUCT ALTERNATE #4)

ID	DESCRIPTION	ELEC DATA		LAMP DATA		BASIS OF DESIGN		MOUNT TYPE														NOTES
								LOCATION						ARRANGEMENT								
		LOAD VA	VOLTAGE	QTY	WATTAGE	MANUFACTURER	MODEL OR SERIES	CEILING	FLOOR	GROUND	POLE	ROOF	SUSPENDED	WALL	FLUSH	PEDESTAL	PENDANT	RECESSED	SURFACE	TRACK	MOUNTING HEIGHT	
AE	FLUORESCENT, RECESSED, EMERGENCY	63	277	3	17W T8	LITHONIA	2SP8G 3 17 A19 M277 1/3 GEB10PSH PAF EL14 USPOM	■										■			NOTE A	
B	FLUORESCENT, RECESSED	79	277	2	32W T8	LITHONIA	2SP8 G 2 32 A19 M277 GEB10PSH PAF USPOM	■										■			NOTE A	
BE	FLUORESCENT, RECESSED, EMERGENCY	79	277	2	32W T8	LITHONIA	2SP8 G 2 32 A19 M277 GEB10PSH PAF EL14 USPOM	■										■			NOTE A	
C	FLUORESCENT RECESSED	79	277	2	32W T8	LITHONIA	2SP8 G 2 32 A19 M277 GEB10PSH PAF USPOM	■										■			9'-0"	
CE	FLUORESCENT, RECESSED, EMERGENCY	79	277	2	32W T8	LITHONIA	2SP8 G 2 32 A19 M277 GEB10PSH PAF EL14 USPOM	■										■			9'-0"	
D	FLUORESCENT RECESSED	63	277	3	17W T8	LITHONIA	2SP8 3 17 A19 M277 1/3 GEB10PSH PAF USPOM	■										■			9'-0"	
DE	FLUOR., RECESSED, EMERGENCY	63	277	3	17W T8	LITHONIA	2SP8 317 A19 M277 1/3 GEB10PSH PAF EL14 USPOM	■										■			NOTE A	
F	CANOPY LIGHTING	50	277	1	50W LED	LITHONIA	VGRSC 50LED MVOLT DDBT USPOM LPI	■										■			NOTE A	
G	FLUOR. STRIPLIGHT, LENSED, LED	79	277	2	32W T8	LITHONIA	AF 2 32 M277 GEB10PSH PAF USPOM	■											■		NOTE A	HANGING MATERIALS BY OTHERS
GE	FLUOR. STRIPLIGHT, LENSED, EMER	79	277	2	32W T8	LITHONIA	AF 2 32 277 GEB10PSH PAF EL14 USPOM	■											■		9'-0"	HANGING MATERIALS BY OTHERS
P1/M1	PATHWAY	18	120	1	13W QUAD	PATHWAY	MP1-W-F-H-P-8-SC USPOM	■									■				15'-0"	AIRCRAFT CABLE WITH HOOK
P2	ORIGINAL CAST LIGHTING	153	277	4	32W TT	OCL	FB1-P1AA-24-BC/GW-PTD-6TT32-277-DML-EC05%-SPECIFY OAH	■									■				9'-6"	AIRCRAFT CABLE WITH HOOK
P3	ORIGINAL CAST LIGHTING	307	277	8	32W TT	OCL	FB1-P1AA-48-BC/GW-PTD-8TT32-277-DML-EC05%-SPECIFY OAH	■									■				14'-8"	AIRCRAFT CABLE WITH HOOK
D2	FLUOR. RECESSED DOWNLIGHT, WET LISTED	35	277	1	32W TRT	LITHONIA	LGFV 32TRT 6RW FFL M277 USPOM	■										■			9'-0"	
D3	FLUOR. RECESSED DOWNLIGHT, WET LISTED	28	277	1	26W TRT	LITHONIA	AF 1/26TRT8AR LD M277 USPOM	■										■			10'-8"	
D3E	LED, RECESSED DOWNLIGHT, EMER.	30	277	1	28W TRT	LITHONIA	AF 1/26TRT8AR LD M277 EL USPOM	■										■			10'-8"	
D4	FLUORESCENT, RECESSED CAN	55	277	2	26W TRT	LITHONIA	AF 2/26TRT 8AR LD M277 USPOM	■										■			A	
D5	FLUORESCENT, RECESSED CAN	55	277	2	26W TRT	LITHONIA	AF 2/26TRT 8AR LD M277 USPOM	■										■			11'-0"	
D6	FLUORESCENT, RECESSED CAN	55	277	2	26W TRT	LITHONIA	AF 2/26DTT 6AR LD M277 USPOM	■										■			8'-0"	
J1	SITE LIGHTING, LED	300	277	1	300W LED	LITHONIA	DSX2 LED 100C 700 40K T3M M277 DDBXD USPOM				■								■		25'-0"	W/ LYTEPOLE POLE CAT.# 405-7015 -5-D1-F(150 MPH WIND RATING)W/CAMERA MOD FOR 8 POLES
J2	SITE LIGHTING, LED	600	277	2	300W LED	LITHONIA	DSX2 LED 100C 700 40K T3M M277 DDBXD USPOM				■								■		25'-0"	W/ LYTEPOLE POLE CAT.# 405-7015-25-D2-F(150 MPH WIND RATING), W/ CAMERA MOD FOR 1 POLE
M	12" SQ. RECESSED WET LISTED	32	277	1	32W TRT	LITHONIA	LAF 1/32TRT-12SB-FFL-M277 USPOM	■											■		10'-0"	
N	8' WALL MTD. COVE INDIRECT	153	277	4	12'-10"	FOCALPOINT	FVRW-ACR-DR4-1T5HO-1C-277-E-DC-WH-8	■													12'-10"	VERIFY CABLE LENGTH, EMERGENCY BATTERY PACKS WHERE SHOWN ON DRAWINGS
W	WALL MOUNTED, FLUORESCENT	16	277	1	16W T5	KENALL	FNL6 36 DB CP 38L 35K 1 DV LEL						■						■		9'-0"	VERIFY CABLE LENGTH
W2	WALL MOUNTED, FLUORESCENT	32	277	1	32W T5	KENALL	FNL672T DB CP 76L 35K 1 DV LEL						■						■		9'-0"	
XE1	LED, EXIT, SINGLE FACE	6	277	1	–	LITHONIA	SOLO W 1 GMR SD USPOM	■						■					■		9'-0"	
XE2	LED, EXIT, DOUBLE FACE	6	277	1	–	LITHONIA	SOLO W 2 GMR SD USPOM	■						■					■		9'-0"	(DIRECTIONAL INDICATOR AS REQ'D)
XIU	X-RAY IN USE, FIXTURE	6	277	1	–	LITHONIA	LE P W 1 R 277 SW16 "X-RAY IN USE"	■											■		9'-0"	"X-RAY IN USE" LABELED
						PATHWAY	MP1 XX H P 8 SC USPOM															

FIXTURE SCHEDULE NOTES:

A. FIXTURE INSTALLED AT VARIOUS ELEVATIONS. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT ELEVATIONS.

B. OUTDOOR FIXTURES SHALL HAVE FACTORY BRONZE FINISH.

C. INDOOR FIXTURES SHALL HAVE FACTORY WHITE FINISH

D. ALL FIXTURES MUST BE U.S. POINT OF MANUFACTURE

E. ALL EMERGENCY BATTERY BACK-UP FIXTURES SHALL ALSO BE NIGHT-LIGHT ENABLED.

FINAL SUBMISSION / FULLY SPRINKLERED

Revisions: | Date

CONSULTANTS:

CIVIL:
KENNETH HORNE & ASSOCIATES
7201 NORTH 9TH AVENUE, STE. 6
PENSACOLA, FLORIDA 32504
PH: (850) 471-9005
FX: (850) 471-0093

LANDSCAPE ARCHITECT:
CSA GROUP, INC.
6300 PICCADILLY SQUARE DRIVE
MOBILE, ALABAMA 36609
PH: (251) 344-4023
FX: (251) 344-4052

COMM/IDS:
SCHMIDT CONSULTING GROUP, INC.
40 S. PALAFOX PLACE, STE. 300
PENSACOLA, FLORIDA 32502
PH: (850) 438-0050
FX: (850) 432-8631

SURVEYORS:
KCI TECHNOLOGIES, INC.
10401 HIGHLAND MANOR DRIVE, SUITE 120
TAMPA, FLORIDA 33610
PH: (813) 740-2300

W.N. BOLTON CERTIFICATE NO. 56537 STATE OF FLORIDA PROFESSIONAL ENGINEER

ARCHITECT/ENGINEERS:

BES DESIGN/BUILD

BES DESIGN/BUILD, LLC
766 Middle St, Fairhope, AL 36532
Phone: 251.990.5778 Fax: 251.990.3716

Drawing Title: LIGHTING FIXTURE SCHEDULE

Approved: Project Director

Project Title: CONSTRUCT VA OUTPATIENT CLINIC, PANAMA CITY

Location: PANAMA CITY, FLORIDA

Date: APRIL 2013 | Checked: KDE | Drawn: GWS

Project Number: 520-326

Building Number: -

Drawing Number: EL103A4
Dwg. 5 of 6

Office of Construction and Facilities Management
Department of Veterans Affairs

VA FORM 08-6231