

ROOM FINISH SCHEDULE CONTINUED																							
ROOM NO.	ROOM NAME	FLOOR		BASE		WALLS												MILLWORK		CEILING		REMARKS	
		MAT	FIN	MAT	FIN	NORTH			EAST			SOUTH			WEST			MAT	COLOR	MAT	COLOR		
						MAT	FIN	COLOR	MAT	FIN	COLOR	MAT	FIN	COLOR	MAT	FIN	COLOR						
C28	CORR.	SVT	1-2	RB	1	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1	R3	
C29	CORR.	SVT	1-2	RB	1	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1	R3	
C30	CASE MGR. OFF.	CPT	1	RB	4	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C31A	CLEAN UTIL.	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C31B	MED. RM.	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C32	CASE MGR. OFF.	CPT	2	RB	4	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C33	CASE MGR. OFF.	CPT	2	RB	4	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C34	CASE MGR. OFF.	CPT	2	RB	4	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C35	CORR.	SVT	1-2	RB	1	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1	R3	
C36	LINEN, STRETCHER, MEDICAL EQUIP. STOR.	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C37	CASE MGR. OFF.	CPT	2	RB	4	GWB	P	8	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C38	EXAM RM	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	10	GWB	P	8			AT	1		
C39	EXAM RM	SVT	1	RB	1	GWB	P	12	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C40	EXAM RM	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	11	GWB	P	8			AT	1		
C41	EXAM RM	SVT	1	RB	1	GWB	P	11	GWB	P	8	GWB	P	8	GWB	P	8			AT	1		
C42	EXAM RM	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	12	GWB	P	8			AT	1		
C43	PT TLT	PT	1	PT	1	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6			AT	1	R1, R19	
C44	EXAM RM	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	10	GWB	P	8			AT	1		
C45	EXAM RM	SVT	1	RB	1	GWB	P	8	GWB	P	8	GWB	P	11	GWB	P	8			AT	1		
D01	R.O.I.	CPT	1	RB	4	GWB	P	1	GWB	P	1	GWB	P	1	GWB	P	1			AT	1		
D02	CIRCULATION	SVT	1	RB	2	GWB	P	1	GWB	P	1	GWB	P	1	GWB	P	1			AT	1	R3	
D03	RECEP.	CPT	2	RB	4	GWB	P	1	GWB	P	1	GWB	P	1	GWB	P	1	S-PL	3-2	AT-P	1-1	R9	
D04	TECHS	CPT	2	RB	4	GWB	P	1	GWB	P	1	GWB	P	1	GWB	P	1	S-PL	3-2	AT-P	1-1	R9	
D05	CORR.	SVT	1	RB	2	GWB	P	1	GWB	P	1	GWB	P	1	GWB	P	1			AT	1		
D06	S. UTILITY	SVT	1	RB	2	GWB	P	1	GWB	P	1	GWB	P	1	GWB	P	1			AT	1		
D07	RADIOLOGY	SVT	1	RB	2	GWB	P	1	GWB	P	2	GWB	P	1	GWB	P	1	S-PL	3-2	AT	2	R 11	
D07A	PT. TLT	PT	1	PT	1	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6			AT	1	R1, 19	
D08	CLEAN STG	SVT	1	RB	2	GWB	P	1	GWB	P	1	GWB	P	1	GWB	P	1			AT	1		
D09	ULTRASOUND	SVT	1	RB	2	GWB	P	2	GWB	P	2	GWB	P	2	GWB	P	2	S-PL	3-2	AT	1		
D10	PT. TLT	PT	1	PT	1	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6			AT	1	R1, 19	
D11	DRESS	SVT	1	RB	2	GWB	P	2	GWB	P	2	GWB	P	2	GWB	P	2	PL	1	AT	1		
D12	MED. RM.	SVT	1	RB	2	GWB	P	2	GWB	P	2	GWB	P	2	GWB	P	2	S-PL	3-2	AT	1		
D13	CORR.	WM-WSF	1-1	RB	5	GWB	P-WG	15-1/2	GWB	P-WG	15-1/2	GWB	P-WG	15-1/2	GWB	P-WG	15-1/2			AT	1	R3, 5, 15	
D14	WOMEN'S ST. TLT	PT	1	PT	1	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	S-PL	3-2	AT	1	R1, 7, 8, 18	
D15	SHOWER	PT	1	PT	1	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6			P	P16	R1, 6, 12, 18	
D16	MEN'S ST. TLT	PT	1	PT	1	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	S-PL	3-2	AT	1	R1, 7, 8, 18	
D17	SHOWER	PT	1	PT	1	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6	CBB	CT-P	1-6			P	P16	R1, 6, 12, 18	
D18	BREAK RM.	PT	1	PT	1	GWB	P	6	GWB	P	6	GWB	P	6	GWB	P	6	S-PL	3-2	AT	1	R3, 9, 19	
D19	LOCKER/KIT.	PT	1	PT	1	GWB	P	6	GWB	P	6	GWB	P	6	GWB	P	6			AT	1	R3, 9, 14, 19	
D20	COMM. RM	C		RB	1	GWB	P	15	GWB	P	15	GWB	P	15	GWB	P	15			EXP	P15		
D21	ELEC. SYS.	SVT	1	RB	1	GWB	P	15	GWB	P	15	GWB	P	15	GWB	P	15			AT	1		
D22	HAC	PT	1	RB	1	GWB	CT-P	1-6	GWB	CT-P	1-6	GWB	CT-P	1-6	GWB	CT-P	1-6			AT	1	R1, 19	
D23	MECHANICAL	C		-			P	15		P	15		P	15		P	15			EXP	P15		
D24	ELECTRICAL	C		-			P	15		P	15		P	15		P	15			EXP	P15		

ROOM FINISH / COLOR SCHEDULE KEY

- AP - ACRYLIC PANELS
- 3'FORM VARIA ECORESIN, TIMBER LATITUDE, NATURAL
 - DESIGNTEX FUSION; ILLUMINATION AP057, FRONT FINISH: PATENT, BACK FINISH: PATINA, 1/8" GAUGE.
 - 3'FORM VARIA ECORESIN; COLOR: SABLE

- AT - ACOUSTICAL CEILING (TILE)
- ARMSTRONG, HEALTHZONE ULTIMA, ITEM NO.1937, BEVELED REGULAR, INSTALLED WITH ARMSTRONG PRELUDE 15/16" SUSPENSION SYSTEM, NRC-0.70, CAC 35, CLASS A, FINE TEXTURE SURFACE, WASHABLE AND SCRUBBABLE, SEMIGLOSS SURFACE.
 - ARMSTRONG, HEALTHZONE ULTIMA, ITEM NO.1937, BEVELED REGULAR, INSTALLED WITH ARMSTRONG PRELUDE 15/16" SUSPENSION SYSTEM, NRC-0.70, CAC35, CLASS A, FINE TEXTURE SURFACE, WASHABLE AND SCRUBBABLE, SEMIGLOSS SURFACE. CLIPPED DOWN INSTALLATION.

C - CONCRETE, SEALED

CBB - CONCRETE BACKER BOARD

CMU - CONCRETE MASONRY UNIT

- CPT - CARPET TILE
- MANNINGTON COMMERCIAL, PATTERN: SYLVAN STRUCTURES I, COLOR: AERIE(1315), TIP SHEARED PATTERNED LOOP, SOLUTION DYED, 100% ANTRON LUMENA TYPE 6.6 NYLON. INSTALL IN ASHLAR PATTERN. 24" SQUARE TILES.
 - MANNINGTON COMMERCIAL, PATTERN: SYLVAN STRUCTURES II, COLOR: AERIE(1315), TIP SHEARED PATTERNED LOOP, SOLUTION DYED, 100% ANTRON LUMENA TYPE 6.6 NYLON. INSTALL IN QUARTER TURN PATTERN. 24" SQUARE TILES.
 - TANDUS, PATTERN: ATMOSPHERE 03666, COLOR: GOLDEN PAGODA 49512, PATTERNED LOOP, 100% ANTRON LEGACY NYLON, 24" SQUARE MODULAR TILE. INSTALL IN RANDOM MODULAR METHOD.

CT - CERAMIC WALL TILE

- DALTILE, PATTERN: AYERS ROCK, COLOR: AY04 MAJESTIC MOUND, FIELD TILE: 13"x13" (33.3X33.3CM) BORDER TILE: 3X3 MOSAIC TILE WITH 3"x13" BULLNOSE TILE CAP.

EXP - EXPOSED

- GR- GROUT
- CUSTOM BUILDING PRODUCTS; 386 OYSTER GRAY

GWB - GYPSUM WALL BOARD SYSTEMS

- MB - MINI BLINDS
- LEVOLOR CONTRACT; 1" RIVIERA BLINDS, COLOR: 201 IVORY

MS - METAL SOFFIT

- P - PAINT; SHERWIN WILLIAMS IS THE PREFERRED PAINT SOURCE. PAINT COLORS NOT INDICATED AS SHERWIN WILLIAMS TO BE MATCHED BY THE MANUFACTURER.
- SHERWIN WILLIAMS; SW7573 EAGLET BEIGE
 - GLIDDENICI; 549 GOLDEN CHAMPAGNE
 - BENJAMIN MOORE; 1553 EQUESTRIAN GRAY
 - BENJAMIN MOORE; 516 IVY LEAGUE
 - NOT USED
 - SHERWIN WILLIAMS; SW6106 KLIM BEIGE
 - SHERWIN WILLIAMS; SW6105 DEVINE WHITE
 - SHERWIN WILLIAMS; SW6141 SOFTER TAN
 - NOT USED
 - SHERWIN WILLIAMS; SW6170 TECHNO GRAY
 - SHERWIN WILLIAMS; SW7057 SILVER STRAND
 - SHERWIN WILLIAMS; SW6161 NONCHALANT WHITE
 - SHERWIN WILLIAMS; SW7003 TOQUE WHITE
 - SHERWIN WILLIAMS; SW7648 BIG CHILL
 - SHERWIN WILLIAMS; SW6378 CRISP LINEN
 - BENJAMIN MOORE; 2159-70 WHITE CLOUD
 - BENJAMIN MOORE; 955 BERBER WHITE
 - PPG; DURANAR COATING, 513-6 DARK ASH

PL - PLASTIC LAMINATE

- FORMICA; 3696-58 SHOJI SCREEN
- NEVAMAR; TM2001T OCHRE TEMPERA
- WILSONART; 10745-60 FONTHILL PEAR
- PIONITE; AFTERNOON SHOWERS HP360 SUEDE
- NEVAMAR; S2085T ENGLISH LACE
- WILSONART; 1531-60 LIGHT BEIGE
- NEVAMAR; S7036T PRECISION WHITE

PT - PORCELAIN TILE (FLOOR AND BASE)

- DALTILE, PATTERN: AYERS ROCK, COLOR: AY04 MAJESTIC MOUND, 13"x13" (33.3 X 33.3 CM) FIELD TILE, 3/8" THICK; RANDOM SHADE VARIATION

RB - RESILIENT BASE, 6" COVE

- ROPPE; 632 FLAX
- FLEXCO; 05 CORNSILK
- ROPPE; 174 SMOKE
- ROPPE; 114 LUNAR DUST
- ROPPE; 131 BISQUE

S- SOLID SURFACE MATERIAL

- ZODIAQ; MOSSY GREEN
- CORIAN; RICE PAPER
- CORIAN; AURORA
- CORIAN; OLIVITE
- GIBRALTAR; FROSTY WHITE MIRAGE 1573MG
- CORIAN; BISQUE

WSF - WELDED SEAM SHEET FLOORING

- MANNINGTON COMMERCIAL, PATTERN: BIOSPEC MD, HOMOGENEOUS SHEET FLOORING. 6'0"(1.83M) WIDTH, COLOR: BUTTERMILK 15360, THICKNESS: .080 (2.03MM). INSTALLED WITH HEAT WELDED SEAMS.
- MANNINGTON COMMERCIAL, PATTERN: BIOSPEC MD, HOMOGENEOUS SHEET FLOORING. 6'0"(1.83M) WIDTH, COLOR: NEW GLACIER 15364 THICKNESS: .080 (2.03MM). INSTALLED WITH HEAT WELDED SEAMS.
- MANNINGTON COMMERCIAL, PATTERN: BIOSPEC MD, HOMOGENEOUS SHEET FLOORING. 6'0"(1.83M) WIDTH, COLOR: SAPPHIRE 15409 THICKNESS: .080 (2.03MM). INSTALLED WITH HEAT WELDED SEAMS.

SVT - SOLID VINYL FLOORING

- 1- MANNINGTON COMMERCIAL, PATTERN: NATURE'S PATH PLANK, COLOR: WINDSOR OAK 12115 GUNSTOCK, 6"x36" (152.5 X 914.5MM) PLANKS, .100" (2.5MM) THICK, QUANTUM GUARD HP URETHANE ALUMINUM OXIDE TOPCOAT, UV CURED. POLISH OR BUFFING NOT REQUIRED
- 2- MANNINGTON COMMERCIAL, PATTERN: NATURE'S PATH PLANK, COLOR: HERITAGE CHERRY 12106 NATURAL, 6"x36" (152.5 X 914.5MM) PLANKS, .100"(2.5MM) THICK, QUANTUM GUARD HP URETHANE ALUMINUM OXIDE TOPCOAT, UV CURED. POLISH OR BUFFING NOT REQUIRED

SOLAR SHADES

- MECHOSHADE; EUROVEIL 5300 SERIES BASKETWEAVE, COLOR: SAND 5304, 5% OPENNESS FACTOR, WITH VALANCE.

TP - TOILET PARTITIONS

- CAPE COD SYSTEMS, STAINLESS STEEL TOILET AND URINAL PARTITIONS, #4 BRUSHED FINISH. TOILET PARTITIONS CEILING HUNG, URINAL SCREEN WALL SUPPORTED.

WG - WALL GUARD

- CS GROUP WALL GUARD CHAIRRAIL, SCR.80E, 8" X 1 3/8", ACROVYN 3000 COVER WITH END CAPS. COLOR: 310 YOSEMITE SAND.
- CS GROUP, ACROVYN 4000 WALL COVERING, 040" THICK ACROVYN, TEXTURED FINISH, SHEETS APPLIED AT WAINSCOT HEIGHT. SEE DETAIL 3, SHEET IS600. COLOR: 310 YOSEMITE SAND, SUEDE TEXTURE.
- CS GROUP WALL GUARD CHAIRRAIL, 6", SCR48N48S SURFACE, ACROVYN 3000 COVER WITH END CAPS. COLOR: 310 YOSEMITE SAND
- CS GROUP CORNER GUARDS, SURFACE MOUNTED, SM-20, PEBBLETTE TEXTURE, 1/4" RADIUS CORNER, 3" WINGS. INSTALL AT 48" AFF. COLOR: SEE GENERAL NOTE 14.
- CS GROUP, ACROVYN SCR-50, COLOR: #100 EGGSHELL
- CS GROUP, ACROVYN WALL COVERING, .040" THICK SHEET, TEXTURE FINISH: DADO, COLOR: 480 TOFFEE. INSTALL WITH DADO TEXTURE RUNNING HORIZONTALLY.

WM - WALK OFF MAT

- CS GROUP, PEDITRED LB GB LOW PROFILE GRID WITH ROLL BACK CAPABILITIES. 1/2" DEPTH USED WITH 3/4" LEVEL BASE FRAME. 750 LB PER WHEEL ROLLING CAPACITY. ALUMINUM RAILS, BLACK EPDM CONNECTOR, RUBBER TREAD INSERTS. COLOR: 1014 GO POUND SAND ECO SURFACES ECOSAND.

WSF - WELDED SEAM SHEET FLOORING

- MANNINGTON COMMERCIAL, PATTERN: BIOSPEC MD, HOMOGENEOUS SHEET FLOORING. 6'0"(1.83M) WIDTH, COLOR: BUTTERMILK 15360, THICKNESS: .080 (2.03MM). INSTALLED WITH HEAT WELDED SEAMS.
- MANNINGTON COMMERCIAL, PATTERN: BIOSPEC MD, HOMOGENEOUS SHEET FLOORING. 6'0"(1.83M) WIDTH, COLOR: NEW GLACIER 15364 THICKNESS: .080 (2.03MM). INSTALLED WITH HEAT WELDED SEAMS.
- MANNINGTON COMMERCIAL, PATTERN: BIOSPEC MD, HOMOGENEOUS SHEET FLOORING. 6'0"(1.83M) WIDTH, COLOR: SAPPHIRE 15409 THICKNESS: .080 (2.03MM). INSTALLED WITH HEAT WELDED SEAMS.

REMARKS

R1. PORCELAIN WALL TILE, CT1, TO BE INSTALLED 4'-3" HIGH WITH PAINT PT6 ABOVE. SEE ELEVATION ON SHEET IS600.

R2. SEE FINISH PLANS SHEET IS121.

R3. INSTALL ACRYLIC FACED SURFACE MOUNTED CORNER GUARDS AND CHAIR RAIL. INSTALL CORNER GUARDS ON ALL OUTSIDE CORNERS.

R4. INSTALL PLASTIC LAMINATE, PL5 ON VERTICAL SIDE WALLS AT EACH CHECK IN STATION.

R5. WALLS TO RECEIVE ACROVYN ACRYLIC PANELS AS WAINSCOTING EXTENDING FROM TOP OF BASE TO BUMPER GUARD - APPROX. 36" H. PAINT ABOVE. SEE ELEVATIONS SHEET IS-600.

R6. SHOWER SURROUND TO BE SOLID SURFACE PANELS, EXTENDING FULL HEIGHT TO THE CEILING. SHOWER PAN TO BE TERRAZZO.

R7. COUNTER TO BE SOLID SURFACE, S3.

R8. TOILET PARTITIONS TO BE TEXTURED STAINLESS STEEL, TP1.

R9. CABINETS TO BE PLASTIC LAMINATE PL2 WITH SOLID SURFACE COUNTER TOPS, S3.

R10. NOT USED.

R11. SEE SHEET AS-101 FOR PARTITION TYPE LEGEND TO IDENTIFY SHIELDING REQUIREMENTS IN RADIOLOGY.

R12. FOLLOW MANUFACTURERS RECOMMENDATION FOR SUBSTRATE TO BE USED AT SOLID SURFACE SHOWER WALL PANELS.

R13. CABINETS TO BE PLASTIC LAMINATE PL6 WITH SOLID SURFACE COUNTERTOPS S2.

R14. LOCKERS TO BE PENCO, COLOR: 826 SLATE BLUE

R15. WALK OFF MAT TO EXTEND 10'-0" U.N.O. INTO BLDG FROM ENTRY DOOR & FULL WIDTH @ VESTIBULES AND CORRIDORS

R16. DESK COUNTER TOP TO BE SOLID SURFACE S1. CASEWORK TO BE PLASTIC LAMINATE PL4.

R17. SOLID SURFACE S5, PLASTIC LAMINATE PL3.

R18. MUD SET INSTALLATION FOR FLOOR TILE, THIN SET FOR WALL TILE.