



- ① PROVIDE NEW AIR HANDLER UNIT ON 4" THICK REINFORCED CONCRETE MAINTENANCE PAD. PAD TO EXTEND A MINIMUM OF 6" BEYOND UNIT FOOTPRINT. SEE SCHEDULE SHEET FOR ADDITIONAL INFORMATION.
- ② VAV BOX ABOVE CEILING. (TYP.)
- ③ PROVIDE NEW AIR COOLED CHILLER ON 4" THICK REINFORCED CONCRETE MAINTENANCE PAD. PAD TO EXTEND A MINIMUM OF 6" BEYOND UNIT FOOTPRINT. SEE SCHEDULE SHEET FOR ADDITIONAL INFORMATION.
- ④ LINEAR DIFFUSER. (TYP.)
- ⑤ BULL HEAD TEE WITH VANES. (BHTV)
- ⑥ 90° ELBOW WITH FIVE VANES (E-90-5V)
- ⑦ ALL SUPPLY, RETURN AND OUTSIDE AIR TAKE-OFFS SHALL INCLUDE BALANCING DAMPER WITH INSULATING STANDOFF

SCALE:  $1/8" = 1'-0"$

VA FORM 08-6231