

three inches = one foot
 one and one-half inch = one foot
 one inch = one foot
 three-quarters inch = one foot
 one-half inch = one foot
 one-quarter inch = one foot
 three-eighths inch = one foot
 one-eighth inch = one foot
 one-quarter inch = one foot
 one-eighth inch = one foot

C:\V\133959\A11-Kitchen_Central_Imagery.rvt
 8/7/2013 11:18:47 PM

NO.	REVISIONS	DATE
ADDENDUM No. 2		08/07/2013

PROJECT TEAM

ARCHITECTURAL: HDR Architecture, Inc. 185 Plaza 444 Cedar St Suite 1900 St. Paul, MN 55101 www.hdrinc.com 612-524-6000	MECHANICAL/ELECTRICAL/PLUMBING: HDR Architecture, Inc. 23 Second Street SW Suite 1900 Rochester, MN 55902-3017 www.hdrinc.com 507-535-8200	STRUCTURAL: HDR Architecture Inc. 8404 Indian Hills Drive Omaha, NE 68114-4108 www.hdrinc.com 402-339-1000	CIVIL SURVEYOR: Anderson Engineering of MN 1305- 1st Avenue North Suite 100 Plymouth, MN 55441 St. Paul, MN 55101 www.aem.com 763-412-4000	FIRE PROTECTION: Summit Fire Consulting 573 Monhegan Ave NE St. Paul, MN 55103 www.summitfire.com 651-251-1855	COMMISSIONING AGENCY: Engineering Design Initiative 1112 North 5th Street Minneapolis, MN 55411 www.edi.com 612-343-9865	ENVIRONMENTAL SERVICES: EWR Incorporated 6301 E. River Road Suite 114 Minneapolis, MN 55421 www.ewr.com 763-277-3200	FOOD SERVICE DESIGN & CONSULTING: Robert Rippe Associates, Inc. 6117 Blue Circle Drive Suite 100 Minneapolis, MN 55343-9108 www.rippa.com 952-933-0313
--	---	--	--	--	--	---	---

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.
 PRINT NAME: **MARK A. JASMIN**
 SIGNATURE: *[Signature]*
 DATE: **1/22/2013** LICENSE # **18698**

ARCHITECTS/ENGINEERS



Drawing Title INTERIOR FINISH SCHEDULE	Project Number 656-321 / 133959
Approved: Project Director	Building Number NKB
Location 4801 Veterans Drive, St. Cloud, MN 56303	Drawing Number AS-71
Date 12/09/2011	Checked by ETD
	Drawn Leanne Tanguay

Office of Construction and Facilities Management
 Department of Veterans Affairs

VOLUME I FULLY SPRINKLERED

GENERAL NOTES:

- COLOR IS A VERY IMPORTANT PART OF THIS PROJECT. ANY COLOR SUBSTITUTE SHALL BE REQUESTED FROM THE ARCHITECT. PROVIDE CONSISTENT MATERIAL COLORS AND PATTERNS IN EACH ROOM OR AREA. IF REQUIRED FOR CONSISTENCY, PROVIDE MATERIALS FROM SAME PRODUCTION RUN.
- CEILING HEIGHT INDICATED IN FEET-INCHES; 9 FEET - 0 INCHES.
- WHERE ITEMS OR SURFACES ARE NOT SPECIFICALLY MENTIONED, PAINT THE SAME AS SIMILAR ADJACENT MATERIALS OR AREA. IF COLOR OR FINISH IS NOT DESIGNATED, ARCHITECT WILL SELECT FROM STANDARD COLORS OR FINISHES AVAILABLE.
- UNLESS OTHERWISE INDICATED, DO NOT INCLUDE PAINTING WHEN FACTORY-FINISHING OR INSTALLER FINISHING IS SPECIFIED FOR SUCH ITEMS AS, BUT NOT LIMITED TO, METAL, TOILET ENCLOSURE, PRE-FINISHED PARTITION SYSTEMS, ACOUSTIC MATERIALS, ARCHITECTURAL WOODWORK AND CASEWORK, STAINLESS STEEL ELEVATOR ENTRANCE DOORS AND FRAMES, INCLUDING LIGHT FIXTURES, SWITCHGEAR AND DISTRIBUTION CABINETS.
- GRILLES, DIFFUSERS, ELECTRICAL PANELS, ACCESS PANELS, ETC., WHICH ARE EXPOSED IN FINISH SPACES SHALL BE PAINTED TO MATCH THE SURFACE ON WHICH THEY OCCUR.
- PAINT INTERIOR SURFACES OF DUCTS FLAT BLACK WHERE SURFACES ARE VISIBLE THROUGH GRILLS OR DIFFUSERS.
- UNLESS OTHERWISE INDICATED, METAL SURFACES OF ANODIZED ALUMINUM, STAINLESS STEEL, CHROMIUM PLATE, COPPER, BRONZE AND SIMILAR FINISHED MATERIALS WILL NOT REQUIRE FINISH PAINTING.
- IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS, PROVIDE FOUR SAMPLES OF EACH COLOR AND MATERIAL AS REQUIRED FOR APPROVAL. RESUBMIT SAMPLES AS REQUESTED BY ARCHITECT UNTIL ACCEPTABLE SHEEN, COLOR, AND TEXTURE IS ACHIEVED.
- PLASTIC LAMINATE COLORS SHALL BE VERIFIED ON ALL APPROVED MILLWORK AND DRAWINGS.
- ALL PLASTIC LAMINATE MILLWORK SHALL BE PL-1. ALL COUNTER TOPS SHALL BE PL-2 EXCEPT AS NOTED.
- HOLLOW METAL DOORS AND HOLLOW METAL FRAMES SHALL BE PAINTED PNTLO-4 IN ALL AREAS.
- COORDINATE WITH CONCRETE CURING METHOD. SEE SECTION 03 30 00.
- PROVIDE WATER VAPOR EMISSION CONTROL SYSTEM FOR CONCRETE WITH APPLIED FLOORING. SEE SECTION 03 30 00.
- ENTRANCE DOORS AND FRAMES TO ELEVATORS, EXCEPT THOSE THAT ARE PRE-FINISHED STAINLESS STEEL, SHALL BE PAINTED PNTLO-4 IN ALL AREAS.
- SOFFIT BOTTOMS SHALL MATCH ADJACENT WALL FINISH.
- ALL WALL GUARDS, CORNER GUARDS AND HANDRAILS (SECTION 10 28 00) SHALL BE ACRYLVN CORPORATION. COLOR: EGGSHELL #R125, UNLESS NOTED OTHERWISE.
- ALL WINDOW SILLS SHALL BE MASONRY BLOCK AT MASONRY BLOCK WALL CONDITIONS. ALL WINDOW SILLS SHALL BE SSF-1 AT ALL GYP WALL BOARD CONDITIONS.
- ALL MILLWORK TO HAVE EDGE BANDING TO MATCH CORRESPONDING LAMINATE.
- PROVIDE CT BORDER BEHIND ALL MIRRORS, PAPER TOWEL DISPENSERS, OR OTHER SURFACE MOUNTED ITEMS THAT EXTEND ABOVE AND BELOW THE CT WAINGSCOT WITH THE CORRESPONDING CT MATERIAL. SEE ELEVATIONS.
- ALL FULL GYP. CEILINGS SHALL BE PNT-2 IN WET AREA CONDITIONS, UNLESS NOTED OTHERWISE.
- ALL TILE SHALL RECEIVE EPOXY GROUT. TEC GROUT. SERIES: ACCUCOLOR EFX, COLOR: RIVER ROCK #990.
- ALL EXPOSED BURNISHED BLOCK AND ROCKFACE BLOCK SURFACE ARE TO BE FACTORY FINISHED.

ARCHITECTURAL FINISH LEGEND

FINISH CODE	KEYNOTE	COLOR	DESCRIPTION	COMMENTS
DOOR AND FRAMES				
ALUM		DARK BRONZE	ANNOZED ALUMINUM FRAME	
SPANDREL PANEL				
SEU-2	08 80 00-2.4-D		SPANDREL PANEL	
WINDOW GLAZING				
G-2	08 81 00-2.1-C	CLEAR	FIRE-RATED GLASS	
G-3	08 80 00-2.2-A	CLEAR	CLEAR TEMPERED GLASS	
SEU-1	08 80 00-2.4-C	GRAY	INSULATING GLASS (LOW E)	

09 60 00_ Stair Schedule

Type	Width	egress width provided	egress width required	Top Level	Base Level	Minimum Tread Depth	Actual Riser Height	Actual Number of Risers
South Stair	42"	42"	42"	FIRST FLOOR	BASEMENT	11"	6 21/32"	24
Concrete - SouthEast Exit	48"	48"	42"	FIRST FLOOR	FIRST FLOOR	12"	5 27/32"	7
Concrete - NorthEast Exit	48"	48"	42"	FIRST FLOOR	BASEMENT	12"	5 5/16"	7
Northwest Stair	36"	36"	42"	FIRST FLOOR	FIRST FLOOR	11"	6 27/32"	7
Northwest Stair	42"	42"	42"	FIRST FLOOR	BASEMENT	11"	7"	16
Concrete - Existing Building 8 Egress	48"	48"	42"	FIRST FLOOR	BLDGB_BASEMENT	10"	6 15/32"	13

FINISH LEGEND

FINISH CODE	KEYNOTE	MANUFACTURER	MANUFACTURER #	COLOR	QUALITY	DESCRIPTION	COMMENTS
ACOUSTICAL & CEILING TILE MATERIAL							
AM-1	09 51 00	USG	"F" FISSURED #131	WHITE	MEDIUM TEXTURE PANEL	ACOUSTIC CEILING TILE 24" X 24"	OFFICES AND CORRIDOR
AM-2	09 51 00	USG	CLEAN ROOM CLIMA PLUS #56090; W/ HOLD DOWN CLIPS	WHITE	SMOOTH TEXTURE. CLASS 100	ACOUSTIC CEILING TILE 24" X 24"	KITCHEN
BURNISHED BLOCK							
MB-1	04 20 00	ANCHOR		LIMESTONE	BURNISHED	SIZE MAY VARY - SEE WALL TYPES	FIELD - DINING AND CORRIDOR
MB-3	04 20 00	ANCHOR		CHOCOLATE	BURNISHED	SIZE MAY VARY - SEE WALL TYPES	BASE - DINING AND CORRIDOR
CARPET TILE							
CPTT-1	09 68 00	BOLYU	IMG75	COSMIC CARAMEL	PATTERNED CUT/LOOP	PATTERN: IMAGETRY TILE	OFFICES: INCLUDES CARPET BASE
CERAMIC TILE							
CT-1	09 30 00	DAL TILE	#0761	MT URBAN PUTTY	MATTE	4" x 4"	FIELD
CT-2	09 30 00	DAL TILE	40%-0148, 30%-0144, 30%-0166	40%-SPA, 30%-ARTISAN BROWN, 30%-ELEMENTAL TAN	GLOSS	4" x 4"	ACCENT WALL TILE
CT-3	09 30 00	DAL TILE	#0761	MT URBAN PUTTY	MATTE	COVE BASE 4" x 6"	FIELD
DECORATIVE POLYMER FABRICATION							
DPF-1	DIVISION 09	3-FORM		HARVEST W/ LINEA VERT	SANDSTONE	OFF	DINING ROOM WALL PANEL
ENGINEERED QUARTZ FABRICATION							
EQF-1	DIVISION 09	CAMBRIA	#5110	WILLISTON		QUARRY COLLECTION	SERVERY COUNTER TOP
PAINT (EPOXY)							
PNTE-1	09 91 00	BENJAMIN MOORE	HC-45	SHAKER BEIGE	EGGSHELL FINISH	EPOXY	TOILET AREAS
PAINT (LOW VOC)							
PNTLO-1	09 91 00	BENJAMIN MOORE	HC-45	SHAKER BEIGE	EGGSHELL FINISH		FIELD
PNTLO-2	09 91 00	BENJAMIN MOORE	962	GRAY MIST	EGGSHELL FINISH		BACK OF HOUSE
PNTLO-3	09 91 00	BENJAMIN MOORE	2128-30	EVENING DOVE	EGGSHELL FINISH		DINING SOFFIT
PNTLO-4	09 91 00	BENJAMIN MOORE	HC-85	FAIRVIEW TAUPE	SEMIGLOSS		DOOR AND FRAMES
PAINT (SPECIAL COATING)							
SC-1	09 96 59	SHERWIN WILLIAMS	AQUARMOR COATING	MATCH PNTLO-1 SHAKER BEIGE	60 GLOSS METER		HIGH BUILD GLAZED COATINGS
PLASTIC LAMINATE							
PL-1	DIVISION 09	PIONITE	WM155	SUGAR MAPLE II	SUEDE FINISH	3MM EDGE BANDING TO MATCH	FIELD
PL-2	DIVISION 09	FORMICA	#7708-58	FAUX GAUZE	MATTE FINISH	3MM EDGE BANDING TO MATCH	COUNTER TOP
PORCELAIN TILE							
PT-1	09 30 00	AMERICAN OLEAN	#A94	WILLOW SPECKLED	UNGLAZED COLORBODY	2"x2" MOSAIC	TOILET AREA FLOORING
QUARRY TILE							
QT-1	09 30 00	DAL TILE	0Q48	ARID FLASH	SMOOTH	6" x 6"	KITCHEN
QT-2	09 30 00	DAL TILE	0Q48 - O-3565	ARID FLASH	SMOOTH	COVE BASE 6" x 6"	BASE
QT-3	09 30 00	DAL TILE	1/2 MIX OF: 0Q42 & 0Q48	1/2 RANDOM MIX OF ARID GRAY & ARID FLASH	SMOOTH	6" x 6", INSTALL RANDOM PATTERN	DINING ROOM
QT-4	09 30 00	DAL TILE	0Q76	GRAY SURETREAD	TEXTURED	6" x 6" SURETREAD	SLIP RESISTANT TREAD
RESILIENT BASE							
RB-1	09 65 00	VPI		TAUPE #14		FIELD BASE	
RESILIENT TILE							
RT-1	09 65 00	ARMSTRONG	IMPERIAL TEXTURE #51868	SMOKEY BROWN		12X12 TILE	FIELD
RT-2	09 65 00	ARMSTRONG	IMPERIAL TEXTURE #51916	DUTCH DELFT		12X12 TILE	ACCENT
RT-3	09 65 00	ARMSTRONG	IMPERIAL TEXTURE #51805	CAMEL BEIGE		12X12 TILE	ACCENT
RT-4	09 65 00	ARMSTRONG	IMPERIAL TEXTURE #51839	FORTRESS WHITE		12X12 TILE	BACK OF HOUSE
RESINOUS FLOORING							
RES-6A	09 67 23.60	BASF	DEGACLAD CQ	CAPE COD GRAY (QC 4)	NON-SKID TEXTURE	MONOLITHIC, MULTI-COMPONENT URETHANE CHEMISTRY RESINOUS FLOORING SYSTEM	REFRIGERATOR & FREEZER
RES-6B	09 67 23.60	BASF	DEGACLAD CQ	CAPE COD GRAY (QC 4)	NON-SKID TEXTURE	EPOXY RESINOUS TROWELED MORTAR	FOOD PREPARATION AND PRODUCTION AREAS
ROCK FACE BLOCK							
MB-2	04 20 00	ANCHOR		CHOCOLATE	ROCK FACE	SIZE MAY VARY - SEE WALL TYPES	ACCENT
RUBBER FLOOR TILE							
RFT-1	09 65 00	JOHNSONITE	CITYSCAPES (GREENWICH COLLECTION)	#543 HOTEL SPECKLED	HAMMERED TEXTURE	24" X 24" X 1/8" THICK	ELEVATOR FLOOR
S. CONC							
Concrete - Cast-in-Place Concrete S. CONC	03 30 00			MATCH EXISTING SURROUNDINGS	CLASS B FINISH ABOVE GRAE		
SOLID SURFACE FABRICATIONS							
SSF-1	12 36 00	CORAIN		VENARO WHITE	SOLID SURFACE FABRICATION		WINDOW SILLS
WALL PROTECTION SPECIALTIES							
CG-1	N/A	C/S ACRYOVN	HRB-4C	EGGSHELL #R125	SHADOWGRAIN	CORNER GAURD	OFFICES
CG-2	N/A	C/S ACRYOVN	CO-8	STAINLESS STEEL	#304 ALLOY W/ #4 SATIN FINISH	CORNER GAURD	FIELD
CG-3	N/A	C/S ACRYOVN	SCO-8	STAINLESS STEEL	#304 ALLOY W/ #4 SATIN FINISH	16 GA, 8"W END GAURD (FELID VERIFY WIDTH)	FIELD
CG-4	N/A	C/S ACRYOVN	SCO-8	STAINLESS STEEL	#304 ALLOY W/ #4 SATIN FINISH	16 GA, 10"W END GAURD (FELID VERIFY WIDTH)	FIELD
CR-1	10 26 00	ACROVYN	HRB-3C	EGGSHELL #R125	SMOOTH	CRASH RAIL	FIELD
HR-1	10 26 00	ACROVYN	HRB-4C	EGGSHELL #R125	SMOOTH	HAND RAIL	FIELD

ALTERNATE NO. 5:
 CHANGE FLOOR MATERIAL QT-1 TO FLUID APPLIED FLOORING (RES-6A & RES-6B) PER NOURISH ROOM 014, RECEIVE/RETURN ROOM 016 ON BASEMENT LEVEL, SEE FINISH PLANS..

ALTERNATE NO. 6:
 CHANGE FLOOR MATERIAL QT-3, AND QT-4 TO V.C.T. PER DINING ROOM 102 ON FIRST FLOOR LEVEL, SEE FINISH PLANS.

ALTERNATE NO. 8:
 CHANGE FLOOR MATERIAL QT-1 TO FLUID APPLIED FLOORING (RES-6A & RES-6B) PER FOOD PREP ROOM 143 ON FIRST FLOOR LEVEL, SEE FINISH PLANS.