

The following items are attached hereto: Specifications:

Large Sheets Volume 1:

AS-71

AMENDMENT NO. 2

TO PLANS & SPECIFICATIONS  
FOR  
GENERAL CONSTRUCTION  
FIRE PROTECTION WORK  
MECHANICAL WORK  
ELECTRICAL WORK  
ABATEMENT WORK

FOR  
St. Cloud VA Health Care System  
Expand Primary & Specialty Care Clinics / Reconfigure Support Space  
ST CLOUD, MINNESOTA

Acknowledge receipt of this Amendment by recording number and date of issue in the Bid Form. Failure to do so may subject bidder to disqualification.

**CHANGES TO SPECIFICATIONS**

**General Project Clarification**

1. For piping: no mechanical fittings and or joints are allowed on this project.

**VOLUME 1 DRAWINGS**

**CHANGES TO ARCHITECTURAL DRAWINGS**

**AS-71 INTERIOR FINISH SCHEDULE**

1. Revise FINISH LEGEND.

**QUESTIONS FROM BIDDERS**

1. Q. Is Storage 003 supposed to be included in Alternate Deduct No. 5? (*Sheet AS-72 details Storage 003 to be included in Alt. 5 but Storage 003 is not included in the schedule of alternates for Alt. 5.*)
  - a. Storage 003 is included in Alternate Deduct No. 5 as shown on sheet AS-72 in the original issued Construction Documents.
2. Q. Which QT is supposed to be used on the floor, in Dining 102? (*Sheet AS-73 details QT 3,4 on the floors.*) If both QT 3,4 are used please clarify locations.
  - a. See AS-73 - Addendum 1 issued 8/2/2013.
3. Q. Which QT is supposed to be used on the floor, in Serving 104? (*Sheet AS-73 details QT-3,4 but also notes QT-1.*)
  - a. See AS-73 - Addendum 1 issued 8/2/2013.
4. Q. What is the pattern for QT-3? (*The interior finish schedule shows 3 colors to be mixed for QT-3*)
  - a. QT-3 pattern is to be a random mix - See revised finish schedule issued 8/7/2013 for clarification.
5. Q. Is the floor finish VCT or CT in the alcove area between Corridor 101 and Toilets 107/108?

Amendment No. 2  
St. Cloud VA Health Care System  
Expand Primary & Specialty Care Clinics / Reconfigure Support Space  
St. Cloud, MN  
August 7<sup>th</sup>, 2013

- a. See AS-73 - Addendum 1 issued 8/2/2013.
- 6. Q. Please clarify which products will be used in Toilets 107/108. (*Floors are detailed for PT-1 and PT-1 is not in the Interior Finish Schedule. Walls are detailed for CT-1 (4" field) and CT-2 (4" base) and the Base is detailed for CT-3 (4" accent).*)
  - a. See revised finish schedule issued 8/7/2013 for clarification.
- 7. Q. Are there any Ceramic or Quarry tile areas where the concrete is recessed and a mud float will be required?
  - a. Concrete is not recessed - See transition detail C5/AS-60 - Addendum 1 issued 8/2/2013.

**END OF MODIFICATION**