



THIS PAGE ONLY SHOWS THE NEW WORK  
BEING PERFORMED BY VAPAHCS IN ORDER  
TO PROVIDE CONNECTION TO DEFENDER'S  
LODGE, INCLUDING INSTALLATION OF  
MANHOLES PMH-16A AND PMH-16B



5.63 PROVIDE NEW FEEDERS IN NEW DUCT BANK.  
3#350KCMIL AND 1 #4G PER FEEDERS.

5.67 PROVIDE NEW 6-WAY (MINIMUM) 600A  
J-BAR

5.63 NOT USED

5.63 NOT USED

5.65 FUTURE CONNECTION MANHOLE FOR SS-2  
AND BLDG 6. MANHOLE SHALL HAVE  
EXPANSION CAPACITY FOR ADDITIONAL  
△ J-BAR CONNECTIONS BEYOND 6 POINTS.

5.66 PROVIDE NEW FEEDERS IN NEW DUCT BANK.  
3#2/0G AND 1 #1/0G PER FEEDER.

5.67 PROVIDE NEW 6-WAY (MINIMUM) 200A  
J-BAR

5.66 PROVIDE NEW 6-WAY (MINIMUM) 600A /200A  
J-BAR WITH FUSE LINK

CONSULTANTS:	

	ARCHITECT/ENGINEERS:

Office of  
Construction  
and Facilities  
Management

 Department of  
Veterans Affairs