



LEGEND:

- ENHANCE (E) STEEL CONNECTION, SEE TYP. MOMENT CONN. DETAILS
- △ A, B, C, ETC. - SEE COLLECTOR SCHEDULE 5/SS531. <SLRS>

SHEET NOTES:

1. REPLACE (E) MECHANICAL EQUIPMENT WITH NEW SIMILAR UNITS OR SIMILAR WEIGHT/DIMENSION, S.M.D.
2. FOR EXISTING FRAMING SIZES CONTRACTOR TO VERIFY WITH EXISTING DRAWINGS AND VERIFY IN FIELD.
3. ITEMS NOTED <SLRS> ARE PART OF THE SEISMIC LOAD RESISTING SYSTEM AS INDICATED IN THE SPECIFICATIONS.

KEY NOTES:

- 1 ADD BENT PLATE ANCHORED TO SLAB AND WALL, SEE DETAIL 3/SS513.
- 2 SEE TYPICAL BEAM TO BEAM CONNECTION DETAIL, SIMILAR.
- 3 CONTINUE BENT PL & ANCHORS BENEATH COLLECTOR △ AND TERMINATE AT EDGE OF CONC. WALL.
- 3A (N) CONCRETE COLLECTOR BEAM AT FLOOR LEVEL LANDING BEAM.
- 3B (N) CONCRETE COLLECTOR BEAM AT INTER-FLOOR LANDING BM ABOVE.
- 4 7/8"Ø NELSON STUDS @ 12" O.C. ON (E) BM. SEE 5/SS513
- 5 TYPICAL FULL-DEPTH BM-TO-BM CONNECTION AT END OF COLLECTOR, SEE 3/SS111.
- 6 NOT USED
- 7 COLLECTOR-TO-WALL CONNECTION, SEE 3/SS514.
- 8 FOR EXISTING SLAB INFORMATION, SEE 13/SS121.
- 9 W12x19 BRACING BM WITH TYPICAL FULL-DEPTH CONNECTION EACH END PROVIDE 3/4" DIA. CORED STUDS @ 12" O.C. ON BEAM, SEE 5/SS513.
- 10 NOT USED
- 11 NOT USED
- 12 HSS 6x6x1/2 POST, 2ND FLOOR BM TO 3RD FLOOR BM. SEE 9/SS517 FOR CONN. T&B
- 13 SEE 12/SS515 FOR 2ND FLOOR SHADING DEVICE CONNECTIONS.
- 14 W16x31 W/ 7/8"Ø STUDS @ 12" O.C. SEE 5/SS513 SIM.

1 SECOND FLOOR FRAMING PLAN
1/8" = 1'-0"

CONSULTANTS:

Degenkolb
 DEGENKOLB ENGINEERS
 235 Montgomery Street, Suite 500
 San Francisco, CA 94104
 415.392.6952 Phone
 415.544.0792 Fax
 www.degenkolb.com
 80584020.00



ARCHITECT/ENGINEERS:

HMC Architects
 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720
 T 559 322 2444 / www.hmcarchitects.com



Drawing Title
SECOND FLOOR FRAMING PLAN
 Approved Project Director

Project Title
BUILDING 24 SEISMIC CORRECTION AND ADDITION
 Location
VAMC FRESNO, CA

Project Number
570-215
 Building Number
24
 Drawing Number
SF202
 Dwg. 11 of 176

Office of Construction and Facilities Management

Revisions	Date
2	7/25/19
1	7/22/19