

CLINICAL TEACHING LABORATORY - PLAN 2/SS203A

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb, U.O.N.)
F1	BIOHAZARD FRIDGE	2'-4"	1'-4"	5'-0"	3/- SIM (FRONT) AND 5/- SIM (REAR)	500
F2	BIOHAZARD FRIDGE	4'-0"	4'-0"	6'-2"	8/- SIM (FRONT) AND 5/- SIM (REAR)	2700
F3	ACID STORAGE	5'-0"	1'-2"	1'-4"	9/-	500
F4	FUME HOOD	4'-6"	3'-0"	10'-0"	5/- T&B	3000
F5	WATER BATH	1'-0"	1'-0"	0'-8"	9/-	500
F6	FUME HOOD	6'-0"	3'-6"	10'-0"	5/-	4500
F7	BASE CABINET	4'-0"	1'-10"	3'-0"	3/-	600
F8	COUNTERTOP SHELVES	4'-0"	1'-4"	4'-0"	3/- AND 15/- SIM	800
F9	LOCK-UP CABINET	3'-0"	1'-10"	7'-0"	3/- AND 5/-	1300
F10	STORAGE CABINET	4'-0"	1'-10"	7'-0"	3/- AND 5/-	1300
F11	STORAGE CABINET	4'-0"	1'-10"	7'-0"	3/- AND 5/-	1300
F12	MICROSCOPE	1'-0"	1'-4"	1'-6"	7/- OR 9/-	100
F13	POWER SOURCE	0'-8"	1'-2"	0'-6"	9/-	300
F14	MICROSCOPE	1'-0"	1'-4"	1'-6"	7/- OR 9/-	100
F15	"SHARP" BOX	0'-10"	0'-8"	0'-7"	9/-	500
F16	CENTRIFUGE	2'-6"	2'-6"	1'-0"	9/-	500
F17	SINK	5'-0"	2'-0"	3'-2"	3/-	500
F18	BIOHAZARD ROLLING GARBAGE BIN	2'-0"Ø		3'-0"	6/- SIM	500
F19	SCALE	0'-6"	1'-10"	1'-3"	9/-	300
F20	OLYMPUS MICROSCOPE	1'-0"	1'-4"	1'-6"	7/- OR 9/-	100
F21	SECTION CUTTER	1'-0"	2'-0"	1'-0"	9/-	300
F22	SAFETY SHOWER			7'-6"	13/- (BOT.)	500
F23	SPECTROPHOTOMETER	3'-6"	2'-0"	0'-10"	9/-	500
F24	MONOLIGHT 2010	1'-2"	1'-6"	0'-10"	9/-	500
F25	ULTRASONIC WASHER	0'-10"	0'-6"	0'-6"	9/-	300
F26	BIOHAZARD FRIDGE	2'-4"	1'-4"	5'-0"	3/-	500
F27	SINK	5'-0"	2'-0"	3'-2"	3/-	500
F28	CANTILEVERED SHELVING	1'-0"		3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ft
F29	CANTILEVERED SHELVING	1'-0"		3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ft
F30	CANTILEVERED SHELVING	1'-0"		3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ft
F31	WALL-MOUNTED CABINETS	1'-0"		4'-5"-7'-0"	5/- SIM, T&B	200 lbs/ft

STORAGE AREA - PLAN 2/SS203A

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
G1	BIOHAZARD FRIDGE	4'-0"	4'-0"	6'-2"	8/- (FRONT) AND 5/- (REAR)	2670
G2	EYE WASH	1'-0"Ø		3'-0"	13/- SIM	500
G3	SINK	5'-0"	2'-0"	3'-2"	3/-	500
G4	FREEZER	1'-8"	2'-0"	2'-6"	9/- AND 5/-	500
G5	GAS TANK	0'-8"Ø		3'-4"	11/-	250
G6	GAS TANK	0'-8"Ø		3'-4"	11/-	250
G7	GAS TANK	0'-8"Ø		3'-4"	11/-	250
G8	STORAGE CABINET	4'-0"	1'-10"	7'-0"	3/- AND 5/-	1300
G9	STORAGE CABINET	4'-0"	1'-10"	7'-0"	3/- AND 5/-	1300

AUDITORIUM - PLANS 1/SS201 AND 1/SS202

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
H1	TV	3'-0"	2'-6"	3'-0"	5/- SIM T&B OR 12/- SIM T&B	300
H2	PROJECTOR	2'-6"	2'-6"	1'-0"	3/- AND 5/-	250
H3	SERVER RACK	4'-0"	2'-0"	6'-3"	3/- AND 5/-	1000 (V.I.F.)
H4	HVAC INTAKE	8'-6"	6'-0"	4'-3"	3/-	1000 (V.I.F.)
H5	HVAC HANDLER	5'-0"	7'-0"	4'-0"	3/-	5000 (V.I.F.)

MECHANICAL PENTHOUSE - SHEET SS204

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
11	FAN	4'-0"	6'-0"	3'-6"	3/-	1000 (V.I.F.)
12	HANDLER	3'-0"	7'-0"	4'-0"	3/-	5000 (V.I.F.)
13	INTAKE	5'-0"	2'-0"	3'-2"	3/-	1000 (V.I.F.)
14	FAN	6'-0"	6'-0"	3'-8"	3/-	1000 (V.I.F.)

SHEET NOTES:

1. CONTRACTOR TO VERIFY ALL ITEMS NOTED IN THESE DRAWINGS.
CONTRACTOR TO RETAIN CALIFORNIA REGISTERED STRUCTURAL
ENGINEER TO PROVIDE BRACING/ ANCHORAGE DETAILS FOR
SUBMITTAL REVIEW BY DEGENKOLB.

2. TYPICAL DETAILS REFERENCED AS #- CAN BE FOUND ON SHEET SS541.

3. THE DETAILS REFERENCED IN THE ABOVE TABLES ARE ANCHORAGE APPROACHES TO BE VERIFIED BY THE CONTRACTOR'S ENGINEER AS INDICATED IN THE GENERAL NOTES AND IN SPECIFICATION SECTION 13 05 41.

LIBRARY MAIN ROOM - PLAN 1/SS201

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
A1	WALL-MOUNTED BOOK SHELF	18'-0"	1'-0"	6'-10"	6- SIM, T&B	2600
A2	NOT USED					
A3	NOT USED					
A4	NOT USED					
A5	NOT USED					
A6	NOT USED					
A7	NOT USED					
A8	NOT USED					
A9	NOT USED					
A10	NOT USED					
A11	NOT USED					
A12	NOT USED					
A13	NOT USED					
A14	WALL-MOUNTED BOOK CASE	3'-0"	1'-4"	6'-0"	5/- SIM, T&B	900

LIBRARY STUDY ROOM - PLAN 1/SS201

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
B1	WALL-MOUNTED BOOK SHELF	6'-0"	1'-2"	7'-6"	5/- SIM, T&B	1100
B2	WALL-MOUNTED BOOK SHELF	21'-0"	1'-2"	7'-6"	5/- SIM, T&B	3600
B3	WALL-MOUNTED BOOK SHELF	15'-0"	1'-2"	7'-6"	5/- SIM, T&B	2600
B4	WALL-MOUNTED BOOK SHELF	3'-0"	1'-2"	7'-6"	5/- SIM, T&B	600

LABORATORY - PLAN 1/SS203A

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb, U.O.N.)
C1	CANTILEVERED SHELVING		1'-0"	3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ ft.
C2	CANTILEVERED SHELVING		1'-0"	3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ ft.
C3	CANTILEVERED SHELVING		1'-0"	3'-8"-7'-0"	3/- AND 15/- SIM	200 lbs/ ft.
C4	WALL-MOUNTED CABINETS		1'-0"	4'-5"-7'-0"	5/- SIM, T&B	200 lbs/ ft.
C5	OLYMPUS CKX41 MICROSCOPE	1'-0"	1'-4"	1'-6"	7/- OR 9/-	100
C6	SORVALL BIOFUGE STRATOS	2'-1"	1'-11"	1'-3"	9/-	500
C7	LIGHTING BOX	1'-0"	0'-3"	0'-8"	9/- SIM	100
C8	SINK W/ BASE UNIT	5'-0"	2'-0"	3'-2"	3/-	500
C9	KENDROLAB PRODUCTS ISOTEMP	2'-2"	2'-0"	3'-5"	9/-	500
C10	BATHWATER EQUIP.	1'-2"	0'-10"	0'-7"	9/-	200
C11	ORBIT SHAKER	0'-10"	1'-1"	0'-7"	9/-	200
C12	HOT PLATE	0'-8"	0'-10"	0'-4"	9/-	100
C13	AB15PLUS PH METER	0'-5"	0'-7"	0'-3"	7/-	100
C14	SAFETY SHOWER			7'-6"	13/- (BOT.)	
C15	HOT PLATE	0'-8"	0'-10"	0'-4"	9/-	100
C16	MICROPLATE READER	1'-2"	1'-4"	0'-6"	9/-	200
C17	BIOHAZARD ROLLING GARBAGE BIN	2'-0"Ø		3'-0"	6/- SIM	500
C18	CENTRIFUGE	0'-9"Ø	0'-11"	9/-		250
C19	TROPICOOLER	1'-0"	0'-9"	0'-7"	9/-	200
C20	SINK W/ BASE UNIT	4'-0"	2'-0"	3'-2"	3/-	500
C21	FUME HOOD	4'-6"	2'-8"	7'-4"	1/- AND 12/-	1100

LABORATORY - PLAN 1/SS203A

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
D1	WALL-MOUNTED SHELVES	4'-0"	1'-1"	4'-6"-7'-0"	5/- SIM, T&B	700
D2	MICROTOME	0'-9"	1'-8"	1'-0"	9/-	200
D3	UNDERHUNG CABINETS	4'-0"	1'-10"	2'-0"	5/- SIM, T&B	400
D4	ROLLING CART	2'-3"	1'-6"	3'-5"	6/-	900
D5	YELLOW CABINET	3'-8"	1'-6"	5'-9"	1/- AND 5/-	700
D6	COUNTERTOP SHELVES	3'-0"	1'-0"	4'-0"	3/- AND 15/- SIM	300

CLINICAL TEACHING LABORATORY - PLAN 2/SS203A

ITEM#	DESCRIPTION	WIDTH	DEPTH	HEIGHT	NEW ANCHORAGE DETAILS	APPROX. WEIGHT (lb)
E1	FILING CABINET	3'-4"	1'-2"	7'-0"	3/- AND 5/-	1000
E2	WALL CABINET	3'-0"	1'-0"	2'-6"	5/- SIM, T&B	500
E3	REFRIDGERATOR	2'-4"	1'-4"	5'-0"	3/- (FRONT) AND 5/- (REAR)	500
E4	SPECTROPHOTOMETER	3'-6"	2'-0"	0'-10"	9/-	500
E5	PRINTER	1'-10"	2'-0"	2'-0"	9/-	300
E6	FUME HOOD	4'-0"	2'-0"	6'-8"	1/- AND 5/-	1100
E7	WATER BATH	0'-10"	1'-10"	2'-2"	9/-	500
E8	WATER BATH	0'-10"	1'-10"	2'-2"	9/-	500
E9	HYBRIDIZATION OVEN	1'-0"	1'-0"	1'-3"	9/-	300

[illegible]