



- FLOOR PLAN LEGEND**
- FULL HEIGHT METAL STUD @ 16" O.C. U.N.O. WITH SOUND BATT. INSULATION AND FINISHES FULL HEIGHT FROM FINISH FLOOR TO DECK ABOVE. REFER TO DETAIL 6, 7 & 8/AS906.
 - PARTIAL HEIGHT METAL STUD @ 16" O.C. U.N.O. WITH SOUND BATT. INSULATION AND FINISHES FROM FINISH FLOOR TO 2" ABOVE FINISH CEILING. REFER TO DETAIL 5/AS906.
 - (E) METAL STUD WALL WITH SOUND BATT INSULATION. WALL AND FINISHES FULL HEIGHT FROM FINISH FLOOR TO DECK ABOVE. REPLACE FINISHES WHERE NOTED.
 - (E) METAL STUD WALL WITH THERMAL INSULATION. WALL AND FINISHES FULL HEIGHT FROM FINISH FLOOR TO DECK ABOVE. REPLACE FINISHES WHERE NOTED.
 - (E) FULL HEIGHT STRUCTURAL CONCRETE WALL.
 - (E) METAL STUD WALL WITH SOUND BATT INSULATION. WALL AND FINISHES PARTIAL HEIGHT. REPLACE FINISHES WHERE NOTED.
 - (E) WORK STATION. FURNITURE PARTITION.
 - 1 HR FIRE BARRIER. WALL AND FINISHES FULL HEIGHT FROM FLOOR TO DECK ABOVE.
 - (E) 2 HR FIRE BARRIER. WALL AND FINISHES FULL HEIGHT FROM FLOOR TO DECK ABOVE.
 - WI DENOTES WALL TYPE. SEE 1/AS906.
 - 100A DENOTES DOOR. SEE SHEET AS901 AND AS902.
 - AZ DENOTES WINDOW. SEE SHEET AS903.
- FIRST FLOOR PLAN - REMODEL KEYNOTES**
- (1) GYPSUM WALLBOARD & RUBBER BASE OVER 2" RIGID INSULATION OVER (E) INSULATION, FROM FLOOR TO DECK TYPICAL AT EXTERIOR WALLS.
 - (2) (2) WHEEL CHAIR CLEAR FLOOR SPACE, SIDE ACCESS. 60" DEEP x 66" WIDE
 - (3) 36"x60" CLEAR LANDING AT BOTTOM OF RAMP.
 - (4) 36"x60" CLEAR LANDING AT TOP OF RAMP.
 - (5) LEVEL LANDING.
 - (6) REINSTALL (E) BOOKCASE.
 - (7) NOT USED
 - (8) OWNER TO REINSTALL ALL (E) WORKSTATIONS
 - (9) (E) SUNSCREEN ABOVE. REMOVE DEBRIS AND CLEAN VIA POWER WASH.
 - (10) AUTOMATIC/SELF-RISEING AUDITORIUM SEAT, TYP. (SHOWN IN RAISED POSITION)
 - (11) ASSISTIVE LISTENING SIGNAGE. REFER TO 10/AS912.
 - (12) TACTILE EXIT SIGN. REFER TO 8/AS912.
 - (13) ACCESSIBLE ENTRANCE SIGN (ISA SYMBOL) REFER TO DETAIL 3/AS912.
 - (14) CONCRETE RAMP
 - (15) GALVANIZED STEEL HANDRAIL
 - (16) COUNTERTOP, SEE DETAIL REFER TO 21/AS907.

	ARCHITECT/ENGINEERS: HMC Architects 1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720 T. 559.322.2444 / www.hmcarchitects.com		Drawing Title FIRST FLOOR PLAN		Project Title BUILDING 24 SEISMIC CORRECTION AND ADDITION		Project Number 570-215		Office of Construction and Facilities Management 	
	Revisions		Approved Project Director		Location VAMC FRESNO, CA		Building Number 24			
CONSULTANTS:						Date March 12, 2013		Checked BB	Drawn CLO	Drawing Number AS201 Dwg. 39 of 176