PLUMBING FIXTURE SCHEDULE

MARK	FIXTURE	S or W	V	CW	HW	DESCRIPTION
24-P-102	WATER CLOSET	3"	2"	1-1/2"	---	ZURN Z5655-BWL-BA FLOOR MOUNTED ELONGATED VITREOUS CHINA BOWL, SIPHON JET, 1-1/2" TOP SPUD, WITH ZURN Z5955SS-EL SEAT, Z6000AV-HET FLUSH VALVE, 1.6 GPF.
24-P-101	WATER CLOSET	3"	2"	1-1/2"	---	ZURN Z5665-BWL-BA FLOOR MOUNTED ELONGATED VITREOUS CHINA BOWL, SIPHON JET, 1-1/2" TOP SPUD, WITH ZURN Z5955SS-EL SEAT, Z6000AV-HET FLUSH VALVE. 1.6 GPF. MOUNT WITH TOP OF SEAT BETWEEN 17" & 19". UFAS COMPLIANT.
24-P-103	WATER CLOSET	3"	2"	1-1/2"	---	ZURN Z5615-BWL-BA-RF WALL MOUNTED ELONGATED VITREOUS CHINA BOWL, SIPHON JET, 1-1/2" TOP SPUD, WITH ZURN Z5955SS-EL SEAT, Z6000AV-HET FLUSH VALVE. 1.6 GPF. UFAS COMPLIANT.
24-P-104	WATER CLOSET	3"	2"	1-1/2"	---	ZURN Z5615-BWL-BA WALL MOUNTED ELONGATED VITREOUS CHINA BOWL, SIPHON JET, 1-1/2" TOP SPUD, WITH ZURN Z5955SS-EL SEAT, Z6000AV-HET FLUSH VALVE. 1.6 GPF.
24-P-202	URINAL	2"	1-1/2"	1/2"	---	ZURN Z5798-U-BA WALL MOUNTED VITREOUS CHINA, 3/4" TOP SPUD, WITH ZURN Z6003AV-ULF FLUSH VALVE, 0.125 GPF. UFAS COMPLIANT.
24-P-402	LAVATORY	2"	1-1/2"	1/2"	1/2"	ZURN Z5348-PED WALL-HUNG, 20"X18" VITREOUS CHINA WITH BACKSPLASH & WALL BRACKET, HOLES ON 8" CENTERS, ZURN Z831A-XL GOOSENECK FAUCET WITH 4" WRIST BLADE HANDLES MIXING VALVE. McGUIRE 155-A PERFORATED GRID DRAIN, P-TRAP, SPEEDWAY COMPRESSION WALL STOP & SUPPLY TUBING. MOUNT LAVATORY AT 29" ABOVE FINISHED FLOOR, UFAS COMPLIANT.
24-P-301	WATER HAMMER ARRESTER	---	---	VARIES	VARIES	SIOUX CHIEF 650 SERIES HYDRA-RESTER, SEAMLESS COPPER CHAMBER SUITABLE FOR CONCEALED INSTALLATION, PDI SIZE INDICATED ON PLANS. INSTALL PER MANUFACTURER RECOMMENDATION.
24-P-604	REFRIG. DRINKING FOUNTAIN	2"	1-1/2"	1/2"	---	ELKAY EZOSTLBC DUAL HEIGHT, S.S. TOP GALV. CABINET, FLEXIBLE BUBBLER, 8GPH RECOVERY, R-134A REFRIGERANT. UFAS COMPLIANT. 115V/ 1PH., 4.0 AMPS.
24-P-701	ROOF DRAIN/ OVERFLOW	3"	---	---	---	ZURN Z165 CAST IRON COMBINATION RD/OD WITH DECK PLATE, DOME GRATE OVER BOTH DRAINS AND 2" WATER DAM AT OVERFLOW.
24-P-519	HAND SINK	2"	1-1/2"	1/2"	1/2"	ADVANCED TABCO MODEL 7-PS-25, 16 GA. WALL HUNG, STAINLESS STEEL, SINGLE COMPARTMENT, 20"X20"X6-1/4" DEEP, 3-HOLE PUNCH WITH GRID STRAINER, ZURN Z6920-XL-CP4-F-MV BATTERY POWERED SENSOR FAUCET WITH 4" COVER PLATE, 0.5 GPM AERATOR & MIXING VALVE SET AT 110°F. SPEEDWAY COMPRESSION WALL STOPS AND SUPPLIES, P-TRAP, UFAS COMPLIANT.
24-P-806	HOSE BIBB	---	---	3/4"	---	WOODFORD Y24, BRASS FAUCET, LOOSE KEY HANDLE, NON-REMOVABLE VACUUM BREAKER & POLISHED CHROME FINISH.

1 PLUMBING SCHEDULES
SCALE: NTS

Revisions:	Date
2	7-25-2013
1	7-22-2013

CONSULTANTS:

REGISTERED PROFESSIONAL ENGINEER GABEN W. LENGERIN NO. 33380 MECHANICAL STATE OF CALIFORNIA

LP Consulting Engineers, Inc.
895 W. Ashlan Ave, Suite 101 Clovis, CA 93612
p 559-348-2130 - f 559-348-2131
www.lpengineers.com
Job #: 10-1698

LICENSED ARCHITECT STEVEN M. GRIFFITH NO. C-34897 REN. 07-31-15 STATE OF CALIFORNIA

ARCHITECT/ENGINEERS:

HMC Architects
1827 E. Fir Avenue, Studio 103 / Fresno, CA 93720
T 559 322 2444 / www.hmcarchitects.com

Drawing Title: PLUMBING SCHEDULES
Approved: Project Director
Project Title: BUILDING 24 SEISMIC CORRECTION AND ADDITION
Location: VAMC FRESNO, CA
Date: 7/26/2013 | Checked: K.K. | Drawn: D.N.
Project Number: 570-215
Building Number: 24
Drawing Number: PP600
Dwg. 108 of 176

Office of Construction and Facilities Management
Department of Veterans Affairs

VA FORM 08-6231