FOOTING SCHEDULE

(2500 PSF ALLOWABLE BEARING PRESSURE ASSUMED)

MARK	FOOTING SIZE	REINFORCING
F-1	4'-0" x 4'-0" x 1'-0"	5-#5 E.W. BOTTOM
F-2	5'-0" x 5'-0" x 1'-0"	6-#5 E.W. BOTTOM
F-3	6'-0" x 6'-0" x 1'-2"	6-#6 E.W. BOTTOM
F-4	6'-6" x 6'-6" x 1'-4"	8-#6 E.W. BOTTOM
F-5	7'-0" x 7'-0" x 1'-6"	9-#6 E.W. BOTTOM
F-6	8'-0" x 8'-0" x 1'-6"	9-#7 E.W. BOTTOM
F-7	8'-6" x 8'-6" x 2'-0"	10-#7 E.W. BOTTOM

TYPICAL LINTEL SCHEDULE

MARK	SIZE	SPAN	REMARK
L-1	(1) L7x4x3/8 (LLH)	UP TO 5'-0" CLEAR	TYPICAL AT EXTERIOR PUNCHED OPENINGS WITH METAL STUD BACKUP
L-2	CMU 8" DEEP PRECAST LINTEL, REINF W/ 2 #5, TOP & BOTTOM BRICK (1) L7x4x3/8 LLH	6'-1" TO 8'-0" CLEAR	
L-3	CMU 8" DEEP PRECAST LINTEL, REINF W/ 2 #5, TOP & BOTTOM	UP TO 5'-0" CLEAR	
L-4	HSS 6x4x1/4 (ROTATE 90°)	UP TO 3'-6" CLEAR	TYPICAL ABOVE LOUVERS

NOTES:

1) ALL LINTELS SHALL HAVE 6" MINIMUM BEARING AT EACH END. PROVIDE 16" LONG X 16" MIN. DEEP SOLID BEARING AT LINTEL ENDS. SOLID LINTEL BEARING SHALL CONSIST OF HOLLOW BLOCK FILLED SOLID W/ GROUT, TYPICAL.

2) PROVIDE LINTELS OVER ALL OPENINGS PER ABOVE, INCLUDING DOORS, WINDOWS, DUCTS LOUVERS, RECESSES, AND OTHER OPENING. UNLESS SHOWN OR NOTED OTHERWISE ON STRUCTURAL OR ARCHITECTURAL DRAWING.

3) FOR DIMENSIONS AND LOCATION OF OPENINGS, SEE ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS.

4) WRAP END OF LINTELS IN BUILDING PAPER AT CONTROL JOINTS.

5) ALL EXTERIOR LINTELS SHALL BE HOT DIPPED GALVANIZED.

STEEL COLUMN SCHEDULE - BUILDING

MARK	LOCATION	SIZE	BASEPLATE (txlxw)	ANCHORS	FOOTING	T/O FTG ELEVATION	T/O STEEL ELEVATION
1	S-1	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
2	M-1	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	21'-6 1/4"
3	K-1	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	27'-1 3/8"
4	J-1	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	22'-5 1/2"
5	D-1	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
6	S-1.9	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
7	K-2	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	27'-1 3/8"
8	Y-3	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
9	X-3	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
10	S-3	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
11	AA-4	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
12	Y-4	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
13	X-4	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	*16'-0"
14	K-3.1	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	27'-1 3/8"
15	R.3-3.9	HSS 8x8x1/4	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	15'-7 5/8"
16	V-7	HSS 8x8x1/4	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	19'-0 1/2"
17	L-8	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	23'-2"
18	AA-9	HSS 6x6x3/16	REFER TO DETAIL G/SF203		REFER TO DETAIL G/SF203		18'-4 5/8"
19	Z-9	HSS 6x6x3/16	REFER TO DETAIL G/SF203		REFER TO DETAIL G/SF203		18'-4 5/8"
20	Y-10	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	17'-1 1/4"
21	V-10	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	17'-1 1/4"
22	B-11	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
23	A-11	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
24	K-12	HSS 8x8x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	27'-1 3/8"
25	P-11.7	HSS 8x8x1/4	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	28'-7"
26	AA-13	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
27	Y-13	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
28	V-13	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	19'-0 1/2"
29	E-12	HSS 8x8x3/16	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	17'-0 5/8"
30	T-14	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	32'-6 3/4"
31	M-14	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-3	-0'-8"	32'-0 5/8"
32	A-15	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-1	-2'-0"	22'-0 5/8"
33	Y-16	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
34	J.8-17	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-1	-0'-8"	25'-11 3/4"
35	F-17	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	25'-11 3/4"
36	C-17	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	25'-11 3/4"
37	A-17	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-2'-0"	25'-11 3/4"
38	Y-18	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
39	T-19	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	32'-6 3/4"
40	M-19	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	32'-0 5/8"
41	G-19	HSS 8x8x3/16	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	19'-4"
42	A-18.9	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	19'-11 7/8"
43	AA-20	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
44	Y-20	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
45	V-20	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	19'-0 1/2"
46	P-21	HSS 8x8x1/4	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	28'-7"
47	B-22	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
48	A-22	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
49	K-20.1	HSS 8x8x1/4	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	27'-1 3/8"
50	AA-24	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	18'-4 5/8"
51	Y-24	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	18'-4 5/8"
52	V-25	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	17'-1"
53	U-25.8	HSS 8x8x1/4	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	21'-6"
54	N-26	HSS 8x8x3/8	1 1/2" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-3	-0'-8"	20'-9 7/8"
55	W-27	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-0'-8"	18'-10 1/2"
56	K-28	HSS 8x8x1/4	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-2	-0'-8"	27'-1 3/8"
57	AA-29	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
58	Y-29	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
59	Y-30	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
60	W-30	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
61	S-30	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
62	S-31	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	12'-10 5/8"
63	N-31	HSS 6x6x1/4	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	20'-9 7/8"
64	K-31	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-2	-2'-0"	27'-1 3/8"
65	J-31	HSS 6x6x3/16	3/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-1	-2'-0"	22'-5 1/2"
66	D-11	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-2	-2'-0"	12'-10 5/8"
67	D-22	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-2	-2'-0"	12'-10 5/8"
68	R-14	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" THRU BOLTS	BEAM (DET. H/SF202)		36'-11 3/4"
69	R-20.1	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" THRU BOLTS	BEAM (DET. H/SF202)		36'-11 3/4"
70	K-11.2	HSS 8x8x3/16	1 1/4" x 14" x 1'-2"	(4) 7/8" x 0'-9" LONG (Gr 105)	F-1	-0'-8"	27'-1 3/8"

STEEL COLUMN SCHEDULE - COVERED WALK/COVERED ENTRY

MARK	LOCATION	SIZE	BASEPLATE (txlxw)	ANCHORS	FOOTING
C17	(+/-) AA-14E	STD 4" DIA PIPE	3/4" x 10" x 0'-10"	(4) 3/4" x 0'-9" LONG (Gr 55)	SEE SECTION 2/SF302
C18	(+/-) AA-14F	STD 4" DIA PIPE	3/4" x 10" x 0'-10"	(4) 3/4" x 0'-9" LONG (Gr 55)	SEE SECTION 2/SF302
C19	CC-14E	STD 4" DIA PIPE	3/4" x 10" x 0'-10"	(4) 3/4" x 0'-9" LONG (Gr 55)	SEE SECTION 2/SF302
C20	CC-14F	STD 4" DIA PIPE	3/4" x 10" x 0'-10"	(4) 3/4" x 0'-9" LONG (Gr 55)	SEE SECTION 2/SF302
C21	DD-14E	STD 4" DIA PIPE	3/4" x 10" x 0'-10"	(4) 3/4" x 0'-9" LONG (Gr 55)	SEE SECTION 2/SF302
C22	DD-14F	STD 4" DIA PIPE	3/4" x 10" x 0'-10"	(4) 3/4" x 0'-9" LONG (Gr 55)	SEE SECTION 2/SF302
C23	EE-10C	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-5
C24	EE-14C	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-5
C25	FF-10C	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-5
C26	FF-14C	HSS 6x6x3/8	1 1/4" x 12" x 1'-0"	(4) 3/4" x 0'-9" LONG (Gr 55)	F-5

FINAL SUBMISSION / FULLY SPRINKLERED

REVISIONS	08-22-2013
Revisions:	Date

CONSULTANTS:

CIVIL:
KENNETH HORNE & ASSOCIATES
7201 NORTH 9TH AVENUE, STE. 6
PENSACOLA, FLORIDA 32504
PH: (850) 471-9005
FX: (850) 471-0093

LANDSCAPE ARCHITECT:
CSA GROUP, INC.
6300 PICCADILLY SQUARE DRIVE
MOBILE, ALABAMA 36609
PH: (251) 344-4023
FX: (251) 344-4052

COMM/IOS:
SCHMOT CONSULTING GROUP, INC.
40 S. PALAFOX PLACE, STE. 300
PENSACOLA, FLORIDA 32502
PH: (850) 438-0050
FX: (850) 432-8631

SURVEYORS:
KCI TECHNOLOGIES, INC.
10401 HIGHLAND MANOR DRIVE, SUITE 120
TAMPA, FLORIDA 33610
PH: (813) 740-2300

W.W. BOLTON CERTIFICATE # NO. 56537 STATE OF FLORIDA PROFESSIONAL ENGINEER

ARCHITECT/ENGINEERS:

BES DESIGN/BUILD

BES DESIGN/BUILD, LLC
766 Middle St, Fairhope, AL 36532
Phone: 251.990.5778 Fax:
251.990.3716

Drawing Title: SCHEDULES

Approved: Project Director

Project Title: CONSTRUCT VA OUTPATIENT CLINIC, PANAMA CITY

Location: PANAMA CITY, FLORIDA

Date: APRIL 2013 | Checked: NB | Drawn: NB/KM

Project Number: 520-326

Building Number: -

Drawing Number: SF600 Dwg. 17 of 17

Office of Construction and Facilities Management

Department of Veterans Affairs

VA FORM 08-6231