





Door Schedule - Phase 1										
Door No.	Door				Frame		Glazing Type	Rating	Hdw. Set	Comments
	Width	Width Sec.	Height	Material	Type	Type				
E0001	3'-0"		7'-0"	H.M.	15	H.M.	N/A	1 Hour	25	
H001	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
H002	3'-0"		7'-0"	Wood	8	H.M.	N/A		16	
H003	3'-8"		7'-0"	Wood	2	H.M.	G4		14	
H008.1	3'-0"		7'-0"	Wood	2	H.M.	G4		14	
H008.2	3'-8"		7'-0"	Wood	2	H.M.	G4		14	
H008A	3'-0"		7'-0"	Wood	1	H.M.	N/A		7	
H010	3'-8"		7'-0"	Wood	6	H.M.	N/A	3/4 Hour	23	
H011	3'-0"		7'-0"	Wood	1	H.M.	N/A		22	
H012.1	Pr	7'-0"	7'-0"	Wood	18	H.M.	See Door Legend		21	Smoke Barrier Door
H012A	3'-0"		7'-0"	Wood	1	H.M.	N/A		28	
H012B	4'-0"		7'-0"	Wood	1	H.M.	G4		3	
H012B1.1	3'-0"		7'-0"	Wood	1	H.M.	N/A		6	
H012B1.2	3'-0"		7'-0"	Wood	1	H.M.	N/A		6	
H012C	4'-0"		7'-0"	Wood	1	H.M.	N/A		3	
H012D	3'-0"		7'-0"	Wood	8	H.M.	N/A		3	
H012D1	3'-0"		7'-0"	Wood	1	H.M.	N/A		6	
H012E	3'-0"		7'-0"	Wood	1	H.M.	N/A		12	
H012F	3'-8"		7'-0"	Wood	6	H.M.	N/A	3/4 Hour	23	
H012G	4'-0"	1'-6"	7'-0"	Wood	13	H.M.	N/A		4	
H012H	3'-0"		7'-0"	Wood	8	H.M.	N/A		1	
H012I	3'-0"		7'-0"	Wood	8	H.M.	N/A		1	
H012J	3'-0"		7'-0"	Wood	8	H.M.	N/A		1	
H012K.1	4'-0"		7'-0"	Wood	9	H.M.	G5		22	
H012K.2	3'-0"		7'-0"	Wood	9	H.M.	G5		22	
H012L	3'-0"		7'-0"	Wood	9	H.M.	G5		22	
H012M	4'-0"	1'-6"	7'-0"	Wood	13	H.M.	N/A		2	
H013	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
H014	4'-0"		7'-0"	Wood	6	H.M.	N/A	3/4 Hour	15	
H017.1	3'-0"		7'-0"	Wood	14	H.M.	G7		28	
H017.2	3'-0"		7'-0"	H.M.	15	H.M.	N/A	1 Hour	27	
H017.3	3'-0"		7'-0"	Aluminum	6	Aluminum	N/A		23	By Curtainwall Manufacturer
H018	3'-8"		7'-0"	Wood	6	H.M.	N/A	3/4 Hour	23	
H020.1	3'-8"		7'-0"	Wood	2	H.M.	G4		14	
H020.2	3'-0"		7'-0"	Wood	2	H.M.	G4		14	
H020A	3'-0"		7'-0"	Wood	1	H.M.	N/A		1	
H021.1	Pr	7'-0"	7'-0"	Wood	10	H.M.	N/A		18	
H021.2	3'-0"		7'-0"	H.M.	4	H.M.	N/A		25	Aluminum Door By Storefront Manufacturer
H022.1	3'-8"		7'-0"	Wood	2	H.M.	G4		14	
H022.2	3'-0"		7'-0"	Wood	2	H.M.	N/A		14	
H023.1	7'-0"		6'-11 3/4"	Aluminum	2	Aluminum	N/A		32	By Storefront Manufacturer
H023.2	10'-0"		6'-10 3/4"	Aluminum	2	Aluminum	N/A		30	By Storefront Manufacturer
Grand total: 42										

Door Schedule - Phase 2										
Door No.	Door				Frame		Glazing Type	Rating	Hdw. Set	Comments
	Width	Width Sec.	Height	Material	Type	Type				
E030	3'-0"		7'-0"	Wood	1	H.M.	N/A		10	
E031.1	3'-0"		7'-0"	Wood	1	H.M.	N/A		25	
E031.2	3'-0"		7'-0"	Wood	6	H.M.	N/A	3/4 Hour	11	
E032.1	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
E032.2	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
E033.1	3'-1 1/2"		7'-0"	Wood	1	Aluminum	N/A		9	
E033.2	3'-1 1/2"		7'-0"	Wood	1	Aluminum	N/A		9	
E033.3	3'-1 1/2"		7'-0"	Wood	1	Aluminum	N/A		9	
E033.4	3'-1 1/2"		7'-0"	Wood	1	Aluminum	N/A		9	
E033A	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
E033C1	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
E033C2.1	3'-0"		7'-0"	Wood	3	H.M.	G4		9	
E033C2.2	3'-0"		7'-0"	Wood	3	H.M.	N/A		9	
E033C.1	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
E033C.2	3'-0"		7'-0"	Wood	1	H.M.	N/A		24	
E033C.3	3'-0"		7'-0"	Wood	2	H.M.	G4		8	
E034.1	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
E034.2	3'-0"		7'-0"	Wood	1	H.M.	N/A		9	
E035	3'-0"		7'-0"	Wood	3	H.M.	N/A		9	
E036.1	Pr	7'-4"	7'-0"	Wood	11	H.M.	N/A	3/4 Hour	19	
E036.2	3'-0"		7'-0"	Wood	1	H.M.	N/A		17	
E036.4	3'-0"		7'-0"	Wood	1	H.M.	N/A		8	
E036A	3'-0"		6'-9 1/2"	Aluminum	1	Aluminum	N/A		33	By Storefront Manufacturer
E036B	3'-8"		7'-0"	H.M.	6	H.M.	See Door Legend	3/4 Hour	16	
E038	3'-0"		7'-0"	Wood	1	H.M.	N/A		13	Provide 12"x12" "Y" Blade Louver
E039	3'-0"		7'-0"	Wood	1	H.M.	N/A		13	Provide 12"x12" "Y" Blade Louver
E040	6'-9 1/2"		6'-10 3/4"	Aluminum	25	Aluminum	N/A		30	By Storefront Manufacturer
E040.1	2'-11"		6'-10 3/4"	Aluminum	25	Aluminum	N/A		9	By Storefront Manufacturer
E040.2	9'-9 1/2"		6'-10 3/4"	Aluminum	29	Aluminum	N/A		29	By Storefront Manufacturer
H015	3'-8"		8'-0"	G6	1	H.M.	N/A		31	Frameless Glass Door
H016	3'-0"		7'-0"	Wood	1	H.M.	N/A		5	
Grand total: 31										



General Door Notes:

- No Universal Doors are to be Used. Right and Left Hand Doors Shall Have Appropriate Bevel, for Correct Closing.
- All Doors Shall be Flush - 1 3/4" Thick Unless Noted Otherwise.
- Top & Side Rails Shall be 9" Min. Bottom Rails Shall be 12" Min.
- All Exposed Fasteners are to be VA Approved Tamper Proof with a Countersunk Smooth Head.
- Doors to be 1/2" Undercut Maximum at smoke and labeled doors and 3/4" max. elsewhere.
- View Panels in Non-Rated Doors Shall be 5/16" Min. Laminated Glass.
- View Panels in Rated Doors Shall be 5/16" Min. Laminated Fire Rated Glass Relative to the Rating on Same Door. (Refer to Door Schedule.)
- Smoke Seal Gaskets Shall be Cut into 1/2" Lengths Max. and Shall Form a Continuous Seal Around the Door.
- All New Doors Shall be Prefinished at the Factory. Door Frames Shall be Painted on Site. Refer to Finish Schedule & Provide Sample for Architect's Approval.
- The General Contractor (G.C.) Shall Provide Fire Resistant Wood Backing at all New Door Stop Locations.
- The G.C. Shall Caulk all Joints at Dissimilar Materials, I.E., Wood/Metal, Aluminum/Masonry, GWB/Metal, Etc.
- For Glass, Refer to Spec. Section 08 60 00.
- Contractor to Coordinate Door Hardware, Operation, and Electrical Requirements with Schedule and the Electrical Contractor (EC). The EC Shall Provide and install All Necessary Door Hardware and Associated Wiring.
- ALL doors and frames to have Label Ratings.
- Non-Rated doors to have 3/4" undercut. Refer to Mechanical Drawings for more information.

Revisions:	Date	Architect/Engineer:	Seal:	Drawing Title	Project Title	Date
				Window & Door Details & Schedules	Expand and Renovate Urgent Care Area - 15E at Castle Point	March 22, 2013
				As Noted	Building Number 15	Project No. 620-332
				Issued For Final Contract Documents	Location 100 Route 9D Castle Point, NY 12511	Drawing No. AE-601

FULLY SPRINKLERED