



Fire-Rated Partitions Legend	
	Fire Resistant Rated Walls, 1 Hour
	Fire Resistant Rated Walls, 2 Hour
	Fire Rated, Smoke Barrier Walls, 1 Hour
	Smoke Barrier Walls

**Finish Plan General Notes:**


1. Refer to the Finish Schedule for complete room finish material information.
2. Flooring material transitions shall occur mid-threshold at doorways.
3. Provide transition strip at all locations where two different finishes meet, refer to AI-601 for details. Follow manufacturers recommended installation instructions and procedures.
4. At locations where new floor finish meets an existing floor finish, the contractor shall flash patch or grind the floor as necessary to allow for floor finishes to be flush.
5. Provide new corner guards (CG-#) at all new outside corner wall locations. See finish plans for locations.
6. Floor finish to continue under all counters and mobile furniture & Equipment.



② Basement - Phase I - North Floor Finish Plan  
1/8" = 1'-0"



① Basement - Phase I - South Floor Finish Plan  
1/8" = 1'-0"



FULLY SPRINKLERED

Revisions:	Date

Architect/Engineer:	Seal:
Architecture SERVICE DISABLED VETERAN OWNED SMALL BUSINESS	

Drawing Title
<b>Basement - Phase I - Floor Finish Plans</b>
Scale
<b>As Noted</b>
Issued For
<b>Final Contract Documents</b>

Project Title
<b>Expand and Renovate Urgent Care Area - 15E at Castle Point</b>
Building Number
15
Location
100 Route 9D Castle Point, NY 12511

Date
March 22, 2013
Project No.
620-332
Drawing No.
<b>AI-101</b>