

SCOPE OF WORK

EXTERIOR EGRESS LIGHTING

CONTRACTOR WILL FURNISH MATERIALS, LABOR, TOOLS, TRANSPORTATION AND SUPERVISION TO:

1. UPGRADE EGRESS LIGHTING IN THE FOLLOWING LOCATIONS

a. MOVE LIGHT CIRCUIT FROM NORMAL POWER PANEL TO EMERGENCY POWER PANEL OR CIRCUIT

- i. FRONT ENTRY
- ii. MORGUE
- iii. EMERGENCY ROOM ENTRANCE
- iv. AMBULANCE BAY ENTRANCE
- v. NORTH PARKING LOT LIGHTS

b. REFEED EXISTING EGRESS LIGHT(S) FROM NEAREST EXIT LIGHT CIRCUIT

- i. TRASH DOCK LIGHTS
- ii. SOUTH SMOKE SHACK
- iii. ANIMAL RESEARCH MAIN ENTRANCE

c. INSTALL NEW EGRESS LIGHT AND FEED FROM NEAREST EXIT LIGHT CIRCUIT

- i. DOCTOR PARKING EXIT
- ii. CONFERENCE ROOM EXIT
- iii. ANIMAL RESEARCH SE EXIT
- iv. ANIMAL RESEARCH SOUTH DOCK
- v. ANIMAL RESEARCH NORTH ENTRANCE
- vi. MRI EXIT

d. REFFED PANEL FOR DOCTORS PARKING LOT LIGHTS FROM EMERGENCY PANEL (WORK TO BE ACCOMPLISHED AFTER NORMAL HOURS)

2. CONTRACTOR WILL REMOVE ALL DEBRIS FROM VA PROPERTY.

3. VENDOR IS RESPONSIBLE FOR ALL DAMAGES TO VA PROPERTY.