

JSN	ITEM DESCRIPTION	PURC & INST	Manufacturer - Basis of Design	Model - Basis of Design	Quantity	REMARKS
A1107M	Rail System, Utilities, Gas & Electric, with Bed Bumper	CC	Modular Services Company	Silhouette III Semi-Recessed Model 8510	Total of Fourteen (14): One (1) per PACU Patient Position	Horizontal Rail System to include 2 Oxygen, 2 Medical Air, 3 Vacuum, 6 each 120 VAC Emergency Duplex Receptacles, 3 each Normal Duplex Receptacles, Night Light, 1 Combination Rocker Switch, 1 Low Voltage Momentary Contact Switch-Single Pole, 3 Position, Center Off, Nurse Call and Code Blue Provision, 2 Horizontal Accessory Channels, Bed Bumper Guard- Horizontal 36", 1 Channel Bracket with 1/2" Socket for Post Mounted Accessory, 1 Post Mount Bracket Assembly w/ Welch Allyn Aneroid Manometer # 7670-01, 3 Vacuum Container Slides-Channel Mounted
A1120	Column/ Boom, Service, Prefab, Anesthesia, Ceiling Mounted (Located at Patient Right - Head of Table)	CC	Berchtold	TP-612-C	Total of Two (2) Each: Include One (1) per Operating Room	Located at Head of Table, Patient Right: Powered Articulating, 1 Layer to include 2 - Oxygen, 1 Medical Air, 2 Vacuum, 2 Vacuum Container Slides, 1 N2O, 1 WAGD (Beacon Medaes Gas Outlets), 6 each Emergency Duplex Electrical Outlets, 1 Phone Jack RJ11, Medical Rail on three sides for mounting accessory items, Arm Mounted Patient Exam Light, and 1 shelf for equipment support.
A1120	Column/ Boom, Service, Prefab, Surgical/ Alternate Anesthesia Location, Ceiling Mounted (Located at Patient Left Foot of Table)	CC	Berchtold	TP-632-C	Total of Two (2) Each: Include One (1) per Operating Room	Located at Patient Left Foot, Surgical Equipment Boom/ Alternate Anesthesia Location: Powered Articulating, 3 Layer to include: 2 Oxygen, 1 Medical Air, 1 CO2, 2 Vacuum, 4 Vacuum Container Slides, 1 N2O, 1 WAGD, 1 Nitrogen w/ Control Panel (Beacon Medaes Gas Outlets), 1 each 220 VAC, 30 Amp Electrical Receptacle, 9 each 120 VAC Duplex Emergency Receptacles, 7 double grommated low voltage boxes, 1 quad RJ45 - CAT6, 1 Phone Jack RJ11, Medical Rail on three sides for mounting accessory items, and 3 shelves for equipment support.
A1122	Column/ Boom, Boom, Service, Prefab, Surgical/ Equipment, Ceiling Mounted	CC	Berchtold	TP-632-C	Total of Two (2) Each: Include One (1) per Operating Room	Powered Articulating, 3 Layer to include 1 Oxygen, 2 Vacuum, 4 Vacuum Container Slides, 1 Medical Air, 1 CO2, 1 Nitrogen w/ Control Panel (Beacon Medaes Gas Outlets), 1 each 220 VAC, 30 Amp Electrical Receptacle, 8 each 120 VAC Duplex Emergency Receptacles, 7 double grommated low voltage boxes, 1 Quad RJ45 CAT6, 1 Phone Jack RJ11, Medical Rail on three sides for mounting accessory items, and 3 shelves for equipment support.
A1122Z	Column/ Boom, Service, Prefab, DaVinci Vision, Ceiling Mounted	CC	Berchtold	TP-632	Total of Two (2) Each: Include One (1) per Operating Room	Powered Articulating, 3 Layer to include 1 Oxygen, 1 Medical Air, 1 CO2, 2 Vacuum, 4 Vacuum Container Slides (Beacon Medaes Gas Outlets), 12 Emergency Duplex Receptacles, 7 double grommated low voltage boxes, 1 Quad RJ45 CAT6, Medical Rail on three sides for mounting accessory items, and 3 shelves for equipment support.
A1200	Lift, Patient, Ceiling Mounted	CC	Arjo Huntleigh	Maxi Sky 600	Total of Four (4): Include One (1) per PACU Isolation Room	
A4015	Clock, Elapsed Time, Electric	CC	National Time & Signal	Digital Elapsed Clock/ Timer	Total of Two (2) Each: Include One (1) per Operating Room	

JSN	ITEM DESCRIPTION	PURC & INST	Manufacturer - Basis of Design	Model - Basis of Design	Quantity	REMARKS
A5210	Bracket, Television, Wall Mounted with Adjustable Arm	CC	Peerless	PT 632	Total of One (1) Each: PACU Lounge	
CT050M	Countertop, Stainless Steel, with Open Shelves & Integral Sink	CC	Inter Dyne Systems	As Specified (11.53.43)	Total of Two (2) Each: Include One (1) per Sub- Sterile Room	
M3110	Cabinet, Warming, Freestanding, 2 Heated Compartment, Electric	CC	Steris	Dual Compartment Glass Warming Cabinet, 24" Deep, Freestanding	Total of Three (3) Each: Include One (1) per Sub- Sterile Room and One (1) in PACU Corridor/ Alcove.	
M7485M	Light, Surgical, Ceiling Mounted, Single Light Head with In-Light Camera, and Single Flat Panel Arm	CC	Berchtold	F628 w/ Single Flat Panel Arm	Total of Two (2) Each: Include One (1) per Operating Room	Unit to include HD In-Light Camera. Flat Panel Arm to accommodate 32" HD Video Display.
M7485M	Light, Surgical, Ceiling Mounted, Single Light Head w/ Single Flat Panel Arm	CC	Berchtold	F628 w/ Sngle Flat Panel Arm		Flat Panel Arm to accommodate 32" HD Video Display.
P6980	Sink, Scrub, Stainless Steel, 2 Bay with Knee Valve	CC	Steris	Flexmatic 2 Bay	Total of Two (2) Each: Include One (1) per Sub- Sterile Room	
S0125	Sterilizer, Steam, Vac, Single Door, Cabinet Enclosed, 16x16x26 Chamber	CC	Steris	400 Series	Total of Two (2) Each: Include One (1) per Sub- Sterile Room	