

SECTION 01 51 26
TEMPORARY LIGHTING

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section specifies requirements for temporary lighting.

1.2 TEMPORARY LIGHTING

- A. Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
- B. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
- C. Install lighting for Project identification sign.
- D. Provide the following minimum lighting levels:
1. Corridor and Stairhalls: 1 foot candle.
 2. Unoccupied Work Spaces: 1 foot candle.
 3. Occupied Work Spaces and Storage Spaces: 5 to 10 foot candles.
 4. Work Areas: 30 foot candles.

- - - E N D - - -

Manhattan VAMC Bldg. 1 - 9th Floor Renovations
Manhattan Veteran's Affairs Medical Center
New York, New York

Issued: August 29, 2013
Addendum No. 1

THIS PAGE INTENTIONALLY LEFT BLANK