

**SECTION 09 06 00
SCHEDULE FOR FINISHES**

SECTION 09 06 00-SCHEDULE FOR FINISHES

VAMC: VA Minneapolis Pharmacy

Location: Minneapolis, Minnesota

Project No. and Name: Construct ScriptPro Site Prep 618-12-CSI-200

Submission: Construction Documents

Date: July 17, 2013

**INSTRUCTIONS FOR PREPARATION OF
SECTION 09 06 00-SCHEDULE FOR FINISHES**

**SECTION 09 06 00
SCHEDULE FOR FINISHES**

PART I - GENERAL

1.1 DESCRIPTION

This section contains a coordinated system in which requirements for materials specified in other sections shown are identified by abbreviated material names and finish codes in the room finish schedule or shown for other locations.

1.2 MANUFACTURERS

Manufacturer's trade names and numbers used herein are only to identify colors, finishes, textures and patterns. Products of other manufacturer's equivalent to colors, finishes, textures and patterns of manufacturers listed that meet requirements of technical specifications will be acceptable upon approval in writing by contracting officer for finish requirements.

1.3 SUBMITALS

Submit in accordance with SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES—provide quadruplicate samples for color approval of materials and finishes specified in this section.

PART 2- PRODUCTS

2.1 DIVISION 06 WOOD, PLASTICS, AND COMPOSITES

A. SECTION 06 20 00, FINISH CARPENTRY

1. WOOD PANELING	Color	Manufacturer	Pattern / Finish
MDF-1	Paint with HPC-1	Interlam, Inc.	SOT-403 / Factory Primed and field painted with HPC-1

2. CHAIR RAIL	Color	Manufacturer	Profile / Finish
CR-1	Glacier White	Corian	4 inches high by 1/4 inch thick; Matte finish

2.2 DIVISION 08 - OPENINGS

A. SECTION 08 11 13, HOLLOW METAL DOORS AND FRAMES

Paint both sides of door and frames same color including ferrous metal and hardware attached to door	
Component	Color of Paint Type and Gloss
Door	PT-2
Frame	PT-2

B. SECTION 08 14 00, WOOD DOORS

Component	Finish/Color
Doors	WD-1: Red Oak, Plain Sliced to match existing; clear finish

C. SECTION 08 71 00, BUILDERS HARDWARE

Item	Material	Finish
Hinges	Satin Stainless Steel	BHMA 630
Door Closers	Stainless Steel	BHMA 689
Closer/ Holder	Stainless Steel	BHMA 689
Door Holders	Satin Chromium Plated	BHMA 626
Lock/ Latches	Satin Chromium Plated	BHMA 626
Key Cabinet	Steel	Field Painted
Armor Plates	Satin Stainless Steel	BHMA 630
Door Edging	Satin Stainless Steel	BHMA 630
Exit Device	Satin Stainless Steel	BHMA 630
Flush Bolts	Satin Chromium Plated	BHMA 626
Door Pulls	Satin Stainless Steel	BHMA 630
Push Plates	Satin Stainless Steel	BHMA 630
Combination Push Pull Plate	Satin Stainless Steel	BHMA 630
Coordinators	Steel	Powder coat to match frame

D. SECTION 08 80 00, GLAZING

Glazing Type	Manufacturer	Mfg. Color Name/No.
DGL-1	Skyline Design	"Organics - Brambles"; 3/8 inch thick

2.3 DIVISION 09 - FINISHES

A. SECTION 09 51 00, ACOUSTICAL CEILINGS

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
	Exposed Suspension System (use with ACT-1)	White - 2'x4'x15/16"	Chicago Metallic	211-209, 229-1420-01H, or approved equal.
ACT-1	Acoustical Ceiling Panel	White - 2'x4'x5/8"	Armstrong	#755B Fissured
	Exposed Suspension System (use with ACT-2)	2'x2'x9/16"	USG	Centricitee
ACT-2	Acoustical Ceiling Panel	White - 2'x2'x3/4"	USG	Mars ClimaPlus Ceilings NO. 86985

B. SECTION 09 65 13, RESILIENT BASE

Finish Code	Item	Height	Manufacturer	Mfg Name/No.
RB-1	Rubber Base (RB)	4"	Johnsonite	49 Beige WB

C. SECTION 09 65 19, RESILIENT TILE FLOORING

Finish Code	Item	Size	Manufacturer	Mfg Name/No.
VCT-1	Luxury Vinyl Tile	24"24"x1/8"	Gerflor	Creation Mineral 0524 Alzamora

D. SECTION 09 68 00, CARPET (CP)

1. SECTION 09 68 00, CARPET EDGE STRIP				
Finish Code	Material	Manufacturer	Mfg. Color Name/No.	
TS-1	Vinyl Transition Strip	Johnsonite	Slim Line Transition "SLT-XX-A - 29 Moon Rock" (1/4"-1/8")	

E. SECTION 09 68 00, CARPET MODULES (CFT)

Finish Code	Size	Pattern direction	Manufacturer	Mfg. Color Name/No.
CPT-1	Use Owner's Attic Stock	Match existing	Shaw Contract Group	Kinetic Tile 59359 "Black to Business - 58505"
CPT-2	24"x24"	Brick Ashlar	The Mohawk Group	Step in Style GT066 / MM014 "518 Blarney Stone"

F. SECTION 09 82 00, MICRO-PERFORATED ACOUSTICAL WOOD PANELS (SCS)

Finish Code	Component	Color Pattern	Manufacturer	Mfg Name/No.
SCS-1	Directly Nail into Furring	Micro (0.5mm), Red Oak, Clear lacquer	RPG Diffusor Systems, Inc.	Topperfo

G. SECTION 09 91 00, PAINT AND COATINGS

1. MPI Gloss and Sheen Standards

		Gloss @60	Sheen @85
Gloss Level 1	a traditional matte finish-flat	max 5 units, and	max 10 units
Gloss Level 2	a high side sheen flat-"a velvet-like" finish	max 10 units, and	10-35 units
Gloss Level 3	a traditional "egg-shell like" finish	10-25 units, and	10-35 units
Gloss Level 4	a "satin-like" finish	20-35 units, and	min. 35 units

Paint code	Gloss	Manufacturer	Mfg. Color Name/No.
PT-1	Flat	Sherwin Williams	SW 7006 Extra White
PT-2	Eggshell	Sherwin Williams	Blk: 24/32oz. DGold: 1- 11/32oz. Maroon 7/32oz. White 1-4/32oz.
PT-3	Eggshell	Sherwin Williams	Y3 Deep Gold: 24/32 and 1/64 oz. B1 Black: 6/32 oz. R4 New Red: 7/32 and 1/128 oz.
PT-4	Eggshell	Sherwin Williams	SW 6423 Rye Grass
HPC-1	Satin	Scuffmaster	Smooth Pearl SP9252 custom color to match SW 7006 "Extra White"

H. SECTION 09 72 16, VINYL COATED FABRIC WALLCOVERING (W)

Finish Code	Manufacturer	Mfg. Color Name/No.
WC-1	Wolf Gordon	G 7835271 Seres Smoke, 52"
WC-2	Wolf Gordon	G 8514645 Seres Raw Silk, 52"

I. SECTION 09 84 33, ACCOUSTICAL WALL PANELLING (AWF)

Finish Code	Manufacturer	Mfg. Color Name/No.
FWP-1	Snap-Tex	Maharam Tek-Wall 398650 010 Foil; 1/2" Square Track Profile

2.4 DIVISION 10 - SPECIALTIES

A. SECTION 10 26 00, WALL GUARDS AND CORNER GUARDS

Item	Material	Manufacturer	Mfg. Color Name/No.
CG-1 - Corner Guards, 90-degree (FOH)	Satin Stainless Steel	InPro	Surface Mount Stainless Steel Corner Guard - 1-1/2" wings
CG-2 - Corner Guards, 90-degree (BOH)	Vinyl	InPro	Surface Mount, 2-Piece, Vinyl Corner Guards - 2" wings; Color: Wood Drift
CG-3 - Corner Guards, End-of-wall (FOH)	Satin Stainless Steel	InPro	Surface Mount Stainless Steel Wall Protectors - 1-1/2" wings; full height.
HR-1 - Handrails	Vinyl	InPro	800 Handrail; Color: Wood Drift
Door Kick Plates	Vinyl acrylic or polyvinyl chloride resilient material, minimum 1.5 mm (0.060-inch) thick	InPro or Construction Specialties	InPro's "Beige 0117" or Construction Specialties' Acrovyn "104 Beige"

B. SECTION 10 44 13, FIRE EXTINGUISHER CABINETS

Component	Material	Finish
Recessed FE Cabinet	Steel	PT-1

C. SECTION 12 36 00, COUNTERTOPS AND ACCESSORIES

Type	Finish/Color
QTZ-1: Quartz	Cambria "White Cliff Desert Collection", Polished; thickness varies as indicated on Drawings.

PART III EXECUTION

3.1 FINISH SCHEDULES & MISCELLANEOUS ABBREVIATIONS

Refer to Drawings.

--- E N D---