

### KEY NOTES


- |  |   |
|--|---|
| <ul style="list-style-type: none"> <li>① DEMOFILL IN STAINLESS STEEL TAMBOR WINDOW</li> <li>② INSTALL NEW STORE FRONT DOORS</li> <li>③ INSTALL PORCELAIN TILE ON ELEVATOR WALL AND COLUMNS TO MATCH 1ST FLOOR</li> <li>④ INSTALL WALL SCONCES AND ADD WALL WASH LIGHTING</li> <li>⑤ REPLACE CEILING TILE AND GRID TO MATCH BUILDING STANDARD</li> <li>⑥ REPLACE 2X4 CEILING LIGHTS TO MATCH BUILDING STANDARD</li> <li>⑦ INSTALL CONTROL JOINT AT EVERY CROSS CORRIDOR AND WHERE CRACK IS EVIDENT APPROX. 10</li> <li>⑧ REPLACE/REFURBISH FLOOR EXPANSION JOINTS AS NEEDED APPROX 7</li> <li>⑨ INSTALL SOLID VINYL FLOORING. FINISH &amp; PATTERN TBD WITH 4" JOHNSONITE MILLWORK BASE</li> <li>⑩ INSTALL ARMOUR PLATE ON EXISTING DOOR</li> <li>⑪ GRIND EXISTING FLOOR, SHOT BLAST, REFINISH CONCRETE WITH SLIP RESISTANCE SURFACE I.E. TNE MEC</li> <li>⑫ REMOVE CORRIDOR WALLS AS SHOWN/INSTALL CURVED SOFFIT/CAN LIGHTS/ CLERK WINDOW WITH TRANSACTION COUNTER/ WRAP COLUMNS WITH DW/PCG/SCONCES. RELOCATE AUTOMATIC DOOR OPENER</li> <li>⑬ ENCASE SPRINKLER FIRE RISER PIPE AS COLUMN WITH ACCESS DOOR</li> <li>⑭ DEMO WALL/DOOR. INSTALL STORE FRONT ASSEMBLY AND AUTOMATIC DOOR WITH HEADER/ WRAPPED COLUMNS WITH DW/PCG/SCONCES</li> </ul> | <ul style="list-style-type: none"> <li>⑮ DEMO WALL/DOOR. RELOCATE LIGHT SWITCH AND PHONE OUTLET/ADD SOFFIT</li> <li>⑯ ADD "EXIT" SIGN AT DOOR</li> <li>⑰ PROVIDE AND INSTALL CUSTOM DIGITAL WALLCOVERING "1 CARE" MURAL</li> <li>⑱ REPAIR DIMPLES IN WALL FROM OLD FASTNERS</li> <li>⑲ ADD KICK PLATE TO EXISTING DOORS</li> <li>⑳ ADD WOOD PANELIZED SYSTEM W/EXTRUDED ALUMINUM REVEALS</li> <li>㉑ REPLACE DOOR TO MATCH BUILDING STANDARD</li> <li>㉒ INSTALL NEW CEILING/DIFFUSER/2 ADDITIONAL CEILING LIGHTS TO MATCH BUILDING STANDARD</li> <li>㉓ MESH/PARGE BLOCK. BUILD OUT TO ENCASE EXPOSED PIPE</li> <li>㉔ WRAP COLUMNS WITH HIGH IMPACT WALL PANELS AND CORNER GUARDS</li> <li>㉕ MESH/PARGE BLOCK WALL/FINISH FOR PAINT</li> <li>㉖ REMOVE PIPE/INSTALL 84" FR STEEL DOOR WITH STAINLESS STEEL EDGE PROTECTION</li> <li>㉗ REFINISH EXISTING DOOR &amp; REPLACE HARDWARE</li> <li>㉘ REPLACE DOOR AND HARDWARE WITH STEEL FIRE RATED DOOR</li> <li>㉙ REPLACE DRINKING FOUNTAIN WITH LOW PROFILE FOUNTAIN</li> <li>㉚ INSTALL HALF WALL WITH ACRYLIC PANEL (3-FORM) PANEL ABOVE</li> </ul> |
|--|---|

BUILDING 3 – FIRST FLOOR

Revisions	Date



Tennessee Valley Healthcare System



Project Title	Halls and Walls Ph 5
Project No.	626A4-11-102
Drawing No.	
Author	Jackson
Checked By	
Scale	

Date	2/27/13
Project No.	626A4-11-102
Drawing No.	
Author	Jackson
Checked By	
Scale	

Department of Veterans Affairs