KEY NOTES

FINISH KEYNOTES

1. REMOVE WALL/ DOOR SO WAITING IS COMPLETELY OPEN TO CORRIDOR :ADD1' X 2' SOFFIT IN WAITING ENTRY
2. OPEN UP RECEPTION WINDOW, REPLACE LAMINATE TRANSACTION TOP ADD WRITING SURFACE AND SMALL PENDANT; SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
3. ADD BULK HEAD IN CORRIDOR
4. REMOVE WOOD WAINSCOTTING: PREP WALLS AND INSTALL HR2 & SC1 BELOW HANDRAIL
5. DEMO WALL AND RELOCATE RECEPTION DESK
6. DEMO RECEPTION DESK AND INSTALL NEW CASEWORK W/SOFFIT/ RECESSED NICHE/ LIGHTING ABOVE: SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
7. INSTALL NEW CASEWORK ; TIE INVADO ADDITIONAL SOFFITS;ADD PENDANT LIGHTING AND CANS: SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
8. REPLACE CEILING TILE WITH GYP.
9. INSTALL FLOOR TO CEILING DWP1: SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
10. FUR OUT COLOMNS AND INSTALL SC1: SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
11. REPLACE CANS WITH DECORATIVE PENDANTS AND UPDATE LIGHT COVE: SEE FINISH LEGEND FOR EXAMPLES AND SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
12. INSTALL WALL SCONCES
13. PAINT SOFFITS
14. INSTALL VWP2 AT 36" A.F.F; ON ALL WALLS TYPICAL
15. STRIP WALLCOVERING, PAINT COLUMNS AND INSTALL CG1
16. INSTALL WALL PROTECTION ON ROUND COLS.
17. INSTALL BUILT IN PLANTER AND CUSTOM DIGITAL WALLCOVERING IN ALCOVE ABOVE PLANTER; SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
18. INSTALL 10 EXTERIOR SELF IRRIGATING PLANTERS: SEE FINISH LISTING FOR EXAMPLE
19. RELOCATE COFFEE BAR TO CANTEEN AREA AND PROVIDE UTILITIES.NEW FINSHES,SOFFIT, AND ACCENT LIGHTING
20. INSTALL WHEELCHAIR ALCOVE AND WRAP W/ VWP2; SEE SHEET 6 FOR KEYNOTE CONCEPT DETAIL
21. INSTALL DWP BELOW CHAIR RAIL AND TACKABLE DISPLAY BOARD ABOVE CHAIR RAILS ON ALL PERIMETER WALLS

FINISH LEGEND

AP ACRYLIC PANEL
CG CORNER GUARD
DWP FRAMED DECORATIVE WALL PANEL
ETR EXISTING TO REMAIN
L LAMINATE
LVT LUXURY VINYL TILE
ME MATCH EXISTING
P PAINT
RB RUBBER BASE
SC STONE CLADDING
SV SHEET VINYL
SS SOLID SURFACE
T TILE
VWP VINYL WALL PROTECTION
VWC VINYL WALLCOVERING
WT WALL TILE

WALLS

P1 SHERWIN WILLIAMS: SW6106 KILIM BEIGE: EGGSHELL
P2 ALL DOORFRAMES:SHERWIN WILLIAMS: SW7038: TONY TAUPE: SEMI-GLOSS
P3 SHERWIN WILLIAMS: SW7039 VIRTUAL TAUPE: EGGSHELL
P4 SHERWIN WILLIAMS: SW7694 DROMENDARY CAMEL: EGSH
P5 SHERWIN WILLIAMS: SW7726 LEMON VERBENA: EGGSHELL
P6 SHERWIN WILLIAMS: SW7705 WHEAT PENNY: EGGSHELL
P7 SHERWIN WILLIAMS: SW6235 FOGGY DAY: EGGSHELL

DWP1 WILSONART LAMINATE - 7919K-78 AMBER CHERRY WITH NICKEL REVEALS

SC1 REALSTONE SYSTEMS: SHADOW STONE: TERRACOTTA

VWC1 VERSA: CITY BLOCKS: ASL-128-899
VWC2 VERSA: SEQUENCE: ASL-111561 DOWLAS
VWC3 VERSA: SEQUENCE: ASL-111535 IRONSTONE
VWC4 VERSA: SEQUENCE: ASL-111333 BYZANTINE
VWC5 VERSA: SEQUENCE: ASL-111387 MIKADO
VWC6 VERSA: SEQUENCE: ASL-111290 BANYAN
VWC7 EYKON: CUSTOM DIGITAL WALLCOVERING

WT1 STONEPEAK:LIMESTONE COLLECTION: HONEY:SIZE: 12"X 24"

WALL PROTECTION

BG1/CG1/HR1/WP1 BUILDING STD: PAWLING TAN
CG2 ACROVYN:WALL PROTECTION: 209 SLATE
HR2 ACROVYN: HRWS-6C: STAINLESS BRACKET: 386 HONDURAS MAH.
VWP2 ACROVYN: WALL PROECTION: 386 HONDURAS MAHOGANY

BASE

RB1 JOHNSNITE: 4" RUBBERBASE: EITHER ORE
TB1 STONEPEAK : 6"X 12" TILE BASE: ;LIMESTONE :HONEY

FLOORS

LVT1 FIELD LVT - SOLARBRITE CLASSIC COLLECTION: SB804S SIZE:12"X24"; 3.2 MIL
LVT2 ACCENT LVT - SOLARBRITE PLANK: CHAPEL HILL LIGHT CHERRY SIZE:4" WIDE; 3.2 MIL
LVT3 ACCENT LVT - ARMSTRONG NATURAL CREATIONS MYSTIX: TP707: KINDERLLOY BRONZE PATINA:SIZE: 12"X24"; 3.2 MIL
LVT4 ACCENT LVT - ARMSTRONG NATURAL CREATIONS ARBOR ART: TP652: AMERICANA WALNUT SIENNA PATINA:SIZE: 4"X36"; 3.2 MIL
CP1 CARPET - TANDUS CHANGE:03747 COLOR: TBD
T1 STONEPEAK: LIMESTONE COLLECTION: PORCELAIN TILE; COLOR: HONEY SIZE:12"X24"
T2 STONEPEAK: LIMESTONE COLLECTION: PORCELAIN TILE; COLOR: HONEY SIZE:12"X12"
T3 STONEPEAK: LIMESTONE COLLECTION: PORCELAIN TILE; COLOR: HONEY SIZE:6"X24"
T4 STONEPEAK: SLATE COLLECTION: PORCELAIN TILE; COLOR: EVERGLADES SIZE:12"X24"
T5 STONEPEAK: SLATE COLLECTION: PORCELAIN TILE; COLOR: EVERGLADES SIZE:6"X6"

LAMINATE/SOLID SURFACE

L1 VERTICAL: WILSONART LAMINATE - 7919K-78 AMBER CHERRY
L2 VERTICAL: WILSONART LAMINATE - COLUMBIAN WALNUT: 7943K
SS1 CORAIN - FOSSIL

CEILING

A1 BUILDING STANDARD: 2x2 ACOUSTICAL TILE: USG
A2 2x2 ACOUSTICAL TILE: TEGULAR EDGE

LIGHTING

LT1 INDIRECT 2X4 FIXTURE -LITHONIA:AVANTE,2AV : T5 LAMP:3 LAMPS GLR; INTERNAL FALST BLOSE FUSE; ADP ACYRLIC DIFFUSER
LT2 CONCEPT WALL SCONCE -VISA LIGHTING: WENGE
LT3 LARGE CONCEPT PENDANT -MANNING LIGHTING: DISCOH PENDANT IN ALUMINUM AND STAINLESS
LT4 SMALL CONCEPT PENDANT -MANNING LIGHTING: DISCOH PENDANT IN ALUMINUM AND STAINLESS

PLANTER

3' and 4' DIAMETER SELF IRRIGATING PLANTER: Tournesol Siteworks: CWF-3410 Low and High Bowl insert and planter

FINISH SCHEDULE

NO.	CORRIDOR NAME	WALL	BASE	FLOORS	CEILING	COMMENTS
A-109	BLOOD DRAW WAITING	P1,2 / VWC1, 2	RB1	LVT1,2,3,4	ETR	
A-118	WAITING	P1,2 / VWC2	RB1	LVT1,2,3	ETR	
A-119	WAITING	P1,2 / VWC1, 2	RB1	LVT1,2,3,4	ETR	PAINT EXISTING SOFFITS
A-126	WAITING	P1,2 / VWC2	RB1	LVT1,2,3	ETR	PAINT EXISTING SOFFITS
C1-1B	MAIN ELEVATOR	P1,2,3/ VWC1, 2	RB1	T-1,2,3,4	A1,A2	SEE KEYNOTES; PAINT SOFFITS
C1-2	COURTYARD CORRIDOR	P1,2,3/ VWC1, 2,3	RB1	LVT1,2,3	ETR	
C1-4	GARDEN ELEVATOR	P1,4/VWC1, 2/DWP1	RB1	LVT1,2,3,4	ETR	
C1-6	CORRIDOR	P1/VWC1, 2	RB1	LVT1,2,3	ETR	
C1-6B	CORRIDOR	P1/VWC1, 2	RB1	LVT1,2,3	ETR	
C1-7	COURTYARD CORRIDOR	P2,3/VWC3	RB1	LVT-1,2,3,4	A1	GRID TO REMAIN
C1-8	CORRIDOR	P1/VWC1,2,4	RB1	LVT1,2,3	ETR	
C1-8A	CORRIDOR	P1/VWC1,3	RB1	LVT1,2,3	ETR	PATCH AND MATCH EXISTING WALL FINISHES
C1-8B	CORRIDOR	P1/VWC1,3	RB1	LVT1,2,3,4	ETR	PATCH AND MATCH EXISTING WALL FINISHES
C1-9	BACK CORRIDOR	P2,4,5/VWP1	RB1	LVT1,2,3	ETR	WALL PROTECTION ETR; WRAP COLS. W/VWP1
C1-10	BACK CORRIDOR	P2,4,5/VWP1	RB1	LVT1,2,3	ETR	WALL PROTECTION ETR; WRAP COLS. W/VWP1
C1-11	BACK CORRIDOR	P2,4,5/VWP1	RB1	LVT1,2,3	ETR	WALL PROTECTION ETR; WRAP COLS. W/VWP1
C1-12	SERVICE ELEVATOR	P2,4,5/VWP1	RB1	LVT1,2,3	ETR	WALL PROTECTION ETR; WRAP COLS. W/VWP1
C1-12A	CORRIDOR	P1,2/VWC1,4	RB1	LVT1,2,3	ETR	
C1-15D	CENTRAL ELEVATOR	VWC-4	ETR	ETR	ETR	INSTALL WALLCOVERING BETWEEN COLS.
C1-19	CORRIDOR	VWC1, DWP1	RB1	LVT1,2,3	ETR	SEE GENERAL NOTES
C1-23	CORRIDOR	P1, VWC1, 2	RB1	LVT1,2,3	ETR	
C1-23A	CORRIDOR	P1, VWC1, 2	RB1	LVT1,2,3	ETR	
C1-25	CORRIDOR	ETR	RB1	LVT1,2,3	ETR	
D-113	ED WAITING	ETR	RB1	ETR	ETR	INSTALL VWP 2 ON PERIMTER WALLS
D-114	FIRM A WAITING	P1, VWC1, 2	RB1	LVT1,2,3	ETR	INSTALL VWP2 UNDER DESK; PAINT SOFFIT
D-116	SPEC. CARE WAITING	ETR	RB1	LVT1,2,3	ETR	PAINT SOFFIT
1F-C1	TOWER ELEVATOR	P1/VWC1, 2/DWP1	RB1	ETR	ETR	SEE KEYNOTES
1F-C2	TOWER ELEVATOR	P1,2/VWC1,4	RB1	ETR	ETR	SEE KEYNOTES
1F-C3	CORRIDOR	P1,2/VWC1,4	RB1	LVT1,2,3	ETR	SEE KEYNOTES
G-110	LOBBY WAITING	P4/VWC1,7/SC1/DWP1	RB1	T1,2,3,4	A1,A2	SEE KEYNOTES: PAINT SOFFITS
G-121	AUDIOLOGY WAITING	P2,4,5/VWP1	RB1	LVT1,2	A1	SEE KEYNOTES
G-124	DENTAL WAITING	P2,4,5/VWP1	RB1	LVT1,2	A1	SEE KEYNOTES
B-104	MULTI-PURPOSE RM	P2,4,5/VWP1/DWP	RB1	LVT1,2	ETR	(TACKABLE SURFACE) ABOVE CHR RAIL

X X
*DENOTES FLOORING TRANSITIONS

*DENOTES DEMO



Revisions	Date

TVHS NASHVILLE CAMPUS

Tennessee Valley Healthcare System

TVHS MURFREESBORO CAMPUS

N E S W

SCALE: 1/8"=1'-0"

Project Title : Halls and Walls Ph 5
NA Part A New Construction & Finish Plan
Approved By :
Approved By :
Location : NA
Building Number : 1
Floor:
Checked By : SS
Drawn By : MW

Date : 3-20-13
Project No. : 626-13-101
DRAWING NO. Dwg. 3 Of 5

Department of Veterans Affairs