

1. Are there any safety certifications required for the contractors crew doing the install and removal of equipment? **Yes, each employee needs to have successfully completed a 10hr Occupational Safety and Health Training Course.**
2. Are the contractors installation personnel doing final connections to the facilities utilities required to be licensed electricians and plumbers with the state of Michigan? **Yes.**
3. Will any infectious disease control measures need to be followed? If so who will be responsible, and what step will need to be followed. **Yes. (See Attached Infection Control Construction Permit).**
4. Are we to assume that all existing utilities are to be adequate to connect the new equipment to? (Air, Water, Drain, Steam, Condensate). **Yes.**
5. Will the existing air piping be extended to the dirty side of the washer by the owner? **No, this needs to be addressed by the contractor.**
6. Will the steam condensate need to be returned with a lift station to the existing condensate system? **Yes.**
7. Clarification on question 5 on amendment 2, will the contractor be expected to epoxy the entire floor space or just the area where new concrete work is performed? **Epoxy the entire floor.**
8. Will there be a space available adjacent to building 31 for a dumpster for disposal of non-recyclable crating materials and waste from required renovation. Who will be responsible for providing the dumpster? **Yes, space will be provided adjacent to Building 31. The contractor is responsible for providing the dumpster.**
9. Regarding temporary barriers, Are there more details regarding the barrier, such as materials of construction, soundproofing, dust control, etc.? **Yes. (See Attached Infection Control Construction Permit). Normally, temporary dust barriers and HEPA equipped air filtration units will be required during construction/equipment installation work.**