


PLANTING NOTES

1. PLANT MATERIAL QUANTITIES SHOWN ON DRAWINGS ARE INFORMATIONAL ONLY. THE CONTRACTOR IS RESPONSIBLE FOR ALL PLANT MATERIAL REQUIRED AS INDICATED IN THE DRAWINGS.
2. ALL PLANT MATERIALS SHALL COMPLY WITH FORM AND CHARACTERISTIC REQUIREMENTS AS SPECIFIED. ALL PLANT MATERIAL WILL COMPLY WITH ANSI Z60.1 "STANDARD FOR NURSERY STOCK" - LATEST EDITION.
3. IMMEDIATELY AFTER AWARD OF CONTRACT, THE CONTRACTOR SHALL NOTIFY THE CONTRACTING OFFICER'S REPRESENTATIVE (COR) IF SPECIFIED PLANT MATERIAL IS NOT AVAILABLE FROM COMMERCIAL NURSERIES. IN CASE A PLANT IS NOT AVAILABLE, THE COR WILL PROVIDE ALTERNATE PLANT MATERIAL SELECTIONS.
4. EXCAVATED PLANT PITS SHALL HAVE POSITIVE DRAINAGE. PLANT PITS WHEN FULLY FLOODED WITH WATER SHALL DRAIN WITHIN 2 HOURS OF FILLING. THE CONTRACTOR SHALL ENSURE ALL PLANT PITS HAVE POSITIVE DRAINAGE.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR / REPLACEMENT OF DAMAGED UTILITIES, TO THE SATISFACTION OF THE OWNER OR GOVERNING AGENCY AND AT NO EXTRA COST TO THE OWNER.
6. THE CONTRACTOR IS RESPONSIBLE FOR SOIL EROSION CONTROL MEASURES THAT MAY BE REQUIRED THROUGHOUT THE DURATION OF THE CONTRACT PERIOD. SEE EROSION CONTROL PLANS.
7. TREE LOCATIONS MAY REQUIRE ADJUSTING IN FIELD TO ACCOMMODATE SPRINKLERS AND UTILITY STRUCTURES.
8. REFER TO SPECIFICATIONS FOR BACK FILL FOR TREES.
9. ALL PLANTING INSTALLATION INSTRUCTIONS THAT REQUIRE FERTILIZATION AND SOIL AMENDMENTS SHALL FOLLOW THE SOIL ANALYSIS RECOMMENDATIONS IN THE SOILS REPORT AND SPECIFICATIONS.
10. APPLY A PRE-EMERGENT HERBICIDE AS APPROVED FOR USE IN THE STATE OF LOUISIANA TO ALL PLANTING AREAS IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDED RATES.
11. THE COR SHALL BE NOTIFIED AT THE COMPLETION OF INSTALLATION FOR A GENERAL LANDSCAPE REVIEW. THE COR SHALL REVIEW THE INSTALLATION FOR CONFORMANCE TO PLANS AND SPECIFICATIONS.
12. ALL LANDSCAPE AREAS SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL FINAL ACCEPTANCE. REFER TO SPECIFICATIONS FOR FOLLOW UP MAINTENANCE AMENDMENTS AND FERTILIZERS.
13. LONG TERM MAINTENANCE, EQUIPMENT REPLACEMENT AND/OR REPAIRS, AND IRRIGATION SCHEDULES SHALL FOLLOW GUIDELINES ESTABLISHED BY THE PLANS AND SPECIFICATIONS.

SITE LEGEND





- LIMIT OF CONSTRUCTION
- LIMIT OF CONSTRUCTION - ADD-ALTERNATE #1



E1 TREE PLANTING


NOT TO SCALE

PLANT SCHEDULE - BASE

TREES	CODE	BOTANICAL NAME	COMMON NAME	SIZE	MATURE HT/SP	NOTES	PLANTING ZONE	QTY	
	CR	CERCIS CANADENSIS	EASTERN REDBUD	15 GAL	25'-35'/25'-35'	STANDARD	B,C	3	
	QV	QUERCUS VIRGINIANA	SOUTHERN LIVE OAK	24"BOX	40'-80'/40'-80'		B,C,F	2	
GROUND COVERS	CODE	BOTANICAL NAME	COMMON NAME	CONT	MATURE HT/SPD	NOTES	FIELD4	SPACING	QTY
	BM	GROUND COVER	BARK MULCH	--	3" DEPTH				4,812 SF
	HS	HYDROSEED	REFER TO SPECIFICATION	SEED					1,362 SF
	TS	TURF-SOD	CELEBRATION BERMUDAGRASS	SOD					30,736 SF

PLANT SCHEDULE - ADD ALTERNATE #1

TREES		CODE	BOTANICAL NAME	COMMON NAME	SIZE	MATURE HT/SP	NOTES	PLANTING ZONE	QTY	
	LT	LIRIODENDRON TULIPIFERA	TULIP TREE	15 GAL	60'-80'/40'			B	2	
	NW	NYSSA SYLVATICA 'WILDFIRE'	BLACK GUM	15 GAL	60'/25'	FRUITLESS (MALE)		B,C	3	
	QV	QUERCUS VIRGINIANA	SOUTHERN LIVE OAK	24"BOX	40'-80'/40'-80'			B,C,F	1	
GROUND COVERS		CODE	BOTANICAL NAME	COMMON NAME	CONT	MATURE HT/SPD	NOTES	FIELD4	SPACING	QTY
	BM	GROUND COVER	BARK MULCH	--	3" DEPTH					7,875 SF
	TS	TURF-SOD	CELEBRATION BERMUDAGRASS	SOD						9,384 SF



CONSTRUCTION DOCUMENTS

<div>Revisions</div> <table><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr></table>																						<div>DATE OF CALIFORNIA</div> <div>NO. 4639</div> <div>SIGNATURE</div> <div>DATE</div>	<div>JACOBS</div> <div>1050 20TH ST, STE 200</div> <div>SACRAMENTO, CA 95811</div> <div>PHONE (916) 929-3323 FAX (916) 929-1772</div>	<div>Subconsultant List</div> <table><tr><td>AQUA ENGINEERING, INC.</td><td>4803 INNOVATION DRIVE, FORT COLLINS, CO 80525 (970) 229-9668</td></tr><tr><td>THE SIERRA WEST GROUP, LLC</td><td>9700 BUSINESS PARK DRIVE, SUITE 102, SACRAMENTO, CA 95827 (916) 925-4000</td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr><tr><td> </td><td> </td></tr></table>	AQUA ENGINEERING, INC.	4803 INNOVATION DRIVE, FORT COLLINS, CO 80525 (970) 229-9668	THE SIERRA WEST GROUP, LLC	9700 BUSINESS PARK DRIVE, SUITE 102, SACRAMENTO, CA 95827 (916) 925-4000													<div>LOUISIANA NATIONAL CEMETERY</div> <div>ADMINISTRATION</div>	<div>Sheet Title</div> <div>PLANTING PLAN, SCHEDULE & DETAILS</div> <div>Approved: Director, Office of Construction Management</div> <div>Approved: Director, Project Management Service</div>	<div>Project Title</div> <div>LOUISIANA NATIONAL CEMETERY</div> <div>GRAVESITE EXPANSION PHASE 1D</div> <div>Building Number</div> <div>Checked</div> <div>WMR</div> <div>Drawn</div> <div>RJM</div> <div>Location</div> <div>LOUISIANA NATIONAL CEMETERY</div> <div>ZACHARY, LOUISIANA</div>	<div>Date:</div> <div>AUGUST 5, 2013</div> <div>Project No.</div> <div>870CM3023D</div> <div>Sheet Reference</div> <div>L-600</div> <div>SH. 16 OF 19</div>
AQUA ENGINEERING, INC.	4803 INNOVATION DRIVE, FORT COLLINS, CO 80525 (970) 229-9668																																											
THE SIERRA WEST GROUP, LLC	9700 BUSINESS PARK DRIVE, SUITE 102, SACRAMENTO, CA 95827 (916) 925-4000																																											